

# Technical Memorandum

|         |  |             |          |
|---------|--|-------------|----------|
| To      | North Kent 1 LP  | Page        | 1        |
| CC      | Mark Van der Woerd (AECOM), Jody Law (Pattern), Joshua Vaidhyan (Samsung)  |             |          |
| Subject | <b>North Kent Wind 1 (Chatham-Kent, ON)</b><br><b>Well Water Impact Complaint Investigation</b><br>[REDACTED] - PIN 007420039, [REDACTED]<br>(Dresden, ON) |             |          |
| From    | Jason Murchison, P.Geo.  |             |          |
| Date    | December 8 <sup>th</sup> , 2017  | Project No. | 60343599 |

## 1. Introduction and Background

AECOM Canada Ltd. (AECOM) has been retained by North Kent Wind 1 LP (NKW1) to provide hydrogeological services pursuant to *Condition G* of Renewable Energy Approval (REA) No. 5272-A9FHRL.

The purpose of this Technical Memorandum (TM) is to present a response to a water well interference complaint that was received by NKW1 via the Project's toll-free telephone line on 10-October-2017. Upon receipt of the complaint, email notification was provided by NKW1 (c/o Mr. Joshua Vaidhyan) to Ms. Deb Jacobs, Environmental Officer, with the Ministry of the Environment and Climate Change (MOECC), Windsor Area Office that same day. In his correspondence, Mr. Vaidhyan provides a summary narrative of the well interference complaint that was received from [REDACTED], the property owners of [REDACTED] (Dresden, ON).

In brief, Mr. Vaidhyan describes the well interference complaint as follows:

*We received a complaint on the Project's toll-free line, below.*

*PIN 007420039*

*Phone: [REDACTED]*

*Located about 650 metres from T12. [REDACTED] called to say his well went dry during the weekend. He got it going on Tuesday, but the water is quite turbid.*

*AECOM will be following up with this landowner. I will inform you regarding the date they schedule the sampling.*

A copy of the NKW1 correspondence described above is provided herein as **Attachment A**.

## 2. REA Condition Response

**Table 1** provides a summary of action(s) taken pursuant to REA Condition G5 in response to the current well interference complaint.

**TABLE 1: REA CONDITIONS AND RESPONSE SUMMARY**

| REA CONDITIONS   | ACTION(S) TAKEN  |
|--|--|
| <p><b>G5.</b> Should the Company receive a complaint about wells or well water from an owner of an active water well (i) within the Project Study Area; or (ii) outside of the Project Study area and located within 1 km from each individual Equipment and meteorological tower, the microwave tower, and the operations &amp; maintenance building, the Company shall retain a qualified expert (P.Eng or P.Geo) to immediately undertake the following:</p> <ol style="list-style-type: none"> <li>(1) collect a water well sample at the complainant's water well, prior to any treatment systems ("raw"), after allowing the distribution system to flow for approximately 5 minutes and submit the water sample to a qualified laboratory for an analysis of the general chemistry suite of water quality parameters identified in Condition G3;</li> <li>(2) compare the results of the analysis of the water sample noted in Condition G5(1) to the pre-construction water sampling analysis results noted in Condition G3 for the subject well (if a pre-construction water sample at the subject well was taken); and,</li> <li>(3) provide a detailed written opinion as to whether the water sampling analysis results demonstrate that the construction, operation or decommissioning of the Facility caused or may have caused an adverse effect to the well's water supply.</li> </ol> | <p>Steps undertaken to satisfy the requirements of Condition G5 are summarized, as follows:</p> <ol style="list-style-type: none"> <li>(1) AECOM was retained by NKW1 to investigate a Well Interference Complaint received directly from the property owners on 10-October-2017.</li> <li>(2) AECOM arranged directly with the property owners an appointment to visit the property at 11:00am on 11-October-2017 (appointment based on property owner availability).</li> <li>(3) Tasks completed by AECOM during the well interference complaint site visit included: <ol style="list-style-type: none"> <li>i) interview with the property owner regarding their reported well interference issue(s);</li> <li>ii) collection of a raw (untreated) groundwater sample for analytical laboratory testing; and,</li> <li>iii) digital photographs of pertinent site features (eg. well, pumping system, etc.).</li> </ol> </li> <li>(4) Information obtained during the site visit has been compiled and is summarized within this technical memorandum. An opinion regarding potential association of the well interference complaint with local construction activities as part of the NKW1 Project is provided and potential remedial options are presented, as appropriate.</li> </ol> |

## 2.1 Property Owner Statements Regarding Well Interference Complaint

During AECOM's 11-October-2017 site visit to the subject property, a series of seven (7) standard questions were raised with the property owner ([REDACTED]) for the purposes of obtaining further details regarding their reported well water supply issue(s). The questions raised with the property owner were as detailed on *Form B: Well Complaint Procedure for Site Investigation*, included as part of MOECC's approved *Well Interference Protocol* (AECOM, 2017) for the NKW1 project.

**TABLE 2: PROPERTY OWNER QUESTIONNAIRE RESPONSE SUMMARY**

| QUESTION  | PROPERTY OWNER RESPONSE  |
|---|--|
| "Please explain the type of problem you are having" | <ul style="list-style-type: none"> <li>Well stopped producing water on the afternoon of 8-October-2017.</li> <li>Neighbours have had problems, so back up supply was arranged by resident for Thanksgiving party (portable tank with municipal water). Used tank until the morning of 10-October-2017, when the well was re-activated. Water was grey in colour and "coarse and fine shale" was observed.</li> <li>Has two (2) samples collected, "normal" and discoloured sample for our information.</li> <li>Has used well gingerly since reconnecting, it has not yet cleared up.</li> <li>Quantity was normal on 11-October-2017 during investigation.</li> </ul> |
| "What do you think is the cause?"                   | <ul style="list-style-type: none"> <li>Unsure.</li> </ul>  |

December 8<sup>th</sup>, 2017

|  |   |
|--|---|
| "When did you first notice the problem (Date/Time)?"                                 | · 8-October-2017 at 1:30pm.   |
| "Is the problem still occurring?"  | · Running hose to flush well (mist through hose), not drinking the water. Collected sample in mason jar after disconnecting temporary supply. |
| "Do you have an alternate source of potable water (i.e. municipal water)?"           | · Arranged by homeowner temporarily.  |
| "Were you provided a temporary supply of potable water?"                             | · Project representative coming 13-October-2017 to discuss temporary supply.  |
| "Did you participate in the Detailed Well Assessment program prior to construction?" | · Yes   |

Upon completion of the questionnaire, the property owner ([REDACTED]) was provided an opportunity to review the responses detailed in **Table 2** to ensure accuracy, but respectfully declined.

### 3. Construction Activities and Vibration Monitoring

Within a one (1) month timeframe preceding the property owner's reported outset of well impact (8-October-2017), no pile driving activities for foundation construction as part of the NKW1 project were completed within a 4.5 km radius of the site well.

The following four (4) turbines represent the closest foundation construction locations to the subject property:

- T12 – July 4<sup>th</sup> to 6<sup>th</sup> @ 695 m South-Southeast
- T7 – July 27<sup>th</sup> & 28<sup>th</sup> @ 1,070 m Northwest
- T31 – July 13<sup>th</sup>, 14<sup>th</sup>, 17<sup>th</sup> & 18<sup>th</sup> @ 1,715 m West-Southwest
- T6 – July 31<sup>st</sup> @ 3,225 m West-Northwest

Construction timeframes, along with approximate directions and distances away from the subject property are provided above for reference purposes. As can be observed, T12 and T7 represent the nearest two (2) turbine locations to the subject property. Pile driving at these turbine sites was completed in July 2017, more than two (2) months prior to the reported outset of well interference impact(s) at the subject property.

Monitoring of vibration effects during pile driving at each of the above-noted turbine locations was completed by Golder Associates Ltd. (GAL) on behalf of NKW1 in accordance with *Condition H* of the REA. The monitoring program developed and implemented by GAL (and as approved by MOECC) comprised the measurement of particle velocities at locations in close proximity to the piles, as well as at local private water well supplies. Vibration monitoring results obtained by GAL are summarized in a technical letter, dated 20-September-2017.

In addition to the foregoing, a site-specific vibration assessment pertaining to the subject property was completed by GAL, the results of which are presented in a letter, dated 24-November-2017.

A copy of each GAL letter is included herein as **Attachment B**.

Based on the vibration monitoring completed by GAL, the following interpretation and conclusions are presented within their 20-September-2017 technical letter:

*In summary, vibration measurements obtained with the geophone system (Instantel Minimate) on all sites reported herein were within expectations as compared to those measured at the T5 and T42*

December 8<sup>th</sup>, 2017

test pile sites and general project expectations. On sites where piles penetrated through the near surface soils under their own weight or a low number of hammer blows (e.g., less than 5) the ground surface vibrations during this phase of pile driving for each pile were nominal. Ground surface vibrations measured when driving the piles on the glacial till or rock were also either comparable to or less than those at the test pile sites and, in all cases, were within expectations. Vibration measurements made using the accelerometers mounted on the well casings were also within expectations based on the T5 and T42 test pile sites and turbine to well distances.

Well monitoring to-date has identified several wells for which the vibrations induced by the pumps dominated the instrument readings when the pumps were active or other activities dominated the measured vibrations. Relevant notes regarding various pumps, their operation and other influences on vibration measurements are described below:

**Well 3:** Activities at the Well 3 property included crop harvesting, movement of farm vehicles and loading of haul trucks in relatively close proximity to Well 3.

**Well 4:** Maximum well casing vibration velocities for Well 4 of about 4.8 mm/s were recorded on September 6, 2017 when a well pump was connected, operated and adjusted and the owner made frequent return visits to the well shed. Crop harvesting was also carried out as close as about 25 m from the well casing.

**Well 6:** The pump for Well 6 is mounted in close proximity to the well casing (as illustrated on the attached Photograph 1). Maximum particle velocities of as much as 0.8 mm/s were obtained from monitoring data collected at Well 6 on July 13, 2017 when the well pump was operating during a time period without pile driving. The influences of the pump were readily discernable in the monitoring data. Approximately 1 minute after driving of Pile 1 for turbine T12 concluded, a loaded tractor-trailer dump truck drove by on the road near Well 6 and, at the same time, the resident was hammering in a nearby shed. Vibrations associated with the loaded dump truck were also perceptible by our well monitoring staff and registered at about 2.8 mm/s.

**Well 9:** A piston pump for Well 9 is located within the barn adjacent to the Well 9 casing location, a total distance (inside and outside) of about 3 to 4 m. During pile driving for turbines T28 and T32, on August 11, 2017, other work was occurring near Well 9. This work included construction along the access road leading to the T32 site and included movement of heavy equipment, excavator operations, dump truck traffic, discharge of stone from delivery vehicles and other activities. This surface construction work was as close as 100 m to Well 9. Additionally, Well 9 is approximately 74 m from Countryview Line that experiences significant traffic. Traffic included loaded construction equipment, buses, fuel tanker trucks and other vehicles. Golder conducted a separate monitoring event at this well on September 8, 2017 to measure the influence of the pump on well casing vibrations in the absence of pile driving. Maximum measured casing vibrations during this test were about 1.2 mm/s. Measurements at Well 9 on dates other than August 11, 2017 are consistent with expectations based on local traffic volumes and the potential influence of the adjacent piston pump.

**Well 10:** Well 10 exhibited maximum vibrations of about 1.25 mm/s during pump operation. The influence of pump operations were clearly discernable in the vibration monitoring data. The proximity of the pump and well casing are illustrated in the attached Photograph 2.

**Well 11:** Vibrations of the casing at Well 11 were measured during water quality sampling on August 17, 2017 in the absence of pile driving at any location. When the pump was operating, a maximum vibration magnitude of 0.016 mm/s was measured at this well. The pump is located within the residence and approximately 40 m from the well.

**Well 12:** During pile driving, Well 12 operated on a number of clearly definable occasions. Maximum vibration measurements of pump-induced well casing vibrations were as much as 2.4 mm/s. The pump for Well 12 is a piston pump mounted directly on top of the well casing as illustrated in the attached Photograph 3.



December 8<sup>th</sup>, 2017

**Well 13:** Well 13 is located approximately 87 m from the centreline of Union Line which is subjected to local truck traffic. Review of the data indicates that well pumping and non-pile driving transient sources influenced the results at this location. Additional evaluation of transient, non-pile driving data is on-going and a specific monitoring period for well pump operation is being planned for a time without pile driving.

**Well 14:** Well 14 is located approximately 13 m from the centreline of Union Line which is subjected to local truck traffic. A limited evaluation of transient traffic vibrations indicated well casing velocities of at least 0.079 mm/s associated with this cause, though inspection of the data indicates higher values occurred outside of pile driving times. Additional evaluation of transient, non-pile driving data is on-going and a specific monitoring period for well pump operation is being planned for a time without pile driving.

In summary, measured vibrations have been evaluated and reported as associated with driving 329 piles and replacement piles on the glacial till/rock along with restrrike events and pile dynamic testing events. These measurements have been obtained at the turbine sites and at wells located at distances ranging from 580 to 4,359 m from the turbine sites. It is our opinion, based on these measurements, that the vibration magnitudes at all wells during pile driving were within expectations, no greater than may be induced by other common day-to-day sources at these well sites, less than the observed and measured influence of well pumps and inconsequential for the wells.

The interpretation and conclusions above are reconfirmed by GAL within their site-specific assessment letter, dated 24-November-2017, which reads:

*This letter is provided to summarize vibration monitoring data associated with Well Complaint 13 dated October 10, 2017 related to the well located at [REDACTED], in Chatham-Kent, Ontario. Golder Associates Ltd. (Golder) has been requested to summarize vibration monitoring data for the period starting one day prior to the first reported issues, identified as October 8, 2017, through to one day following the date of the reported well condition complaint. Based on Golder's records, no piles were driven on October 7, 8 or 9, 2017 and therefore there is no vibration monitoring data for this period. Given that there was no pile driving during this period, it is our opinion that the reported conditions at the well would not have been related to pile driving.*

#### 4. Well Construction Details

**Table 3** provides a summary of available construction details for the existing water well located at [REDACTED], based on details provided to AECOM by [REDACTED] during our 11-October-2017 well interference complaint site visit, as well as information provided by the property owners on their completed water well survey (WWS) form and during our baseline site visit on 20-January-2017.

A review of the MOECC on-line database has revealed a water well record for the subject property that is consistent with the date of installation reported by the property owner (1989). Relevant information obtained from the MOECC record also is included in **Table 3**. In addition, a small number of other well installation and abandonment records also were located within the MOECC database for the subject property dating as far back as 1971 (with 2008 as most recent). A copy of the MOECC record interpreted to be associated with the currently used water well on the subject property is provided herein as **Attachment C**.

Visual assessment of the water well at surface did not reveal any apparent concerns, save for the well being equipped with an older slip-on style metallic well lid rather than a vermin-proof cap. A photograph of the well is provided as **Photo 1**.

**TABLE 3: REPORTED PRIVATE WELL CONSTRUCTION DETAILS**

| DETAILS                | [REDACTED]<br>(PIN 007420039)   |
|------------------------|---|
| Well Tag #             | Not Applicable  |
| Well ID                | 3308387   |
| Installation Date      | 24-November-1988  |
| Well Location          | Side Yard (Northeast of Residence)  |
| Contractor             | Marvin Johanston  |
| Contractor No.         | 3065  |
| Construction Method    | Cable Tool  |
| Total Depth            | 19.2 mBGS (63')   |
| Target Formation       | Black Shale   |
| Casing Length          | 18.9 mBGS (62')   |
| Casing Diameter        | 127 mm (5")   |
| Casing Material        | Steel   |
| Casing Stick-Up        | 0.40 m (as measured by AECOM)   |
| Annular Seal           | None Indicated on WWR   |
| Sealant Type           | None Indicated on WWR   |
| Well Screen Installed? | No  |
| Well Screen Details    | Open Hole (Shale Bedrock)   |
| Well Screen Interval   | Not Applicable  |
| Well Cover Type        | Metallic Slip Cap (non vermin-proof)  |
| Pump Intake Depth      | 15.2 mBGS (50') recommended on WWR<br>(unconfirmed)   |
| Pumping Rate           | 15.2 L/min (4 USgpm) recommended on WWR<br>(determined via air-lift)<br>21.0 L/min (5.5 USgpm) as measured by AECOM on<br>13-October-2017 (average of 3 separate flow rate<br>measurements) |
| Well Pump Type         | Jet Pump (as observed by AECOM)   |
| Well Pump Size         | ½ hp (as observed by AECOM)   |
| Static Level           | 4.0 mBGS (13') as on WWR  |
| Pumping Level          | 7.6 mBGS (25') as on WWR  |

**NOTE:** mBGS - meters below ground surface; L/min – litres per minute; USgpm – US gallons per minute.

#### 4.1 Limited Well Flow Rate Testing and Pumping System Assessment

During AECOM's site visit on 11-October-2017, a limited flow rate test was completed to assess the current pumping capacity of the jet pump connected to the well. This testing was completed using a standard hose faucet installed within the garage portion of the residence.

For the test, the water system was permitted to flush continuously for a period of approximately eleven (11) minutes using a 12 mm (1/2") hose assembly (provided and installed by AECOM) attached to the faucet orifice. During pumping, the discharge rate was assessed by AECOM on three (3) separate occasions. Flow rate measurement was completed by timing the discharge of 10 L of

December 8<sup>th</sup>, 2017

water into a calibrated pail. Based on this monitoring, an average flow rate of approximately 21 L/min (5.5 USgpm) was determined for the residence's water system (affected by pressure tank). Discharge from the hose was directed to ground at the exterior of the residence.

Gas bubbles were observed within the discharge water stream which remained relatively consistent during testing and subsequent sample collection activities.

No variation in flow rate (including increasing or decreasing trends) was observed during testing. Similarly, no detectable changes in the quality of the water discharge stream (eg. colour, odour, dissolved gas, sediment, etc.) were identified.



PHOTO 1: Drilled Water Well (as observed on 20-January-2017)

## 5. Water Quality Data

**Table 4** provides a summary of available groundwater quality data for the site well. Laboratory Certificates of Analysis are included as **Attachment D**.

**TABLE 4: PRIVATE WELL SAMPLING SUMMARY**

| LOCATION   | SAMPLED BY | DATE            | TYPE            | PURPOSE                 |
|------------|------------|-----------------|-----------------|-------------------------|
| [REDACTED] | AECOM      | 20-January-2017 | Raw (Untreated) | Baseline                |
|            | AECOM      | 11-October-2017 | Raw (Untreated) | Complaint Investigation |

### 5.1 Discussion

Available raw (untreated) groundwater quality data for the well is provided in **Table 5**, which includes analysis results for AECOM's 11-October-2017 complaint investigation site visit, as well as baseline (pre-construction) sampling that was completed on 20-January-2017.

**TABLE 5: RAW (UNTREATED) GROUNDWATER SAMPLING RESULTS**

| PARAMETER                              | ODWQS CRITERIA | ODWQS TYPE | BASELINE (20-January-2017) | COMPLAINT INVESTIGATION (11-October-2017) |
|--|----------------|------------|----------------------------|---|
| Escherichia coli                       | 0 CFU/100mL    | MAC        | NDOGN                      | Non detection                             |
| Total Coliforms                        | 0 CFU/100mL    | MAC        | NDOGN                      | 90 CFU/100 mL                             |
| Electrical Conductivity                | --             | --         | 548 µS/cm                  | 540 µS/cm                                 |
| pH                                     | 6.5 – 8.5      | OG         | 8.23                       | 8.21                                      |
| Total Hardness (as CaCO <sub>3</sub> ) | 80 – 100 mg/L  | OG         | <b>36.7 mg/L</b>           | <b>37.2 mg/L</b>                          |
| Total Dissolved Solids                 | 500 mg/L       | AO         | 292 mg/L                   | 318 mg/L                                  |
| Total Suspended Solids                 | --             | --         | <10 mg/L                   | <10 mg/L                                  |
| Alkalinity (as CaCO <sub>3</sub> )     | 30 – 500 mg/L  | OG         | 258 mg/L                   | 269 mg/L                                  |
| Fluoride                               | 1.5            | MAC        | 1.37 mg/L                  | 1.44 mg/L                                 |
| Chloride                               | 250            | AO         | 20.7 mg/L                  | 20.8 mg/L                                 |
| Nitrate as N                           | 10             | MAC        | <0.05 mg/L                 | <0.05 mg/L                                |
| Nitrite as N                           | 1              | MAC        | <0.05 mg/L                 | <0.05 mg/L                                |
| Bromide                                | --             | --         | 0.26 mg/L                  | <0.05 mg/L                                |
| Sulphate                               | 500 mg/L       | AO         | <0.10 mg/L                 | <0.10 mg/L                                |
| Ammonia as N                           | --             | --         | 0.09 mg/L                  | 0.69 mg/L                                 |
| Dissolved Organic Carbon               | 5 mg/L         | AO         | 3.8 mg/L                   | 4.2 mg/L                                  |
| Colour                                 | 5 TCU          | AO         | <b>19 TCU</b>              | <b>67 TCU</b>                             |
| Turbidity                              | 5 NTU          | AO         | 3.7 NTU                    | <b>10.9 NTU</b>                           |
| Calcium                                | --             | --         | 9.29 mg/L                  | 9.44 mg/L                                 |
| Magnesium                              | --             | --         | 3.29 mg/L                  | 3.32 mg/L                                 |
| Sodium                                 | 200 mg/L       | AO         | 114 mg/L                   | 116 mg/L                                  |
| Potassium                              | --             | --         | 1.33 mg/L                  | 1.37 mg/L                                 |
| Iron                                   | 0.300 mg/L     | AO         | 0.010 mg/L                 | <b>0.733 mg/L</b>                         |
| Manganese                              | 0.050 mg/L     | AO         | 0.002 mg/L                 | 0.011 mg/L                                |

**NOTE:** MAC – maximum acceptable concentration (health-related); AO – Aesthetic Objective (non health-related); Operational Guideline (non health-related); NDOGN – No Data, Sample Overgrown with Target (refers to over-crowding microbial growth).

At the time of AECOM's baseline site visit on 20-January-2017, no water treatment devices were observed to be present within the residence. Likewise, no treatment equipment was observed during our 13-October-2017 site visit.

Raw (untreated) groundwater sample collection during AECOM's 13-October-2017 site visit was completed using a standard hose faucet located in the garage portion of the residence; that same location as that which was utilized during baseline sampling (ref. **Photo 2**). Prior to sampling, the faucet was permitted to flush thoroughly with the pumped water being directed to ground at the exterior of the residence. Prior to sample collection, the discharge hose was removed and the faucet orifice was disinfected (using chlorine) and flushed. Clean nitrile gloves were worn by AECOM staff during sample collection.

December 8<sup>th</sup>, 2017

**PHOTO 2: Sampling and Flow Rate Testing Location in Garage (as observed on 11-October-2017)**

The groundwater sample was examined by AECOM in the field for visual and olfactory evidence of impact then immediately placed in laboratory-supplied sample bottles prepared in advance with the appropriate preservatives, sealed, labeled and stored on ice to maintain a sample temperature of 10°C or lower during transportation under chain of custody documentation to a CALA-accredited environmental analytical laboratory within the specified sample analyte holding times.

A detectable population of total coliforms (90 CFU/100 mL) was identified within the raw (untreated) groundwater sample collected from the well on 11-October-2017. This result is consistent with baseline sampling results where significant (ie. overgrown) bacteriological populations for both total coliforms and *Escherichia coli* (*E.coli*) were identified. It is noted that *E.coli* was determined to be absent in the most recent water quality sample. Both total coliforms and *E.coli* represent health-related parameters of the Ontario Drinking Water Quality Standards (ODWQS). It is recommended that the property owner seek the guidance of MOECC, their local Public Health Unit, and/or an experienced water treatment specialist to address the elevated levels of bacteria within the well.

No exceedances of inorganic health-related parameters analyzed, including Nitrate (as N), Nitrite (as N), and Fluoride, were detected either in the baseline or complaint investigation raw (untreated) groundwater samples collected from the existing on-site well supply.

Turbidity is an Aesthetic Objective (AO) of the ODWQS. In this regard, a value of 5 Nephelometric Turbidity Units (NTU) has been established by MOECC. The MOECC's *Technical Support Document for Ontario Drinking Water Standards, Objectives and Guidelines* (June 2003; revised June 2006) makes a clear distinction between turbidity related to organic constituents and inorganic constituents

December 8<sup>th</sup>, 2017

stating: "Raw water supply which is ground water with very low organic content may contain inorganic-based turbidity, which may not seriously hinder disinfection. For such waters, an Operational Guideline for turbidity is not established". Further guidance is provided by MOECC regarding the relationship between turbidity and its organic and inorganic components, the disinfection processes, and as a measure of the water supply filtration and treatment efficiency. The technical explanations also note that while organic turbidity is an important measure as related to health concerns, the AO value is an aesthetic component which is set for all waters at the point of consumption (i.e., not at the source). At the site well, turbidity levels were 3.7 NTU in the baseline sample and 10.9 NTU during the recent well interference complaint site visit. The latter value was somewhat higher than the baseline sample and above the ODWQS AO limit.

Iron concentrations were determined to be in excess of its ODWQS AO limit of 0.3 mg/L in the complaint investigation (0.733 mg/L) raw groundwater sample collected by AECOM from the site well. Elevated concentrations of iron can impart a brownish discolouration to water (including staining of fixtures and laundry) and can also provide an astringent taste during consumption. It is surmised that the elevated concentration of iron in the sample is correlated with the similarly elevated turbidity level and is interpreted to be of a natural (non-anthropogenic) source.

Where elevated iron concentrations occur in well water, the presence of iron-related bacteria (IRB) is not uncommon. IRB combine iron (as well as manganese, where present) with oxygen as part of their metabolic processes to form visible 'rust' deposits / stains (eg. yellow, orange, red or brown) that are typically associated with a greasy or slimy texture. Various foul odours may also be associated with the presence of IRB within a well water system (eg. rotten egg, swampy, sewage-like, etc.). The 'slime' will tend stick to fixtures and water system components, including filter elements, pump foot valve assemblies, and well screens, which can result in flow restrictions over time. While not assessed as part of this investigation, IRB may potentially be present within the site well which could affect sample results, most notably turbidity. Although being a nuisance, there is no documented health risk associated with IRB, if present, and can be managed through treatment combined with regular maintenance disinfection of the well supply.

Total suspended solids (TSS) levels within both the baseline and complaint investigation raw groundwater samples were below laboratory method detection limits indicating a relative absence of detectable sediment load in the raw (untreated) groundwater pumped from the well. An ODWQS criteria limit has not been established for this parameter.

The potential for groundwater quality impact(s) associated with pile driving is both time-dependent and related to the intensity and propagation of ground-borne vibration. In this instance, no pile driving activities were completed within a radial distance of 4.5 km from the site well within a timeframe of one (1) month prior to the reported outset of well impacts (8-October-2017). As such, no vibrations attributable to pile driving activities as part of the NKW1 project would have been present in proximity to the site well either immediately prior to or on the date of outset of impact, as reported by the property owners.

As an alternate consideration, to have the potential to impact the subject well vibration impacts in the immediate vicinity of a pile driving (turbine) location would have needed to result in: i) the suspension of settled particles within the groundwater system; ii) the particles remaining in suspension for a prolonged period of time; and, iii) the water well being situated in a position hydraulically downgradient of and/or within the radius of pumping influence relative to the pile driving location. Factors (ii) and (iii) above are not considered plausible in the context of the local hydrogeological setting (ie. potential hydraulic gradient and groundwater travel times), vibration monitoring data collected by GAL, and recent sampling results.

December 8<sup>th</sup>, 2017

## 6. Conclusions

Based on a review and interpretation of information gathered during AECOM's well interference complaint investigation, as presented herein, it is our opinion that the groundwater quality issue reported by the property owners at [REDACTED] (PIN 007420039) is *not* as a result of NKW1 turbine foundation construction or pile-driving activities as no work had been completed within a 4.5 km radius of the subject property within a one (1) month period prior to the reported onset of well impact on 8-October-2017.

The water well impact(s) reported by the property owner appear to be related to local water system issues versus an area-wide impact to the local groundwater system. As noted within this report, consultation with a qualified professional regarding the current condition of the on-site well supply / pumping system, and bacteriological quality of the raw water source is recommended.

This interpretation and opinions presented in this technical memorandum are based on information available as of the date the document was prepared. Should additional information become available at a future date, AECOM reserves the right to review and potentially reconsider the findings of our current assessment through the issuance of addenda to this technical memorandum.

-- End of Memorandum --



**AECOM**

## **Attachments**





**AECOM**

**Attachment    A**

**Correspondence**

## Murchison, Jason

---

From: Joshua Vaidyan <j.vaidhyan@samsung.com>  
Sent: Tuesday, October 10, 2017 4:47 PM  
To: 'Jacobs, Deb (MOECC)'  
Cc: 'Gilbert, Teri (MOECC)'; 'Smith, Mark (MOECC)'; 'Harman, Bruce (MOECC)'; 'Thuss, Simon (MOECC)'; 'Moroney, Michael (MOECC)'; 'Lehouillier, Jason (MOECC)'; 'McDonald, Dan (MOECC)'; 'Pat Murray'; Murchison, Jason; 'Sre.Bop'; 'Boone, Storer'; 'Colella, Nick (MOECC)'; 'Keyvani, Mohsen (MOECC)'; 'Jody Law'; Van der Woerd, Mark  
Subject: New Complaint - [REDACTED] North Kent 1

Hi Deb,

We received a complaint on the Project's toll-free line, below.

PIN 007420039

[REDACTED]

Phone: [REDACTED]

Located about 650 metres from T12. [REDACTED] called to say his well went dry during the weekend. He got it going on Tuesday, but the water is quite turbid..

AECOM will be following up with this landowner. I will inform you regarding the date they schedule the sampling.



**AECOM**

**Attachment B**

**Vibration Monitoring Data  
(Golder Associates Ltd.)**

November 24, 2017

Project No. 1668031-2000-L23

Mr. Jody Law  
c/o North Kent Wind 1 LP  
355 Adelaide Street West, Suite 1000  
Toronto, ON M5V 1S2

**WATER WELL COMPLAINT 13  
NORTH KENT WIND 1 PROJECT  
CHATHAM-KENT, ONTARIO**


Dear Mr. Law:

This letter is provided to summarize vibration monitoring data associated with Well Complaint 13 dated October 10, 2017 related to the well located at [REDACTED] in Chatham-Kent, Ontario. Golder Associates Ltd. (Golder) has been requested to summarize vibration monitoring data for the period starting one day prior to the first reported issues, identified as October 8, 2017, through to one day following the date of the reported well condition complaint. Based on Golder's records, no piles were driven on October 7, 8 or 9, 2017 and therefore there is no vibration monitoring data for this period. Given that there was no pile driving during this period, it is our opinion that the reported conditions at the well would not have been related to pile driving.

We trust that this letter is adequate for your present requirements. If any point requires further clarification, please contact this office.

Yours truly,

**GOLDER ASSOCIATES LTD.**



Nov. 24/17  
S. J. BOONE  
90559733  
PROV. OF ONTARIO

Storer J. Boone, Ph.D., P.Eng.

Principal

SJB/MEB/cr

CC: J. Vaidyan, Samsung

n:\active\2016\3 proj\1668031 pattern\_north kent vib monit\_chatham-kent\ph 2000-vib monit field work\2-correspondence\3-ltrs\123\1668031-2000-l23 nov 24 17 water well complaint 13.docx



September 20, 2017

Project No. 1668031-2000-L06

Mr. Jody Law  
c/o North Kent Wind 1 LP  
355 Adelaide Street West, Suite 1000  
Toronto, ON M5V 1S2

**SUMMARY OF VIBRATION MONITORING  
FOUNDATION PILE DRIVING – MULTIPLE TURBINES  
NORTH KENT WIND 1 PROJECT  
CHATHAM-KENT, ONTARIO**

Dear Mr. Law:

Please find attached a summary of the vibration monitoring that has been undertaken during driving of foundation piles for turbines being constructed as part of the North Kent Wind 1 project (NK1) at the locations listed in Table 1 (following the text of this letter) through to September 12, 2017, exclusive of data for Turbines T26 and T27 as these are still being processed and analyzed. Vibration monitoring was carried out to meet Section H1 of the Renewable Energy Approval (REA) document issued by the Ontario Ministry of the Environment and Climate Change (MOECC). The work was carried out in accordance with a vibration monitoring program prepared by Golder Associates Ltd. (Golder) dated June 2, 2017 and subsequently approved by MOECC and issued June 9, 2017.

This report addresses vibration monitoring data obtained during pile foundation driving at the turbine sites and domestic water well pairs listed in Table 1, attached, as defined by the times and dates for pile driving within the seven geographic turbine clusters. The locations of the turbines and associated wells are illustrated on the attached figures. The attached pages of summary data and notes include particle velocity measurements made at the referenced sites that were taken in close proximity to the pile driving together with measurements obtained at domestic water well casings associated with the relevant turbine clusters. Previously issued summary pages have been updated to reflect changes, if and as applicable, related to:

- detailed review of Instantel Minimate data histogram files for the turbine sites;
- well and turbine site vibration monitoring data associated with pile dynamic analyser testing, subsequent pile restrikes or replacements;
- monitoring of vibrations during well pump operating periods in the absence of pile driving;



- examination of vibration data associated with background conditions, other transient vibration sources (e.g., road traffic, movement of farm equipment, pump maintenance) and/or time durations during which pile driving was not actively in progress;
- clarifications or additions to pile driving monitoring notes; and
- typographical/clerical corrections, if and as needed.

The vibration measurements as reported on the attached pages are considered finalized for the analysis time periods, stated conditions and the context of this report. Golder reserves the right to update reports for the various turbine sites and wells as additional information becomes available and to address any of the items noted above. In particular, additional evaluation of turbine site geophone data is anticipated whereby actual off-set distances and vibration measurements at specific piles and times of day may be updated rather than the current listing of daily maximum measurements. A finalized report will be issued after the conclusion of all pile driving for this project.

## Monitoring Work Plan

Vibration monitoring was carried out in accordance with the June 2, 2017 work plan submitted to and approved by the MOECC and reissued on June 9, 2017. In summary, key elements of the work plan include:

- Pile driving at the turbine sites is visually monitored by a Golder staff member who keeps notes regarding start and stop times of active pile hammering, monitoring data logging and instrument status and other site conditions as relevant to the pile driving. Ground surface vibrations at each turbine site are being monitored with two Instantel Minimate Pro III or Pro IV systems. Two systems are being utilized to allow periodic downloading of data so that vibrations, if any, could then be captured by the other redundant system. The geophone systems captured vibration velocities in three mutually perpendicular directions. One direction was vertical and the longitudinal direction was oriented toward the closest pile with the third (transverse) direction being determined by the other two.
- Three accelerometers are being securely coupled to the monitored well casings for which permissions to enter and carry out monitoring have been obtained. The accelerometers are oriented in three mutually perpendicular directions. One direction is vertical and the longitudinal direction is oriented toward the closest pile driving operation, with the third (transverse) direction being determined by the other two. Golder personnel monitor the instrument status and any other relevant activities around the wells such as local road traffic, movements of farm equipment, traffic in and out of the well properties, other construction activities (if any) and well pump operations or maintenance.

## Overview of Pile Driving Conditions and Monitoring Notes

Pile driving at the turbine sites was conducted after constructing an access road, stripping topsoil, excavating to approximately 2.6 m below the ground surface and placing a concrete working pad. The concrete working pads have been fitted with pre-formed openings for the piles or constructed to a smaller diameter with the piles driven just beyond the outer perimeter of the concrete. Pile driving cranes were operated on timber mats placed on the concrete. Typically, piles were driven with the same hammer type as used for the pre-construction test pile and vibration monitoring program. In one case, a different hammer was used with a significantly lower driving energy. Subsequent use of this hammer has been rejected by the constructor.

On the attached monitoring reports, three times are reported for each driven pile. The column heading “Start” refers to the time of day when the pile hammering commenced on the indicated pile. Times of other site activities, such as crane movements, welding, equipment start-up and other work occurring prior to start of active pile hammering were not recorded except in specific instances where the turbine site geophones were inadvertently influenced by other equipment operating too closely. The column heading “Rock/Till” indicates the time at which hard driving started, as evidenced by the rate of pile depth change as compared to the numbers of hammer strikes on the pile. Commonly, the piles penetrated the first few metres of ground under their own weight, with nominal pile driving effort required until the underlying glacial till and/or rock was encountered. In many cases, the pile driving resistance in the upper soil layers was insufficient to engage the firing mechanism in the diesel hammer. Upon reaching the glacial till, the pile hammer fully engaged for the remainder of driving. The column heading “End” indicates the time of day at which active pile hammering ceased for the identified pile. While the total pile driving duration can be determined by the difference between the “Start” and “End” times, the duration of active pile hammering was frequently interrupted by pile splicing, welding, equipment repair, decision-making required for pile termination depths, pile testing and daily labour breaks. Many of these start and stop instances are identified on the attached summary pages.

## Summary of Results

In summary, vibration measurements obtained with the geophone system (Instantel Minimate) on all sites reported herein were within expectations as compared to those measured at the T5 and T42 test pile sites and general project expectations. On sites where piles penetrated through the near-surface soils under their own weight or a low number of hammer blows (e.g., less than 5) the ground surface vibrations during this phase of pile driving for each pile were nominal. Ground surface vibrations measured when driving the piles on the glacial till or rock were also either comparable to or less than those at the test pile sites and, in all cases, were within expectations. Vibration measurements made using the accelerometers mounted on the well casings were also within expectations based on the T5 and T42 test pile sites and turbine to well distances.

Well monitoring to-date has identified several wells for which the vibrations induced by the pumps dominated the instrument readings when the pumps were active or other activities dominated the measured vibrations. Relevant notes regarding various pumps, their operation and other influences on vibration measurements are described below:

- **Well 3:** Activities at the Well 3 property included crop harvesting, movement of farm vehicles and loading of haul trucks in relatively close proximity to Well 3.
- **Well 4:** Maximum well casing vibration velocities for Well 4 of about 4.8 mm/s were recorded on September 6, 2017 when a well pump was connected, operated and adjusted and the owner made frequent return visits to the well shed. Crop harvesting was also carried out as close as about 25 m from the well casing.
- **Well 6:** The pump for Well 6 is mounted in close proximity to the well casing (as illustrated on the attached Photograph 1). Maximum particle velocities of as much as 0.8 mm/s were obtained from monitoring data collected at Well 6 on July 13, 2017 when the well pump was operating during a time period without pile driving. The influences of the pump were readily discernable in the monitoring data. Approximately 1 minute after driving of Pile 1 for turbine T12 concluded, a loaded tractor-trailer dump truck drove by on the road near Well 6 and, at the same time, the resident was hammering in a nearby shed. Vibrations associated with the loaded dump truck were also perceptible by our well monitoring staff and registered at about 2.8 mm/s.

- **Well 9:** A piston pump for Well 9 is located within the barn adjacent to the Well 9 casing location, a total distance (inside and outside) of about 3 to 4 m. During pile driving for turbines T28 and T32, on August 11, 2017, other work was occurring near Well 9. This work included construction along the access road leading to the T32 site and included movement of heavy equipment, excavator operations, dump truck traffic, discharge of stone from delivery vehicles and other activities. This surface construction work was as close as 100 m to Well 9. Additionally, Well 9 is approximately 74 m from Countryview Line that experiences significant traffic. Traffic included loaded construction equipment, buses, fuel tanker trucks and other vehicles. Golder conducted a separate monitoring event at this well on September 8, 2017 to measure the influence of the pump on well casing vibrations in the absence of pile driving. Maximum measured casing vibrations during this test were about 1.2 mm/s. Measurements at Well 9 on dates other than August 11, 2017 are consistent with expectations based on local traffic volumes and the potential influence of the adjacent piston pump.
- **Well 10:** Well 10 exhibited maximum vibrations of about 1.25 mm/s during pump operation. The influence of pump operations were clearly discernable in the vibration monitoring data. The proximity of the pump and well casing are illustrated in the attached Photograph 2.
- **Well 11:** Vibrations of the casing at Well 11 were measured during water quality sampling on August 17, 2017 in the absence of pile driving at any location. When the pump was operating, a maximum vibration magnitude of 0.016 mm/s was measured at this well. The pump is located within the residence and approximately 40 m from the well.
- **Well 12:** During pile driving, Well 12 operated on a number of clearly definable occasions. Maximum vibration measurements of pump-induced well casing vibrations were as much as 2.4 mm/s. The pump for Well 12 is a piston pump mounted directly on top of the well casing as illustrated in the attached Photograph 3.
- **Well 13:** Well 13 is located approximately 87 m from the centreline of Union Line which is subjected to local truck traffic. Review of the data indicates that well pumping and non-pile driving transient sources influenced the results at this location. Additional evaluation of transient, non-pile driving data is on-going and a specific monitoring period for well pump operation is being planned for a time without pile driving.
- **Well 14:** Well 14 is located approximately 13 m from the centreline of Union Line which is subjected to local truck traffic. A limited evaluation of transient traffic vibrations indicated well casing velocities of at least 0.079 mm/s associated with this cause, though inspection of the data indicates higher values occurred outside of pile driving times. Additional evaluation of transient, non-pile driving data is on-going and a specific monitoring period for well pump operation is being planned for a time without pile driving.



In summary, measured vibrations have been evaluated and reported as associated with driving 329 piles and replacement piles on the glacial till/rock along with restrrike events and pile dynamic testing events. These measurements have been obtained at the turbine sites and at wells located at distances ranging from 580 to 4,359 m from the turbine sites. It is our opinion, based on these measurements, that the vibration magnitudes at all wells during pile driving were within expectations, no greater than may be induced by other common day-to-day sources at these well sites, less than the observed and measured influence of well pumps and inconsequential for the wells.



We trust that this letter is adequate for your present requirements. If any point requires further clarification, please contact this office.

Yours truly,

**GOLDER ASSOCIATES LTD.**

Storer J. Boone, Ph.D., P.Eng.  
Principal

SJB/MEB/cr

Attachments: Table 1 - Vibration Measurement Locations  
Photographs of Wells 6, 10 and 12 Pump Configurations  
Preliminary Vibration Monitoring Summaries and Figures, Turbines T3, T4, T6, T7, T12, T14, T20, T21, T28, T30, T31, T32, T33, T35, T36, T43, T45 and T46

n:\active\2016\3 proj\1668031 pattern\_north kent vib monit\_chatham-kent\ph 2000-vib monit field work\2-correspondence\3-ltrs\06\1668031-2000-l06 sep 20 17 summary of vibration monitoring.docx

**TABLE 1 – VIBRATION MEASUREMENT LOCATIONS**

| Turbine Cluster 1                                   |                   |                   |
|---|-------------------|-------------------|
| Turbine   | Well              | Well              |
| Turbine Cluster 1                                   |                   |                   |
| T12   | 5 ( [REDACTED] )  | 6 ( [REDACTED] )  |
| T35   |                   |                   |
| T36   |                   |                   |
| Turbine Cluster 2                                   |                   |                   |
| T6  | 7 ( [REDACTED] )  | 8 ( [REDACTED] )  |
| T7  |                   |                   |
| T31   |                   |                   |
| Turbine Cluster 3                                   |                   |                   |
| T28   | 9 ( [REDACTED] )  | 10 ( [REDACTED] ) |
| T30   |                   |                   |
| T32   |                   |                   |
| Turbine Cluster 4                                   |                   |                   |
| T3  | 11 ( [REDACTED] ) | 12 ( [REDACTED] ) |
| T4  |                   |                   |
| T20   |                   |                   |
| T21   |                   |                   |
| T43   |                   |                   |
| T45   |                   |                   |
| T46   |                   |                   |
| Turbine Cluster 5                                   |                   |                   |
| T33   | 3 ( [REDACTED] )  | 4 ( [REDACTED] )  |
| Turbine Cluster 6                                   |                   |                   |
| T14   | 13 ( [REDACTED] ) | 14 ( [REDACTED] ) |
| T26   |                   |                   |
| T27   |                   |                   |
| Turbine Cluster 7                                   |                   |                   |
| No construction pile driving to date of this report | 1A ( [REDACTED] ) | 2 ( [REDACTED] )  |

Note: Table to be read in conjunction with accompanying text.

Prepared By: SJB

Checked By: DB

## SITE PHOTOGRAPHS



Photograph 1: Well 6 illustrating proximity of pump, hoses and tank to well casing.



Photograph 2: Well 10 illustrating proximity of pump, hoses and tank to well casing.



Photograph 3: Well 12 illustrating pump mounted directly on well casing.



# NORTH KENT 1

## Preliminary Vibration Monitoring Report

**Turbine Location:** T3

### Vibration Measurements at Turbine Site

### Vibration Measurements at Wells

| Pile Driving Times and Dates         |                    |                 |                  |                    |   | Particle Velocity (mm/s) <sup>c, d</sup> |         |                      |
|--------------------------------------|--------------------|-----------------|------------------|--------------------|---|--|---------|----------------------|
| Pile No.:                            | Start <sup>a</sup> | Rock/Till       | End <sup>a</sup> | Geophone Dist. (m) | Daily Maximum Particle Velocity (mm/s) <sup>b</sup> | Well 11                                  | Well 12 | No Pump <sup>e</sup> |
| 1                                    | 8/23/2017 10:01    | 8/23/2017 10:10 | 8/23/2017 10:11  | 21.6               | 7.27  | NA <sup>e</sup>                          | 0.021   |                      |
| 2                                    | 8/23/2017 11:29    | 8/23/2017 11:35 | 8/23/2017 12:35  | 23.2               | 7.27  | 0.011                                    | 0.003   |                      |
| 3                                    | 8/23/2017 11:46    | 8/23/2017 11:56 | 8/23/2017 12:41  | 24.2               | 7.27  | 0.024                                    | 0.013   |                      |
| 4                                    | 8/23/2017 12:12    | 8/23/2017 12:19 | 8/23/2017 12:21  | 24.5               | 7.27  | 0.014                                    | 0.010   |                      |
| 5                                    | 8/23/2017 9:43     | 8/23/2017 9:49  | 8/23/2017 9:52   | 24.2               | 7.27  | NA <sup>e</sup>                          | 0.010   |                      |
| 6                                    | 8/23/2017 9:28     | 8/23/2017 9:35  | 8/23/2017 9:35   | 23.2               | 7.27  | NA <sup>e</sup>                          | 0.004   |                      |
| 7                                    | 8/22/2017 12:16    | 8/22/2017 12:22 | 8/22/2017 12:57  | 21.6               | 8.26  | 0.015                                    | 0.016   |                      |
| 8                                    | 8/22/2017 18:43    | 8/22/2017 18:49 | 8/22/2017 18:54  | 19.4               | 8.26  | 0.013                                    | 0.004   |                      |
| 9                                    | 8/22/2017 16:52    | 8/22/2017 16:58 | 8/22/2017 17:00  | 16.8               | 8.26  | 0.018                                    | 0.011   |                      |
| 10                                   | 8/22/2017 18:19    | 8/22/2017 18:27 | 8/22/2017 18:32  | 13.9               | 8.26  | 0.014                                    | 0.008   |                      |
| 11                                   | 8/22/2017 16:34    | 8/22/2017 16:40 | 8/22/2017 16:45  | 11.0               | 8.26  | 0.022                                    | 0.025   |                      |
| 12                                   | 8/22/2017 17:48    | 8/22/2017 17:57 | 8/22/2017 18:08  | 8.7                | 8.26  | 0.011                                    | 0.003   |                      |
| 13                                   | 8/22/2017 16:08    | 8/22/2017 16:16 | 8/22/2017 16:18  | 7.7                | 8.26  | 0.007                                    | 0.029   |                      |
| 14                                   | 8/22/2017 17:29    | 8/22/2017 17:38 | 8/22/2017 17:39  | 8.7                | 8.26  | 0.012                                    | 0.013   |                      |
| 15                                   | 8/22/2017 14:27    | 8/22/2017 14:33 | 8/22/2017 15:41  | 11.0               | 8.26  | 0.066                                    | 0.008   |                      |
| 16                                   | 8/22/2017 17:13    | 8/22/2017 17:20 | 8/22/2017 17:20  | 13.9               | 8.26  | 0.026                                    | 0.005   |                      |
| 17                                   | 8/22/2017 13:14    | 8/22/2017 13:22 | 8/22/2017 15:48  | 16.8               | 8.26  | 0.046                                    | 0.008   |                      |
| 18                                   | 8/23/2017 11:05    | 8/23/2017 11:12 | 8/23/2017 11:16  | 19.4               | 7.27  | 0.018                                    | 0.014   |                      |
| <b>Restrikes</b>                     |                    |                 |                  |                    |   |  |         |                      |
| 7C                                   | 8/23/2017 18:27    | 8/23/2017 18:27 | 8/23/2017 18:31  | 21.6               | 7.27  | 0.023                                    | 1.354   | 0.022                |
| 8C                                   | 8/23/2017 8:14     | 8/23/2017 8:14  | 8/23/2017 8:14   | 19.4               | 7.27  | 0.010                                    | 0.004   |                      |
| 11C                                  | 8/23/2017 8:18     | 8/23/2017 8:18  | 8/23/2017 8:18   | 11.0               | 7.27  | 0.009                                    | 2.405   | 0.006                |
| 12C                                  | 8/23/2017 8:22     | 8/23/2017 8:22  | 8/23/2017 8:22   | 8.7                | 7.27  | 0.009                                    | 2.405   | 0.006                |
| 13C                                  | 8/23/2017 8:25     | 8/23/2017 8:26  | 8/23/2017 8:26   | 7.7                | 7.27  | 0.009                                    | 0.007   |                      |
| 14C                                  | 8/23/2017 8:28     | 8/23/2017 8:28  | 8/23/2017 8:28   | 8.7                | 7.27  | 0.007                                    | 0.007   |                      |
| 16C                                  | 8/23/2017 8:31     | 8/23/2017 8:31  | 8/23/2017 8:32   | 13.9               | 7.27  | 0.007                                    | 0.007   |                      |
| 17C                                  | 8/23/2017 8:34     | 8/23/2017 8:34  | 8/23/2017 8:34   | 16.8               | 7.27  | 0.007                                    | 0.007   |                      |
| 6                                    | 8/23/2017 12:14    | 8/23/2017 12:15 | 8/23/2017 12:15  | 23.2               | 7.27  | 0.025                                    | 0.023   |                      |
| <b>Replacement Piles</b>             |                    |                 |                  |                    |   |  |         |                      |
| 7A                                   | 9/6/2017 12:05     | 9/6/2017 12:14  | 9/6/2017 12:19   | 20.6               | 1.99  | 0.033                                    | 0.005   |                      |
| <b>Well Information</b>              |                    |                 |                  |                    |   |  |         |                      |
| <b>Well No.:</b>                     | 11                 |                 |                  |                    | <b>Well No.:</b>                                    | 12                                       |         |                      |
| <b>Municipal Address:</b>            |                    |                 |                  |                    | <b>Municipal Address:</b>                           |  |         |                      |
| <b>Distance from Turbine Centre:</b> |                    | 1707 m          |                  |                    | <b>Distance from Turbine Centre:</b>                |  | 1264 m  |                      |

ISO 2631-2 particle velocity threshold for human perception is 0.1 mm/s between approximately 8 to 100 Hz

Background values at T5 and T42 test pile sites and Wells 1 and 3, when other common activities observed ranged from <0.01 to approximately 0.07 mm/s

**Monitoring Notes:** After installation, selected piles were struck again with the hammer to demonstrate resistance performance and these are noted as "restrikes". Continued pile driving on subsequent days are marked "C". Replacement piles are marked "A". Vibration measurements were undertaken on August 17, 2017 at Wells 11 and 12 during water quality sampling events in the absence of pile driving within the cluster. Both pumps turned on and operated during the sampling events. Maximum vibration measurements for Well 11 were 0.016 mm/s and this pump was located within the residence approximately 40 m from the well. Maximum vibration measurements for Well 12 were 0.896 mm/s and this pump was mounted on the well casing. During pile driving on August 23, 2017, the maximum vibration measurement of the Well 12 casing was 2.4 mm/s for clearly definable periods during which the pump was operating. Data shown for the "no pump" condition was obtained during pile driving when the pump was not operating. Data not available for Piles 1, 5 and 6 at Well 11 on August 23, 2017 due to battery failure in monitoring equipment. Battery was subsequently replaced. Driving/restriking of some piles occurred in relatively rapid succession and, therefore, in some cases the vibration measurement data for the 10 minute periods of analysis are applicable to multiple piles. Where total driving duration between till/rock start and end times noted above is not representative, actual driving duration is shown in parentheses in minutes and seconds: 2(6:42), 3(5:13), 7(8:45), 12(7:08), 15(1:20), 17(1:42). Total pile driving durations derived from start and end times noted above includes labour breaks, equipment work, splicing, welding and other standby time.

**NORTH KENT 1**  
**Preliminary Vibration Monitoring Report**

**Footnotes:** a) start and end of pile driving are start and stop times for active hammering; b) values shown are maximum daily values regardless of direction; c) preliminary values subject to further data review/analysis; d) values shown are based on fast Fourier transform analyses of consecutive 1 second intervals for a total period of 10 minutes during pile driving on till/rock (600 seconds) and represent the maximum of the 1 second interval peak velocity values during these periods regardless of measurement direction; e) see monitoring notes above.

## Preliminary Vibration Monitoring Report

Turbine Location: T4

## Vibration Measurements at Turbine Site

## Vibration Measurements at Wells

| Pile Driving Times and Dates |                    |                 |                  | Geophone Dist. (m) | Daily Maximum Particle Velocity (mm/s) <sup>b</sup> | Particle Velocity (mm/s) <sup>c, d</sup> |         |                      |
|------------------------------|--------------------|-----------------|------------------|--------------------|---|--|---------|----------------------|
| Pile No.:                    | Start <sup>a</sup> | Rock/Till       | End <sup>a</sup> |                    |   | Well 11                                  | Well 12 | No Pump <sup>e</sup> |
| 1                            | 8/25/2017 8:00     | 8/25/2017 8:08  | 8/25/2017 8:09   | 23.9               | 2.54  | 0.004                                    | 0.006   |                      |
| 2                            | 8/25/2017 8:30     | 8/25/2017 9:15  | 8/25/2017 9:16   | 25.6               | 2.54  | 0.006                                    | 2.335   | 0.008                |
| 3                            | 8/25/2017 9:03     | 8/25/2017 9:09  | 8/25/2017 9:10   | 26.6               | 2.54  | 0.007                                    | 2.335   | 0.008                |
| 4                            | 8/25/2017 8:47     | 8/25/2017 8:56  | 8/25/2017 8:57   | 27.0               | 2.54  | 0.005                                    | 0.011   |                      |
| 5                            | 8/25/2017 8:15     | 8/25/2017 8:22  | 8/25/2017 8:23   | 26.6               | 2.54  | 0.028                                    | 0.018   |                      |
| 6                            | 8/24/2017 13:01    | 8/24/2017 13:10 | 8/24/2017 13:11  | 25.6               | 4.32  | 0.011                                    | 0.056   |                      |
| 7                            | 8/24/2017 9:56     | 8/24/2017 10:04 | 8/24/2017 10:51  | 23.9               | 4.32  | 0.018                                    | 1.511   | 0.024                |
| 8                            | 8/24/2017 13:19    | 8/24/2017 15:13 | 8/24/2017 15:14  | 21.6               | 4.32  | 0.024                                    | 1.777   | 0.014                |
| 9                            | 8/24/2017 10:56    | 8/24/2017 11:04 | 8/24/2017 11:04  | 19.0               | 4.32  | 0.006                                    | 0.004   |                      |
| 10                           | 8/24/2017 13:35    | 8/24/2017 13:45 | 8/24/2017 13:45  | 16.1               | 4.32  | 0.006                                    | 0.018   |                      |
| 11                           | 8/24/2017 11:10    | 8/24/2017 11:18 | 8/24/2017 11:18  | 13.2               | 4.32  | 0.013                                    | 0.026   |                      |
| 12                           | 8/24/2017 13:52    | 8/24/2017 15:09 | 8/24/2017 15:10  | 11.0               | 4.32  | 0.024                                    | 1.777   | 0.014                |
| 13                           | 8/24/2017 11:23    | 8/24/2017 11:32 | 8/24/2017 11:33  | 10.1               | 4.32  | 0.009                                    | 0.009   |                      |
| 14                           | 8/24/2017 14:07    | 8/24/2017 14:17 | 8/24/2017 14:17  | 11.0               | 4.32  | 0.007                                    | 0.006   |                      |
| 15                           | 8/24/2017 11:38    | 8/24/2017 15:03 | 8/24/2017 15:04  | 13.2               | 4.32  | 0.009                                    | 1.374   | 0.028                |
| 16                           | 8/24/2017 14:24    | 8/24/2017 14:33 | 8/24/2017 15:01  | 16.1               | 4.32  | 0.009                                    | 1.374   | 0.028                |
| 17                           | 8/24/2017 12:46    | 8/24/2017 14:55 | 8/24/2017 14:56  | 19.0               | 4.32  | 0.030                                    | 1.374   | 0.028                |
| 18                           | 8/24/2017 14:40    | 8/24/2017 14:52 | 8/24/2017 14:52  | 21.6               | 4.32  | 0.030                                    | 0.029   |                      |

## Well Information

Well No.: 11

Municipal Address:

Distance from Turbine Centre: 1424 m

Well No.: 12

Municipal Address:

Distance from Turbine Centre: 1072 m

ISO 2631-2 particle velocity threshold for human perception is 0.1 mm/s between approximately 8 to 100 Hz

Background values at T5 and T42 test pile sites and Wells 1 and 3, when other common activities observed ranged from &lt;0.01 to approximately 0.07 mm/s

**Monitoring Notes:** Vibration measurements were undertaken on August 17, 2017 at Wells 11 and 12 during water quality sampling events in the absence of pile driving within the cluster. Both pumps turned on and operated during the sampling events. Maximum vibration measurements for Well 11 were 0.016 mm/s and this pump was located within the residence approximately 40 m from the well. Maximum vibration measurements for Well 12 were 0.896 mm/s and this pump was mounted on the well casing. During pile driving on August 24, 2017, the maximum vibration measurement of the Well 12 casing was 1.777 mm/s for clearly definable periods during which the pump was operating. Data shown for the "no pump" condition was obtained during pile driving when the pump was not operating. Note that driving of some piles was paused while the tip was in the upper soil deposits and subsequently driven to the glacial till/rock later in the day. In these instances, the hard driving conditions for different piles occurred in relatively rapid succession and, therefore, the vibration measurement data for the 10 minute periods of analysis are applicable to multiple piles. Where total driving duration between till/rock start and end times noted above is not representative, actual driving duration is shown in parentheses in minutes and seconds: 2(7:33), 7(1:32), 8(0:53), 12(1:10), 15(1:15), 16(1:02), 17(1:31). Total driving durations derived from start and end times noted above include labour breaks, equipment work, splicing, welding and other standby time.

**Footnotes:** a) start and end of pile driving are start and stop times for active hammering; b) values shown are maximum daily values regardless of direction; c) preliminary values subject to further data review/analysis; d) values shown are based on fast Fourier transform analyses of consecutive 1 second intervals for a total period of 10 minutes during pile driving on till/rock (600 seconds) and represent the maximum of the 1 second interval peak velocity values during these periods regardless of measurement direction; e) see monitoring notes above.



## Preliminary Vibration Monitoring Report

Turbine Location: T6

## Vibration Measurements at Turbine Site

## Vibration Measurements at Wells

| Pile Driving Times and Dates |                    |                 |                  | Daily Maximum Particle Velocity |                     | Particle Velocity (mm/s) <sup>c, d</sup> |        |
|------------------------------|--------------------|-----------------|------------------|---------------------------------|---------------------|--|--------|
| Pile No.:                    | Start <sup>a</sup> | Rock/Till       | End <sup>a</sup> | Geophone Dist. (m)              | (mm/s) <sup>b</sup> | Well 7                                   | Well 8 |
| 1                            | 7/31/2017 11:25    | 7/31/2017 11:28 | 7/31/2017 11:32  | 27.0                            | 4.57                | 0.068                                    | 0.049  |
| 2                            | 7/31/2017 12:20    | 7/31/2017 12:26 | 7/31/2017 12:28  | 26.6                            | 4.57                | 0.044                                    | 0.032  |
| 3                            | 7/31/2017 12:37    | 7/31/2017 12:41 | 7/31/2017 12:46  | 25.6                            | 4.57                | 0.018                                    | 0.028  |
| 4                            | 7/31/2017 13:35    | 7/31/2017 13:40 | 7/31/2017 13:46  | 23.9                            | 4.57                | 0.066                                    | 0.011  |
| 5                            | 7/31/2017 13:18    | 7/31/2017 13:23 | 7/31/2017 13:28  | 21.6                            | 4.57                | 0.017                                    | 0.010  |
| 6                            | 7/31/2017 12:59    | 7/31/2017 13:05 | 7/31/2017 13:07  | 19.0                            | 4.57                | 0.012                                    | 0.033  |
| 7                            | 7/31/2017 7:33     | 7/31/2017 7:37  | 7/31/2017 7:42   | 16.1                            | 4.57                | 0.050                                    | 0.050  |
| 8                            | 7/31/2017 7:53     | 7/31/2017 7:56  | 7/31/2017 8:03   | 13.2                            | 4.57                | 0.127                                    | 0.070  |
| 9                            | 7/31/2017 8:14     | 7/31/2017 8:18  | 7/31/2017 8:22   | 11.0                            | 4.57                | 0.051                                    | 0.015  |
| 10                           | 7/31/2017 8:31     | 7/31/2017 8:37  | 7/31/2017 8:41   | 10.1                            | 4.57                | 0.025                                    | 0.058  |
| 11                           | 7/31/2017 8:48     | 7/31/2017 8:51  | 7/31/2017 8:53   | 11.0                            | 4.57                | 0.035                                    | 0.012  |
| 12                           | 7/31/2017 9:02     | 7/31/2017 9:07  | 7/31/2017 9:12   | 13.2                            | 4.57                | 0.058                                    | 0.023  |
| 13                           | 7/31/2017 9:21     | 7/31/2017 9:25  | 7/31/2017 9:33   | 16.1                            | 4.57                | 0.118                                    | 0.005  |
| 14                           | 7/31/2017 9:42     | 7/31/2017 9:47  | 7/31/2017 9:50   | 19.0                            | 4.57                | 0.082                                    | 0.007  |
| 15                           | 7/31/2017 10:21    | 7/31/2017 10:24 | 7/31/2017 10:29  | 21.6                            | 4.57                | 0.039                                    | 0.032  |
| 16                           | 7/31/2017 10:36    | 7/31/2017 10:40 | 7/31/2017 10:43  | 23.9                            | 4.57                | 0.010                                    | 0.014  |
| 17                           | 7/31/2017 10:51    | 7/31/2017 10:54 | 7/31/2017 10:58  | 25.6                            | 4.57                | 0.040                                    | 0.057  |
| 18                           | 7/31/2017 11:09    | 7/31/2017 11:13 | 7/31/2017 11:17  | 26.6                            | 4.57                | 0.024                                    | 0.071  |

## Well Information

Well No.: 7

Municipal Address:

Distance from Turbine Centre: 1049 m

Well No.: 8

Municipal Address:

Distance from Turbine Centre: 872 m

ISO 2631-2 particle velocity threshold for human perception is 0.1 mm/s between approximately 8 to 100 Hz

Background values at T5 and T42 test pile sites and Wells 1 and 3, when other common activities observed ranged from &lt;0.01 to approximately 0.07 mm/s

**Monitoring Notes:** Well monitoring undertaken during periods of time on these same days when pile driving was not occurring measured maximum particle velocities of as much as 0.37 mm/s (Well 7). Total pile driving durations derived from start and end times noted above includes labour breaks, equipment work, splicing, welding and other standby time.

**Footnotes:** a) start and end of pile driving are start and stop times for active hammering; b) values shown are maximum daily values regardless of direction; c) preliminary values subject to further data review/analysis; d) values shown are based on fast Fourier transform analyses of consecutive 1 second intervals for a total period of 10 minutes during pile driving on till/rock (600 seconds) and represent the maximum of the 1 second interval peak velocity values during these periods regardless of measurement direction.

# NORTH KENT 1

## Preliminary Vibration Monitoring Report

**Turbine Location:** T7

### Vibration Measurements at Turbine Site

### Vibration Measurements at Wells

| Pile Driving Times and Dates |                    |                 |                  |                    | Daily Maximum<br>Particle Velocity | Particle Velocity (mm/s) <sup>c, d</sup> |        |
|------------------------------|--------------------|-----------------|------------------|--------------------|------------------------------------|--|--------|
| Pile No.:                    | Start <sup>a</sup> | Rock/Till       | End <sup>a</sup> | Geophone Dist. (m) | (mm/s) <sup>b</sup>                | Well 7                                   | Well 8 |
| 1                            | 7/27/2017 17:57    | 7/27/2017 18:03 | 7/27/2017 18:04  | 27.0               | 5.97                               | 0.030                                    | 0.011  |
| 2                            | 7/27/2017 18:31    | 7/27/2017 18:36 | 7/27/2017 18:36  | 26.6               | 5.97                               | 0.063                                    | 0.013  |
| 3                            | 7/28/2017 8:11     | 7/28/2017 8:16  | 7/28/2017 8:16   | 25.6               | 2.16                               | 0.019                                    | 0.022  |
| 4                            | 7/28/2017 8:37     | 7/28/2017 8:43  | 7/28/2017 8:44   | 23.9               | 2.16                               | 0.035                                    | 0.045  |
| 5                            | 7/27/2017 18:11    | 7/27/2017 18:17 | 7/27/2017 18:18  | 21.6               | 5.97                               | 0.017                                    | 0.012  |
| 6                            | 7/27/2017 15:27    | 7/27/2017 15:32 | 7/27/2017 15:33  | 19.0               | 5.97                               | 0.019                                    | 0.028  |
| 7                            | 7/27/2017 15:10    | 7/27/2017 15:15 | 7/27/2017 15:16  | 16.1               | 5.97                               | 0.026                                    | 0.028  |
| 8                            | 7/27/2017 14:30    | 7/27/2017 14:36 | 7/27/2017 14:37  | 13.2               | 5.97                               | 0.017                                    | 0.027  |
| 9                            | 7/27/2017 14:10    | 7/27/2017 14:16 | 7/27/2017 14:18  | 11.0               | 5.97                               | 0.011                                    | 0.031  |
| 10                           | 7/27/2017 13:55    | 7/27/2017 14:00 | 7/27/2017 14:01  | 10.1               | 5.97                               | 0.030                                    | 0.012  |
| 11                           | 7/27/2017 13:42    | 7/27/2017 13:46 | 7/27/2017 13:47  | 11.0               | 5.97                               | 0.025                                    | 0.042  |
| 12                           | 7/27/2017 13:09    | 7/27/2017 13:13 | 7/27/2017 13:23  | 13.2               | 5.97                               | 0.019                                    | 0.035  |
| 13                           | 7/27/2017 12:21    | 7/27/2017 12:34 | 7/27/2017 12:53  | 16.1               | 5.97                               | 0.030                                    | 0.049  |
| 14                           | 7/27/2017 15:42    | 7/27/2017 15:51 | 7/27/2017 15:54  | 19.0               | 5.97                               | 0.026                                    | 0.039  |
| 15                           | 7/27/2017 16:06    | 7/27/2017 16:12 | 7/27/2017 16:13  | 21.6               | 5.97                               | 0.032                                    | 0.021  |
| 16                           | 7/27/2017 16:34    | 7/27/2017 16:44 | 7/27/2017 16:45  | 23.9               | 5.97                               | 0.010                                    | 0.066  |
| 17                           | 7/27/2017 16:55    | 7/27/2017 17:01 | 7/27/2017 17:02  | 25.6               | 5.97                               | 0.069                                    | 0.030  |
| 18                           | 7/27/2017 17:17    | 7/27/2017 17:25 | 7/27/2017 17:26  | 26.6               | 5.97                               | 0.027                                    | 0.060  |

#### Well Information

**Well No.:** 7

**Municipal Address:**

**Distance from Turbine Centre:** 1354 m

**Well No.:** 8

**Municipal Address:**

**Distance from Turbine Centre:** 2883 m

ISO 2631-2 particle velocity threshold for human perception is 0.1 mm/s between approximately 8 to 100 Hz

Background values at T5 and T42 test pile sites and Wells 1 and 3, when other common activities observed ranged from <0.01 to approximately 0.07 mm/s

**Monitoring Notes:** Well monitoring undertaken during periods of time on these same days when pile driving was not occurring measured maximum particle velocities of as much as 0.073 mm/s. Total driving duration between till/rock start and end times noted above for Pile 13 is not representative and actual driving duration was 00:1:45 due to pauses in actual hammering. Total pile driving durations derived from start and end times noted above includes labour breaks, equipment work, splicing, welding and other standby time.

**Footnotes:** a) start and end of pile driving are start and stop times for active hammering; b) values shown are maximum daily values regardless of direction; c) preliminary values subject to further data review/analysis; d) values shown are based on fast Fourier transform analyses of consecutive 1 second intervals for a total period of 10 minutes during pile driving on till/rock (600 seconds) and represent the maximum of the 1 second interval peak velocity values during these periods regardless of measurement direction.

## Preliminary Vibration Monitoring Report

Turbine Location: T12

## Vibration Measurements at Turbine Site

## Vibration Measurements at Wells

| Pile Driving Times and Dates |                    |                 |                  |                    | Daily Maximum Particle Velocity (mm/s) <sup>b</sup> | Particle Velocity (mm/s) <sup>c, d</sup> |        |                      |
|------------------------------|--------------------|-----------------|------------------|--------------------|---|--|--------|----------------------|
| Pile No.:                    | Start <sup>a</sup> | Rock/Till       | End <sup>a</sup> | Geophone Dist. (m) |   | Well 5                                   | Well 6 | No Pump <sup>e</sup> |
| 1                            | 7/5/2017 12:33     | 7/5/2017 12:46  | 7/5/2017 12:47   | 27.5               | 5.97  | 0.008                                    | 0.044  | See Notes            |
| 2                            | 7/5/2017 15:47     | 7/5/2017 16:01  | 7/5/2017 16:01   | 27.8               | 5.97  | 0.001                                    | 0.106  |                      |
| 3                            | 7/6/2017 8:08      | 7/6/2017 8:19   | 7/6/2017 8:20    | 27.5               | 4.32  | 0.010                                    | 0.775  |                      |
| 4                            | 7/6/2017 7:47      | 7/6/2017 7:58   | 7/6/2017 7:59    | 26.4               | 4.32  | 0.002                                    | 0.048  |                      |
| 5                            | 7/5/2017 12:57     | 7/5/2017 13:26  | 7/5/2017 13:27   | 24.7               | 5.97  | 0.002                                    | 0.729  |                      |
| 6                            | 7/5/2017 14:11     | 7/5/2017 14:22  | 7/5/2017 14:23   | 22.5               | 5.97  | 0.002                                    | 0.298  |                      |
| 7                            | 7/4/2017 14:48     | 7/4/2017 14:57  | 7/4/2017 14:58   | 19.8               | 5.97  | 0.002                                    | 0.026  |                      |
| 8                            | 7/5/2017 11:38     | 7/5/2017 11:49  | 7/5/2017 11:50   | 16.8               | 5.97  | 0.008                                    | 0.030  |                      |
| 9                            | 7/4/2017 9:26      | 7/4/2017 9:58   | 7/4/2017 10:00   | 14.0               | 9.91  | 0.011                                    | 0.246  | 0.014                |
| 10                           | 7/5/2017 11:11     | 7/5/2017 11:25  | 7/5/2017 11:26   | 11.8               | 5.97  | 0.002                                    | 0.047  | 0.014                |
| 11                           | 6/30/2017 12:03    | 6/30/2017 13:47 | 6/30/2017 13:54  | 11.0               | 11.20   | 0.004                                    | 0.755  |                      |
| 12                           | 7/4/2017 15:15     | 7/4/2017 15:25  | 7/4/2017 15:25   | 11.8               | 9.91  | 0.002                                    | 0.179  |                      |
| 13                           | 7/4/2017 11:22     | 7/4/2017 11:33  | 7/4/2017 11:34   | 14.0               | 9.91  | 0.002                                    | 0.066  |                      |
| 14                           | 7/4/2017 15:47     | 7/4/2017 15:58  | 7/4/2017 15:58   | 16.8               | 9.91  | 0.069                                    | 0.037  |                      |
| 15                           | 7/4/2017 11:55     | 7/4/2017 12:06  | 7/4/2017 12:07   | 19.8               | 9.91  | 0.003                                    | 0.023  |                      |
| 16                           | 7/4/2017 16:35     | 7/4/2017 16:47  | 7/4/2017 16:47   | 22.5               | 9.91  | 0.004                                    | 0.155  |                      |
| 17                           | 7/4/2017 13:01     | 7/4/2017 13:14  | 7/4/2017 13:20   | 24.7               | 9.91  | 0.007                                    | 0.085  |                      |
| 18                           | 7/4/2017 15:08     | 7/4/2017 15:27  | 7/4/2017 15:28   | 26.4               | 9.91  | 0.002                                    | 0.729  |                      |
| <b>Restrikes</b>             |                    |                 |                  |                    |   |  |        |                      |
| 7                            | 7/5/2017 8:42      | 7/5/2017 8:42   | 7/5/2017 8:42    | 19.8               | 5.97  | 0.007                                    | 0.647  | 0.027                |
| 9                            | 7/5/2017 8:47      | 7/5/2017 8:47   | 7/5/2017 8:48    | 14.0               | 5.97  | 0.007                                    | 0.634  | 0.027                |
| 11                           | 7/5/2017 8:51      | 7/5/2017 8:51   | 7/5/2017 8:52    | 11.0               | 5.97  | 0.007                                    | 0.634  | 0.032                |
| 12                           | 7/5/2017 8:57      | 7/5/2017 8:57   | 7/5/2017 8:58    | 11.8               | 5.97  | 0.003                                    | 0.624  |                      |
| 13                           | 7/5/2017 9:02      | 7/5/2017 9:02   | 7/5/2017 9:03    | 14.0               | 5.97  | 0.008                                    | 0.662  |                      |
| 14                           | 7/5/2017 9:09      | 7/5/2017 9:09   | 7/5/2017 9:10    | 16.8               | 5.97  | 0.008                                    | 0.624  |                      |
| 15                           | 7/5/2017 9:13      | 7/5/2017 9:13   | 7/5/2017 9:14    | 19.8               | 5.97  | 0.003                                    | 0.546  | 0.057                |
| 16                           | 7/5/2017 9:17      | 7/5/2017 9:17   | 7/5/2017 9:19    | 22.5               | 5.97  | 0.002                                    | 0.546  | 0.057                |
| 17                           | 7/5/2017 9:22      | 7/5/2017 9:22   | 7/5/2017 9:23    | 26.4               | 5.97  | 0.002                                    | 0.546  | 0.057                |

## Well Information

Well No.: 5  
Municipal Address: [REDACTED]  
Distance from Turbine Centre: 3346 m

Well No.: 6  
Municipal Address: [REDACTED]  
Distance from Turbine Centre: 3368 m

ISO 2631-2 particle velocity threshold for human perception is 0.1 mm/s between approximately 8 to 100 Hz

Background values at T5 and T42 test pile sites and Wells 1 and 3, when other common activities observed ranged from <0.01 to approximately 0.07 mm/s

**Monitoring Notes:** After installation, selected piles were struck again with the hammer to demonstrate resistance performance and these are noted as "restrikes". On July 5, 2017, approximately 1 minute after pile driving stopped for Pile 1, the well monitoring personnel at Well 6 observed a loaded tractor/trailer dump truck drive by the well at 54 m distance and ground vibrations were sensed. At this time, the resident was also hammering on equipment within a nearby (120 m) shed during which it sounded as though a heavy sledge was being used with multiple recoil/hammer falls after each main strike. Vibrations associated with these activities (not separable) registered as 2.8 mm/s, consistent with the perception of vibrations by the well monitoring personnel. Monitoring of deliberate pump operation at Well 6 on July 13, 2017, during a period when no pile driving was occurring, measured maximum particle velocities of 0.08 to 0.8 mm/s. Driving/restriking of some piles occurred in relatively rapid succession and, therefore, in some cases the vibration measurement data for the 10 minute periods of analysis are applicable to multiple piles. Total pile driving durations derived from start and end times noted above includes labour breaks, equipment work, splicing, welding and other standby time. The driving duration for Pile 11 on June 30, 2017 were unusually long since a small driving hammer was used for this pile. The total duration of driving on till/rock was 7 minutes for this pile.

**Footnotes:** a) start and end of pile driving are start and stop times for active hammering; b) values shown are maximum daily values regardless of direction; c) preliminary values subject to further data review/analysis; d) values shown are based on fast Fourier transform analyses of consecutive 1 second intervals for a total period of 10 minutes during pile driving on till/rock (600 seconds) and represent the maximum of the 1 second interval peak velocity values during these periods regardless of measurement direction; e) see monitoring notes above.

# NORTH KENT 1

## Preliminary Vibration Monitoring Report

**Turbine Location:** T14

| Vibration Measurements at Turbine Site |                    |                 |                  |                    |   | Vibration Measurements at Wells          |         |                      |
|--|--------------------|-----------------|------------------|--------------------|---|--|---------|----------------------|
| Pile Driving Times and Dates           |                    |                 |                  | Geophone Dist. (m) | Daily Maximum Particle Velocity (mm/s) <sup>b</sup> | Particle Velocity (mm/s) <sup>c, d</sup> |         |                      |
| Pile No.:                              | Start <sup>a</sup> | Rock/Till       | End <sup>a</sup> |                    |   | Well 13                                  | Well 14 | No Pump <sup>e</sup> |
| 1                                      | 9/11/2017 16:01    | 9/11/2017 16:06 | 9/11/2017 16:09  | 18.9               | 4.95  | 0.020                                    | 0.206   |                      |
| 2                                      | 9/11/2017 16:24    | 9/11/2017 16:29 | 9/11/2017 16:32  | 21.0               | 4.95  | 0.010                                    | 0.056   |                      |
| 3                                      | 9/11/2017 15:48    | 9/11/2017 15:54 | 9/11/2017 15:56  | 22.6               | 4.95  | 0.017                                    | 0.132   |                      |
| 4                                      | 9/11/2017 15:33    | 9/11/2017 15:39 | 9/11/2017 15:43  | 23.6               | 4.95  | 0.012                                    | 0.190   |                      |
| 5                                      | 9/11/2017 15:19    | 9/11/2017 15:24 | 9/11/2017 15:26  | 24.0               | 4.95  | 0.006                                    | 0.064   |                      |
| 6                                      | 9/11/2017 15:04    | 9/11/2017 15:10 | 9/11/2017 15:13  | 23.6               | 4.95  | 0.005                                    | 0.221   |                      |
| 7                                      | 9/11/2017 12:33    | 9/11/2017 12:39 | 9/11/2017 12:44  | 22.6               | 4.95  | 0.007                                    | 0.083   |                      |
| 8                                      | 9/11/2017 12:17    | 9/11/2017 12:25 | 9/11/2017 12:27  | 21.0               | 4.95  | 0.005                                    | 0.338   |                      |
| 9                                      | 9/11/2017 11:53    | 9/11/2017 11:59 | 9/11/2017 12:02  | 18.9               | 4.95  | 0.114                                    | 0.675   |                      |
| 10                                     | 9/11/2017 11:36    | 9/11/2017 11:43 | 9/11/2017 11:45  | 16.3               | 4.95  | 0.013                                    | 0.240   |                      |
| 11                                     | 9/11/2017 11:20    | 9/11/2017 11:25 | 9/11/2017 11:28  | 13.5               | 4.95  | 0.013                                    | 0.168   |                      |
| 12                                     | 9/11/2017 10:24    | 9/11/2017 10:30 | 9/11/2017 10:34  | 10.6               | 4.95  | 0.428                                    | 0.077   | 0.011                |
| 13                                     | 9/11/2017 10:07    | 9/11/2017 10:14 | 9/11/2017 10:16  | 8.1                | 4.95  | 0.543                                    | 0.141   | 0.008                |
| 14                                     | 9/11/2017 9:50     | 9/11/2017 9:56  | 9/11/2017 10:01  | 7.1                | 4.95  | 0.021                                    | 0.102   |                      |
| 15                                     | 9/11/2017 9:34     | 9/11/2017 9:39  | 9/11/2017 9:42   | 8.1                | 4.95  | 0.004                                    | 0.014   |                      |
| 16                                     | 9/11/2017 9:17     | 9/11/2017 9:24  | 9/11/2017 9:28   | 10.6               | 4.95  | 0.318                                    | 0.021   | 0.007                |
| 17                                     | 9/11/2017 8:57     | 9/11/2017 9:03  | 9/11/2017 9:05   | 13.5               | 4.95  | 0.026                                    | 0.070   |                      |
| 18                                     | 9/11/2017 8:39     | 9/11/2017 8:47  | 9/11/2017 8:49   | 16.3               | 4.95  | 0.007                                    | 0.018   |                      |

### Restrikes

### Well Information

Well No.: 13  
Municipal Address: [REDACTED]  
Distance from Turbine Centre: 841 m

Well No.: 14  
Municipal Address: [REDACTED]  
Distance from Turbine Centre: 580 m

ISO 2631-2 particle velocity threshold for human perception is 0.1 mm/s between approximately 8 to 100 Hz

Background values at T5 and T42 test pile sites and Wells 1 and 2, when other common activities observed ranged from <0.01 to approximately 0.07 mm/s

**Monitoring Notes:** Total pile driving durations derived from start and end times noted above includes labour breaks, equipment work, splicing, welding and other standby time. Well 13 pump vibrations dominated data for periods of 1 to 5 minutes. "No pump" data column indicates vibration velocities exclusive of pump operating times for Well 13. Wells 13 and 14 are located approximately 87 m and 13 m from the centre line of Union Line, respectively. Vibration velocities noted above for both wells reflect maximum values induced by transient sources other than pile driving. Evaluation of acceleration time histories concluded that other transient vibrations occurring before, during and after pile driving times dominated all measurements. Data for two 10-minute time periods during which no pile driving occurred were evaluated with start times of 10:47 and 14:27 for Well 13 and 10:48 and 14:36 for Well 14 indicated a maximum velocity of 0.079 mm/s. Additional evaluation of pump operations and other transient sources for both wells is pending.

**Footnotes:** a) start and stop of pile driving are start and stop times for active hammering; b) values shown are maximum daily values regardless of direction; c) preliminary values subject to further data review/analysis; d) values shown are based on fast Fourier transform analyses of consecutive 1 second intervals for a total period of 10 minutes during pile driving on till/rock (600 seconds) and represent the maximum of the 1 second interval peak velocity values during these periods regardless of measurement direction; e) see monitoring notes above.

## Preliminary Vibration Monitoring Report

Turbine Location: T20

## Vibration Measurements at Turbine Site

## Vibration Measurements at Wells

| Pile No.:        | Pile Driving Times and Dates |                 |                  | Geophone Dist. (m) | Daily Maximum Particle Velocity (mm/s) <sup>b</sup> | Particle Velocity (mm/s) <sup>c, d</sup> |                 |                      |
|------------------|------------------------------|-----------------|------------------|--------------------|---|--|-----------------|----------------------|
|                  | Start <sup>a</sup>           | Rock/Till       | End <sup>a</sup> |                    |   | Well 11                                  | Well 12         | No Pump <sup>e</sup> |
| 1                | 8/30/2017 15:30              | 8/30/2017 15:33 | 8/30/2017 15:54  | 25.0               | 5.33  | 0.016                                    | NA <sup>e</sup> |                      |
| 2                | 8/30/2017 18:17              | 8/30/2017 18:21 | 8/30/2017 18:29  | 26.0               | 5.33  | 0.005                                    | 0.008           |                      |
| 3                | 8/30/2017 18:33              | 8/30/2017 18:38 | 8/30/2017 18:45  | 26.3               | 5.33  | 0.003                                    | 0.004           |                      |
| 4                | 8/30/2017 17:55              | 8/30/2017 17:59 | 8/30/2017 18:10  | 26.0               | 5.33  | 0.004                                    | 0.005           |                      |
| 5                | 8/30/2017 17:38              | 8/30/2017 17:37 | 8/30/2017 17:49  | 25.0               | 5.33  | 0.004                                    | 0.855           | 0.022                |
| 6                | 8/30/2017 17:14              | 8/30/2017 17:19 | 8/30/2017 17:31  | 23.3               | 5.33  | 0.004                                    | NA <sup>e</sup> |                      |
| 7                | 8/30/2017 16:54              | 8/30/2017 16:56 | 8/30/2017 17:09  | 21.0               | 5.33  | 0.003                                    | NA <sup>e</sup> |                      |
| 8                | 8/30/2017 16:19              | 8/30/2017 16:24 | 8/30/2017 16:53  | 18.3               | 5.33  | 0.046                                    | NA <sup>e</sup> |                      |
| 9                | 8/30/2017 16:01              | 8/30/2017 16:05 | 8/30/2017 16:12  | 15.4               | 5.33  | 0.005                                    | NA <sup>e</sup> |                      |
| 10               | 8/30/2017 11:34              | 8/30/2017 11:38 | 8/30/2017 11:50  | 12.5               | 5.33  | 0.005                                    | 0.016           |                      |
| 11               | 8/30/2017 10:26              | 8/30/2017 10:29 | 8/30/2017 10:40  | 9.1                | 5.33  | 0.018                                    | 0.013           |                      |
| 12               | 8/30/2017 9:58               | 8/30/2017 10:02 | 8/30/2017 10:16  | 10.1               | 5.33  | 0.011                                    | 0.014           |                      |
| 13               | 8/30/2017 9:49               | 8/30/2017 9:44  | 8/30/2017 9:50   | 12.5               | 5.33  | 0.010                                    | 0.014           |                      |
| 14               | 8/30/2017 12:02              | 8/30/2017 12:04 | 8/30/2017 12:22  | 15.4               | 5.33  | 0.028                                    | 0.008           |                      |
| 15               | 8/30/2017 12:36              | 8/30/2017 12:39 | 8/30/2017 12:54  | 18.3               | 5.33  | 0.023                                    | 0.006           |                      |
| 16               | 8/30/2017 13:01              | 8/30/2017 13:05 | 8/30/2017 13:20  | 21.0               | 5.33  | 0.004                                    | 0.004           |                      |
| 17               | 8/30/2017 14:26              | 8/30/2017 14:29 | 8/30/2017 14:41  | 23.3               | 5.33  | 0.004                                    | 0.006           |                      |
| 18               | 8/30/2017 14:52              | 8/30/2017 14:56 | 8/30/2017 15:24  | 25.0               | 5.33  | 0.003                                    | 0.025           |                      |
| <b>Restrikes</b> |                              |                 |                  |                    |   |  |                 |                      |
| 13               | 8/30/2017 13:23              | 8/30/2017 13:23 | 8/30/2017 13:35  | 12.5               | 5.33  | 0.008                                    | 0.008           |                      |

## Well Information

Well No.: 11 [REDACTED]  
Municipal Address: [REDACTED]  
Distance from Turbine Centre: 3800 m

Well No.: 12 [REDACTED]  
Municipal Address: [REDACTED]  
Distance from Turbine Centre: 3962 m

ISO 2631-2 particle velocity threshold for human perception is 0.1 mm/s between approximately 8 to 100 Hz

Background values at T5 and T42 test pile sites and Wells 1 and 2, when other common activities observed ranged from <0.01 to approximately 0.07 mm/s

**Monitoring Notes:** After installation, selected piles were struck again with the hammer to demonstrate resistance performance and these are noted as "restrikes". Vibration measurements were undertaken on August 17, 2017 at Wells 11 and 12 during water quality sampling events in the absence of pile driving within the cluster. Both pumps turned on and operated during the sampling events. Maximum vibration measurements for Well 11 were 0.016 mm/s and this pump was located within the residence approximately 40 m from the well. Maximum vibration measurements for Well 12 were 0.896 mm/s and the pump was mounted on the well casing. During pile driving on August 23, 2017, the maximum vibration measurement of the Well 12 casing was 2.4 mm/s for clearly definable periods during which the pump was operating. Data shown for the "no pump" condition was obtained during pile driving when the pump was not operating. Data not available for Piles 1, 6, 7, 8 and 9 at Well 12 on August 30, 2017 due to battery failure in monitoring equipment. Battery was subsequently replaced. Total driving duration between till/rock start and end times noted above for Pile 1 is not representative and actual driving duration was 00:7:40 due to pauses in actual hammering. Total pile driving durations derived from start and end times noted above includes labour breaks, equipment work, splicing, welding and other standby time.

**Footnotes:** a) start and end of pile driving are start and stop times for active hammering; b) values shown are maximum daily values regardless of direction; c) preliminary values subject to further data review/analysis; d) values shown are based on fast Fourier transform analyses of consecutive 1 second intervals for a total period of 10 minutes during pile driving on till/rock (600 seconds) and represent the maximum of the 1 second interval peak velocity values during these periods regardless of measurement direction; e) see monitoring notes above.

# NORTH KENT 1

## Preliminary Vibration Monitoring Report

**Turbine Location:** T21

| Vibration Measurements at Turbine Site |                    |                 |                  |                    |                                 | Vibration Measurements at Wells          |         |                      |
|--|--------------------|-----------------|------------------|--------------------|---------------------------------|--|---------|----------------------|
| Pile Driving Times and Dates           |                    |                 |                  | Geophone Dist. (m) | Daily Maximum Particle Velocity | Particle Velocity (mm/s) <sup>c, d</sup> |         |                      |
| Pile No.:                              | Start <sup>a</sup> | Rock/Till       | End <sup>a</sup> |                    | (mm/s) <sup>b</sup>             | Well 11                                  | Well 12 | No Pump <sup>e</sup> |
| 1                                      | 8/29/2017 12:01    | 8/29/2017 12:04 | 8/29/2017 12:14  | 23.7               | 2.79                            | NA <sup>e</sup>                          | 0.008   |                      |
| 2                                      | 8/29/2017 1:27     | 8/29/2017 1:30  | 8/29/2017 1:39   | 25.4               | 2.79                            | 0.003                                    | 0.006   |                      |
| 3                                      | 8/29/2017 1:44     | 8/29/2017 1:47  | 8/29/2017 1:54   | 26.4               | 2.79                            | 0.009                                    | 0.006   |                      |
| 4                                      | 8/29/2017 11:20    | 8/29/2017 11:23 | 8/29/2017 11:32  | 26.8               | 2.79                            | 0.003                                    | 0.013   |                      |
| 5                                      | 8/29/2017 11:05    | 8/29/2017 11:08 | 8/29/2017 11:13  | 26.4               | 2.79                            | NA <sup>e</sup>                          | 0.013   |                      |
| 6                                      | 8/29/2017 8:48     | 8/29/2017 8:51  | 8/29/2017 8:59   | 25.4               | 2.79                            | NA <sup>e</sup>                          | 0.026   |                      |
| 7                                      | 8/29/2017 8:28     | 8/29/2017 8:33  | 8/29/2017 8:40   | 23.7               | 2.79                            | NA <sup>e</sup>                          | 0.005   |                      |
| 8                                      | 8/29/2017 8:07     | 8/29/2017 8:11  | 8/29/2017 8:19   | 21.5               | 2.79                            | NA <sup>e</sup>                          | 0.003   |                      |
| 9                                      | 8/29/2017 7:51     | 8/29/2017 7:54  | 8/29/2017 7:59   | 18.8               | 2.79                            | 0.004                                    | 0.004   |                      |
| 10                                     | 8/28/2017 16:40    | 8/28/2017 16:44 | 8/28/2017 16:53  | 15.9               | 3.30                            | 0.015                                    | 0.071   |                      |
| 11                                     | 8/28/2017 16:11    | 8/28/2017 16:14 | 8/28/2017 16:27  | 13.0               | 3.30                            | 0.007                                    | 1.551   | 0.039                |
| 12                                     | 8/28/2017 15:51    | 8/28/2017 15:58 | 8/28/2017 16:05  | 10.8               | 3.30                            | 0.005                                    | 0.007   |                      |
| 13                                     | 8/28/2017 14:27    | 8/28/2017 14:30 | 8/28/2017 14:37  | 9.9                | 3.30                            | 0.003                                    | 0.005   |                      |
| 14                                     | 8/28/2017 14:10    | 8/28/2017 14:13 | 8/28/2017 14:21  | 10.8               | 3.30                            | 0.006                                    | 0.005   |                      |
| 15                                     | 8/28/2017 13:45    | 8/28/2017 13:48 | 8/28/2017 13:58  | 13.0               | 3.30                            | 0.008                                    | 0.013   |                      |
| 16                                     | 8/28/2017 13:21    | 8/28/2017 13:24 | 8/28/2017 13:37  | 15.9               | 3.30                            | 0.006                                    | 0.011   |                      |
| 17                                     | 8/28/2017 13:01    | 8/28/2017 13:05 | 8/28/2017 13:13  | 18.8               | 3.30                            | 0.011                                    | 0.010   |                      |
| 18                                     | 8/29/2017 11:44    | 8/29/2017 11:47 | 8/29/2017 11:54  | 21.5               | 2.79                            | NA <sup>e</sup>                          | 0.031   |                      |

### Restrikes

### Well Information

**Well No.:** 11

Municipal Address:

Distance from Turbine Centre: 3960 m

**Well No.:** 12

Municipal Address:

Distance from Turbine Centre: 4161 m

ISO 2631-2 particle velocity threshold for human perception is 0.1 mm/s between approximately 8 to 100 Hz

Background values at T5 and T42 test pile sites and Wells 1 and 2, when other common activities observed ranged from <0.01 to approximately 0.07 mm/s

**Monitoring Notes:** Vibration measurements were undertaken on August 17, 2017 at Wells 11 and 12 during water quality sampling events in the absence of pile driving within the cluster. Both pumps turned on and operated during the sampling events. Maximum vibration measurement for Well 11 was 0.016 mm/s and this pump was located within the residence approximately 40 m from the well. Maximum vibration measurement for Well 12 was 0.896 mm/s and the pump was mounted on the well casing. During pile driving on August 23, 2017, the maximum vibration measurement of the Well 12 casing was 2.4 mm/s for clearly definable periods during which the pump was operating. Data shown for the "no pump" condition was obtained during pile driving when the pump was not operating. Data not available for Piles 1, 5, 6, 7, 8 and 18 at Well 11 on August 29, 2017 due to battery failure in monitoring equipment. Battery was subsequently replaced. Total pile driving durations derived from start and end times noted above includes labour breaks, equipment work, splicing, welding and other standby time.

**Footnotes:** a) start and end of pile driving are start and stop times for active hammering; b) values shown are maximum daily values regardless of direction; c) preliminary values subject to further data review/analysis; d) values shown are based on fast Fourier transform analyses of consecutive 1 second intervals for a total period of 10 minutes during pile driving on till/rock (600 seconds) and represent the maximum of the 1 second interval peak velocity values during these periods regardless of measurement direction; e) see monitoring notes above.

## Preliminary Vibration Monitoring Report

Turbine Location: T28

| Vibration Measurements at Turbine Site |                    |                 |                  |                    |                                 | Vibration Measurements at Wells          |         |                      |
|--|--------------------|-----------------|------------------|--------------------|---------------------------------|--|---------|----------------------|
| Pile Driving Times and Dates           |                    |                 |                  |                    | Daily Maximum Particle Velocity | Particle Velocity (mm/s) <sup>c, d</sup> |         |                      |
| Pile No.:                              | Start <sup>a</sup> | Rock/Till       | End <sup>a</sup> | Geophone Dist. (m) | (mm/s) <sup>b</sup>             | Well 9                                   | Well 10 | No Pump <sup>e</sup> |
| 1                                      | 8/15/2017 14:33    | 8/15/2017 14:41 | 8/15/2017 14:43  | 21.6               | 3.17                            | 0.061                                    | 0.020   |                      |
| 2                                      | 8/15/2017 14:53    | 8/15/2017 15:04 | 8/15/2017 15:06  | 23.9               | 3.17                            | 0.019                                    | 0.036   |                      |
| 3                                      | 8/15/2017 15:31    | 8/15/2017 15:42 | 8/15/2017 15:44  | 25.6               | 3.17                            | 0.111                                    | 0.805   | 0.019                |
| 4                                      | 8/15/2017 13:23    | 8/15/2017 13:37 | 8/15/2017 13:39  | 26.6               | 3.17                            | 0.022                                    | 0.804   | 0.100                |
| 5                                      | 8/15/2017 12:10    | 8/15/2017 12:22 | 8/15/2017 12:24  | 27.0               | 3.17                            | 0.108                                    | 0.158   |                      |
| 6                                      | 8/15/2017 11:46    | 8/15/2017 11:59 | 8/15/2017 12:00  | 26.6               | 3.17                            | 0.012                                    | 0.095   |                      |
| 7                                      | 8/15/2017 9:56     | 8/15/2017 10:08 | 8/15/2017 10:11  | 25.6               | 3.17                            | 0.027                                    | 0.052   |                      |
| 8                                      | 8/15/2017 9:16     | 8/15/2017 9:34  | 8/15/2017 9:36   | 23.9               | 3.17                            | 0.040                                    | 0.009   |                      |
| 9                                      | 8/15/2017 8:51     | 8/15/2017 9:03  | 8/15/2017 9:04   | 21.6               | 3.17                            | 0.046                                    | 0.015   |                      |
| 10                                     | 8/15/2017 8:18     | 8/15/2017 8:33  | 8/15/2017 8:35   | 19.0               | 3.17                            | NA <sup>e</sup>                          | 0.750   | 0.026                |
| 11                                     | 8/15/2017 7:45     | 8/15/2017 7:58  | 8/15/2017 8:02   | 16.1               | 3.17                            | NA <sup>e</sup>                          | 0.007   |                      |
| 12                                     | 8/11/2017 13:27    | 8/11/2017 14:45 | 8/11/2017 14:46  | 13.2               | 5.59                            | 0.812                                    | 0.014   |                      |
| 13                                     | 8/11/2017 12:36    | 8/11/2017 12:48 | 8/11/2017 12:50  | 11.0               | 5.59                            | 0.054                                    | 0.006   |                      |
| 14                                     | 8/11/2017 12:13    | 8/11/2017 12:25 | 8/11/2017 12:27  | 10.1               | 5.59                            | 0.055                                    | 0.112   |                      |
| 15                                     | 8/11/2017 11:19    | 8/11/2017 11:28 | 8/11/2017 11:30  | 11.0               | 5.59                            | 0.244                                    | 0.015   |                      |
| 16                                     | 8/11/2017 11:48    | 8/11/2017 12:02 | 8/11/2017 12:03  | 13.2               | 5.59                            | 0.183                                    | 0.007   |                      |
| 17                                     | 8/11/2017 10:22    | 8/11/2017 11:06 | 8/11/2017 11:07  | 16.1               | 5.59                            | 0.686                                    | 0.034   |                      |
| 18                                     | 8/15/2017 13:56    | 8/15/2017 14:09 | 8/15/2017 14:10  | 19.0               | 3.17                            | 0.015                                    | 0.705   | 0.052                |
| <b>Restrikes</b>                       |                    |                 |                  |                    |                                 |  |         |                      |
| 2                                      | 8/16/2017 8:19     | 8/16/2017 8:19  | 8/16/2017 8:23   | 23.9               | 2.65                            | 0.017                                    | 0.029   |                      |

## Well Information

Well No.: 9 [REDACTED]  
Municipal Address: [REDACTED]  
Distance from Turbine Centre: 2568 m

Well No.: 10 [REDACTED]  
Municipal Address: [REDACTED]  
Distance from Turbine Centre: 1769 m

ISO 2631-2 particle velocity threshold for human perception is 0.1 mm/s between approximately 8 to 100 Hz

Background values at T5 and T42 test pile sites and Wells 1 and 3, when other common activities observed ranged from <0.01 to approximately 0.07 mm/s

**Monitoring Notes:** After installation, selected piles were struck again with the hammer to demonstrate resistance performance and these are noted as "restrikes". Data for Well 9 was not available for August 15, 2017 during driving of piles 10 and 11 while awaiting site security changes implemented following an incident at the Well 9 property the evening of August 14, 2017. Highlighted values for Well 9 on August 11, 2017 are higher than and inconsistent with other measurements during pile driving at the T28 site. On August 11, 2017, construction activities were underway along the entrance road to T32, located as close as about 100 m from Well 9. These activities included: hammering, movements of large construction equipment (e.g., loaders, dump trucks, excavators, "stone throwers"), and equipment travelled on access road site without construction mats, equipment operating on T32 access resulted in "pounding" sounds. The Well 9 area is also subject to heavy passing traffic on Countryview Line (74 m from well) including: fuel trucks, loaded dump trucks, large transport trucks, a bus, and cranes/boom trucks among other vehicles. Further analysis of Well 9 vibration data was undertaken for 10 minute periods on August 11, 2017 during which pile driving was not occurring between 08:32:00 and 08:42:00, 09:12:00 and 09:22:00, 11:22:00 and 11:32:00, and 13:48:00 and 13:58:00. During these periods the maximum velocities (regardless of direction) of the Well 9 casing ranged from 0.011 to 1.2 mm/s. Data shown for Well 9 during driving of Piles 12, 15, 16 and 17 (highlighted) are considered unrepresentative of pile driving and associated with other vibration sources. The piston pump for Well 9 is within the barn approximately 4 to 5 m from the well location. When the Well 9 pump was deliberately operated on September 8, 2017, in the absence of pile driving, well casing velocities were up to 0.04 mm/s. When the pump for Well 10 was operating, well casing vibrations of as much as 1.25 mm/s were measured. "No pump" data is provided to indicate measurements exclusive of data consistent with typical pump operations. Total pile driving durations derived from start and end times noted above includes labour breaks, equipment work, splicing, welding and other standby time.

## Preliminary Vibration Monitoring Report

**Footnotes:** a) start and end of pile driving are start and stop times for active hammering; b) values shown are maximum daily values regardless of direction; c) preliminary values subject to further data review/analysis; d) values shown are based on fast Fourier transform analyses of consecutive 1 second intervals for a total period of 10 minutes during pile driving on till/rock (600 seconds) and represent the maximum of the 1 second interval peak velocity values during these periods regardless of measurement direction; e) see monitoring notes above.



## Preliminary Vibration Monitoring Report

Turbine Location: T30

| Vibration Measurements at Turbine Site |                    |                |                  |                    |   | Vibration Measurements at Wells          |         |                      |
|--|--------------------|----------------|------------------|--------------------|---|--|---------|----------------------|
| Pile Driving Times and Dates           |                    |                |                  |                    |   | Particle Velocity (mm/s) <sup>c, d</sup> |         |                      |
| Pile No.:                              | Start <sup>a</sup> | Rock/Till      | End <sup>a</sup> | Geophone Dist. (m) | Daily Maximum Particle Velocity (mm/s) <sup>b</sup> | Well 9                                   | Well 10 | No Pump <sup>e</sup> |
| 1                                      | 8/4/2017 14:24     | 8/4/2017 14:42 | 8/4/2017 15:01   | 23.0               | 4.70  | 0.054                                    | 0.815   | 0.014                |
| 1A                                     | 8/9/2017 9:30      | 8/9/2017 9:51  | 8/9/2017 9:58    | 23.5               | 2.41  | 0.080                                    | 0.935   | 0.027                |
| 2                                      | 8/8/2017 8:42      | 8/8/2017 8:52  | 8/8/2017 9:03    | 24.6               | 3.17  | 0.061                                    | 0.049   |                      |
| 3                                      | 8/8/2017 9:17      | 8/8/2017 9:25  | 8/8/2017 9:35    | 25.6               | 3.17  | 0.041                                    | 0.883   | 0.009                |
| 4                                      | 8/8/2017 7:49      | 8/8/2017 8:02  | 8/8/2017 8:10    | 26.0               | 3.17  | 0.035                                    | 1.251   | 0.036                |
| 5                                      | 8/4/2017 16:24     | 8/4/2017 16:32 | 8/4/2017 16:40   | 25.6               | 4.70  | 0.061                                    | 0.007   |                      |
| 6                                      | 8/4/2017 15:57     | 8/4/2017 16:03 | 8/4/2017 16:11   | 24.6               | 4.70  | 0.059                                    | 0.003   |                      |
| 7                                      | 8/4/2017 15:24     | 8/4/2017 15:34 | 8/4/2017 15:39   | 23.0               | 4.70  | 0.082                                    | 0.028   |                      |
| 8                                      | 8/4/2017 10:57     | 8/4/2017 11:03 | 8/4/2017 11:06   | 20.8               | 4.70  | 0.032                                    | 0.540   | 0.033                |
| 9                                      | 8/3/2017 13:33     | 8/3/2017 13:38 | 8/3/2017 13:46   | 18.1               | 5.33  | 0.076                                    | 0.088   |                      |
| 10                                     | 8/3/2017 13:07     | 8/3/2017 13:16 | 8/3/2017 13:20   | 15.2               | 5.33  | 0.088                                    | 0.014   |                      |
| 11                                     | 8/3/2017 11:46     | 8/3/2017 11:52 | 8/3/2017 11:56   | 9.1                | 5.33  | 0.029                                    | 0.007   |                      |
| 12                                     | 8/3/2017 11:25     | 8/3/2017 11:29 | 8/3/2017 11:34   | 10.1               | 5.33  | 0.066                                    | 0.005   |                      |
| 13                                     | 8/3/2017 10:44     | 8/3/2017 10:53 | 8/3/2017 10:59   | 12.4               | 5.33  | 0.059                                    | 0.876   | 0.005                |
| 14                                     | 8/3/2017 14:04     | 8/3/2017 14:11 | 8/3/2017 14:19   | 15.2               | 5.33  | 0.061                                    | 0.023   |                      |
| 15                                     | 8/3/2017 14:34     | 8/3/2017 14:47 | 8/3/2017 14:50   | 18.1               | 5.33  | 0.032                                    | 0.005   |                      |
| 16                                     | 8/4/2017 8:50      | 8/4/2017 8:55  | 8/4/2017 9:08    | 20.8               | 4.70  | 0.048                                    | 0.032   |                      |
| 17                                     | 8/4/2017 9:32      | 8/4/2017 9:38  | 8/4/2017 9:43    | 23.0               | 4.70  | 0.051                                    | 0.002   |                      |
| 18                                     | 8/4/2017 10:17     | 8/4/2017 10:33 | 8/4/2017 10:36   | 24.6               | 4.70  | 0.024                                    | 0.004   |                      |
| <b>Restrikes</b>                       |                    |                |                  |                    |   |  |         |                      |
| 15C                                    | 8/4/2017 8:15      | 8/4/2017 8:15  | 8/4/2017 8:21    | 18.1               | 4.70  | 0.044                                    | 0.022   |                      |
| 1                                      | 8/8/2017 15:19     | 8/8/2017 15:19 | 8/8/2017 15:25   | 23.0               | 3.17  | 0.080                                    | 0.006   |                      |
| 5                                      | 8/8/2017 8:15      | 8/8/2017 8:15  | 8/8/2017 8:20    | 25.6               | 3.17  | 0.056                                    | 1.016   | 0.006                |
| 6                                      | 8/8/2017 9:40      | 8/8/2017 9:40  | 8/8/2017 9:41    | 24.6               | 3.17  | 0.041                                    | 1.116   | 0.146                |

## Well Information

Well No.: 9 [REDACTED]  
Municipal Address: [REDACTED]  
Distance from Turbine Centre: 1808 m

Well No.: 10 [REDACTED]  
Municipal Address: [REDACTED]  
Distance from Turbine Centre: 1385 m

ISO 2631-2 particle velocity threshold for human perception is 0.1 mm/s between approximately 8 to 100 Hz

Background values at T5 and T42 test pile sites and Wells 1 and 3, when other common activities observed ranged from <0.01 to approximately 0.07 mm/s

**Monitoring Notes:** Piles noted with "A" represent piles installed to replace similarly-numbered piles. After installation, selected piles were struck again with the hammer to demonstrate resistance performance and these are noted as "restrikes" (where applicable). Piles noted with "C" were those that were started on one day and continued on a separate day; therefore, additional well monitoring data is presented for the time periods during which piling continued on till/rock. When the pump for Well 10 was operating, well casing vibrations of as much as 1.25 mm/s were measured. "No pump" data is provided to indicate measurements exclusive of data consistent with typical pump operations. Total driving duration between till/rock start and end times noted above for Pile 1 is not representative and actual driving duration was 00:11:50 due to pauses in actual hammering. Total pile driving durations derived from start and end times noted above includes labour breaks, equipment work, splicing, welding and other standby time.

**Footnotes:** a) start and stop of pile driving are start and stop times for active hammering; b) values shown are maximum daily values regardless of direction; c) preliminary values subject to further data review/analysis; d) values shown are based on fast Fourier transform analyses of consecutive 1 second intervals for a total period of 10 minutes during pile driving on till/rock (600 seconds) and represent the maximum of the 1 second interval peak velocity values during these periods regardless of measurement direction; e) see monitoring notes above.

## Preliminary Vibration Monitoring Report

Turbine Location: T31

| Vibration Measurements at Turbine Site |                    |                 |                  |                    | Vibration Measurements at Wells |  |        |
|--|--------------------|-----------------|------------------|--------------------|---------------------------------|--|--------|
| Pile Driving Times and Dates           |                    |                 |                  |                    | Daily Maximum Particle Velocity | Particle Velocity (mm/s) <sup>c, d</sup> |        |
| Pile No.:                              | Start <sup>a</sup> | Rock/Till       | End <sup>a</sup> | Geophone Dist. (m) | (mm/s) <sup>b</sup>             | Well 7                                   | Well 8 |
| 1                                      | 7/17/2017 13:18    | 7/17/2017 13:24 | 7/17/2017 13:26  | 8.1                | 2.92                            | 0.042                                    | 0.028  |
| 2                                      | 7/17/2017 14:46    | 7/17/2017 14:52 | 7/17/2017 14:54  | 9.1                | 2.92                            | 0.038                                    | 0.034  |
| 3                                      | 7/18/2017 7:39     | 7/18/2017 7:47  | 7/18/2017 7:49   | 11.4               | 4.19                            | 0.016                                    | 0.075  |
| 4                                      | 7/18/2017 8:03     | 7/18/2017 8:10  | 7/18/2017 8:13   | 14.3               | 4.19                            | 0.023                                    | 0.005  |
| 5                                      | 7/17/2017 12:56    | 7/17/2017 13:01 | 7/17/2017 13:05  | 17.2               | 2.92                            | 0.020                                    | 0.071  |
| 6                                      | 7/17/2017 11:49    | 7/17/2017 11:53 | 7/17/2017 11:54  | 19.8               | 2.92                            | 0.100                                    | 0.099  |
| 7                                      | 7/17/2017 11:25    | 7/17/2017 11:30 | 7/17/2017 11:35  | 22.0               | 2.92                            | 0.014                                    | 0.028  |
| 8                                      | 7/17/2017 10:25    | 7/17/2017 10:31 | 7/17/2017 10:36  | 23.6               | 2.92                            | 0.044                                    | 0.028  |
| 9                                      | 7/17/2017 8:03     | 7/17/2017 8:09  | 7/17/2017 8:30   | 24.6               | 2.92                            | 0.011                                    | 0.041  |
| 10                                     | NA                 | NA              | NA               | 25.0               |                                 | NA                                       | NA     |
| 11                                     | 7/14/2017 16:18    | 7/14/2017 16:25 | 7/14/2017 16:28  | 24.6               | 5.46                            | 0.041                                    | NA     |
| 12                                     | 7/13/2017 15:38    | 7/13/2017 15:44 | 7/13/2017 15:45  | 23.6               | 5.08                            | 0.037                                    | 0.034  |
| 13                                     | 7/13/2017 16:12    | 7/13/2017 16:26 | 7/13/2017 16:30  | 24.6               | 5.08                            | 0.012                                    | 0.015  |
| 14                                     | 7/14/2017 8:22     | 7/14/2017 8:47  | 7/14/2017 8:48   | 25.0               | 5.46                            | 0.072                                    | 0.023  |
| 15                                     | 7/13/2017 16:56    | 7/13/2017 17:06 | 7/13/2017 17:08  | 24.6               | 5.08                            | 0.156                                    | 0.020  |
| 16                                     | 7/14/2017 11:18    | 7/14/2017 11:23 | 7/14/2017 11:29  | 23.6               | 5.46                            | 0.044                                    | 0.034  |
| 17                                     | 7/14/2017 11:40    | 7/14/2017 11:48 | 7/14/2017 11:51  | 22.0               | 5.46                            | 0.074                                    | 0.075  |
| 18                                     | 7/14/2017 12:10    | 7/14/2017 12:16 | 7/14/2017 12:21  | 19.8               | 5.46                            | 0.050                                    | 0.041  |

## Well Information

Well No.: 7

Municipal Address:

Distance from Turbine Centre: 636 m

Well No.: 8

Municipal Address:

Distance from Turbine Centre: 2497 m

ISO 2631-2 particle velocity threshold for human perception is 0.1 mm/s between approximately 8 to 100 Hz

Background values at T5 and T42 test pile sites and Wells 1 and 3, when other common activities observed ranged from &lt;0.01 to approximately 0.07 mm/s

**Monitoring Notes:** On July 14, 2017 at about 14:00, Golder was informed that piling operations at T31 were concluded. At 15:45 instruments were therefore turned off at Well 8 in preparation for removal for the day. Piling resumed at approximately 16:15. As a result, data was not captured for Wells 7 or 8 when driving Pile 10 and Well 8 when driving Pile 11. Well monitoring undertaken during periods of time when pile driving was not occurring measured maximum particle velocities of as much as 0.37 mm/s at Well 7. Total driving duration between till/rock start and end times noted above for Pile 9 is not representative and actual driving duration was 00:04:00 due to pauses in actual hammering. Total pile driving durations derived from start and end times noted above includes labour breaks, equipment work, splicing, welding and other standby time.

**Footnotes:** a) start and stop of pile driving are start and stop times for active hammering; b) values shown are maximum daily values regardless of direction; c) preliminary values subject to further data review/analysis; d) values shown are based on fast Fourier transform analyses of consecutive 1 second intervals for a total period of 10 minutes during pile driving on till/rock (600 seconds) and represent the maximum of the 1 second interval peak velocity values during these periods regardless of measurement direction.

## Preliminary Vibration Monitoring Report

Turbine Location: T32

## Vibration Measurements at Turbine Site

## Vibration Measurements at Wells

| Pile Driving Times and Dates |                    |                 |                  | Daily Maximum Particle Velocity |                     | Particle Velocity (mm/s) <sup>c, d</sup> |         |                      |
|------------------------------|--------------------|-----------------|------------------|---------------------------------|---------------------|--|---------|----------------------|
| Pile No.:                    | Start <sup>a</sup> | Rock/Till       | End <sup>a</sup> | Geophone Dist. (m)              | (mm/s) <sup>b</sup> | Well 9                                   | Well 10 | No Pump <sup>e</sup> |
| 1                            | 8/11/2017 14:41    | 8/11/2017 14:43 | 8/11/2017 15:01  | 25.0                            | 3.43                | 0.069                                    | 0.020   |                      |
| 2                            | 8/14/2017 15:43    | 8/14/2017 15:46 | 8/14/2017 16:19  | 23.3                            | 4.83                | 0.050                                    | 0.013   |                      |
| 3                            | 8/14/2017 16:25    | 8/14/2017 16:28 | 8/14/2017 16:57  | 21.1                            | 4.83                | 0.045                                    | 0.045   |                      |
| 4                            | 8/14/2017 14:51    | 8/14/2017 14:55 | 8/14/2017 15:21  | 18.4                            | 4.83                | 0.046                                    | 0.697   |                      |
| 5                            | 8/14/2017 13:52    | 8/14/2017 13:55 | 8/14/2017 14:11  | 15.5                            | 4.83                | 0.059                                    | 0.035   |                      |
| 6                            | 8/14/2017 13:12    | 8/14/2017 13:15 | 8/14/2017 13:33  | 12.7                            | 4.83                | 0.055                                    | 0.009   |                      |
| 7                            | 8/14/2017 11:40    | 8/14/2017 11:42 | 8/14/2017 12:18  | 10.4                            | 4.83                | 0.062                                    | 0.049   |                      |
| 8                            | 8/14/2017 11:20    | 8/14/2017 11:23 | 8/14/2017 11:33  | 9.5                             | 4.83                | 0.050                                    | 0.880   |                      |
| 9                            | 8/14/2017 7:47     | 8/14/2017 7:50  | 8/14/2017 7:54   | 10.4                            | 4.83                | 0.041                                    | 0.733   |                      |
| 10                           | 8/14/2017 10:59    | 8/14/2017 11:04 | 8/14/2017 11:12  | 12.7                            | 4.83                | 0.028                                    | 0.010   |                      |
| 11                           | 8/11/2017 10:53    | 8/11/2017 10:56 | 8/11/2017 11:00  | 15.5                            | 3.43                | 1.090                                    | 0.049   |                      |
| 12                           | 8/11/2017 10:42    | 8/11/2017 10:44 | 8/11/2017 10:47  | 18.4                            | 3.43                | 0.871                                    | 0.014   |                      |
| 13                           | 8/11/2017 10:28    | 8/11/2017 10:30 | 8/11/2017 10:34  | 21.1                            | 3.43                | 1.346                                    | 0.738   | 0.005                |
| 14                           | 8/11/2017 10:14    | 8/11/2017 10:19 | 8/11/2017 10:21  | 23.3                            | 3.43                | 0.068                                    | 0.051   |                      |
| 15                           | 8/11/2017 9:00     | 8/11/2017 9:03  | 8/11/2017 9:07   | 25.0                            | 3.43                | 0.037                                    | 0.764   | 0.004                |
| 16                           | 8/11/2017 11:07    | 8/11/2017 11:10 | 8/11/2017 11:14  | 26.0                            | 3.43                | 0.229                                    | 0.034   |                      |
| 17                           | 8/11/2017 13:12    | 8/11/2017 13:14 | 8/11/2017 13:19  | 26.4                            | 3.43                | 0.230                                    | 0.684   | 0.009                |
| 18                           | 8/11/2017 13:26    | 8/11/2017 13:28 | 8/11/2017 13:42  | 26.0                            | 3.43                | 0.135                                    | 0.713   | 0.004                |

## Restrikes

## Well Information

Well No.: 9  
Municipal Address: [REDACTED]  
Distance from Turbine Centre: 680 m

Well No.: 10  
Municipal Address: [REDACTED]  
Distance from Turbine Centre: 1122 m

ISO 2631-2 particle velocity threshold for human perception is 0.1 mm/s between approximately 8 to 100 Hz

Background values at T5 and T42 test pile sites and Wells 1 and 3, when other common activities observed ranged from <0.01 to approximately 0.07 mm/s

**Monitoring Notes:** Highlighted values for Well 9 on August 11, 2017 are higher than and inconsistent with other measurements during pile driving at the T32 site. On August 11, 2017, construction activities were underway along the entrance road to T32, located as close as about 100 m from the well. These activities included: hammering, movements of large construction equipment (e.g., loaders, dump trucks, excavators, aggregate delivery equipment), and equipment travelled on site access road without construction mats, equipment operating on T32 access road resulted in "pounding" sounds. Well 9 area is subject to heavy passing traffic on Countryview Line (74 m from well) including: fuel trucks, loaded dump trucks, large transport trucks, a bus, and cranes/boom trucks among other vehicles. Further analysis of Well 9 vibration data was undertaken for 10 minute periods on August 11, 2017 during which pile driving was not occurring between 08:32:00 and 08:42:00, 09:12:00 and 09:22:00, 11:22:00 and 11:32:00, and 13:48:00 and 13:58:00. During these periods, the maximum velocities (regardless of direction) of the Well 9 casing ranged from 0.011 to 1.2 mm/s. Data shown for Well 9 during driving of Piles 12, 15, 16 and 17 (highlighted) are considered unrepresentative of pile driving and associated with other vibration sources. The piston pump for Well 9 is within the barn approximately 4 to 5 m from the well location. When the Well 9 pump was deliberately operated on September 8, 2017, in the absence of pile driving, well casing velocities were up to 0.04 mm/s. When the pump for Well 10 was operating, well casing vibrations of as much as 1.25 mm/s were measured. "No pump" data is provided to indicate measurements exclusive of data consistent with typical pump operations. Total pile driving durations derived from start and end times noted above includes labour breaks, equipment work, splicing, welding and other standby time.

**Footnotes:** a) start and stop of pile driving are start and stop times for active hammering; b) values shown are maximum daily values regardless of direction; c) preliminary values subject to further data review/analysis; d) values shown are based on fast Fourier transform analyses of consecutive 1 second intervals for a total period of 10 minutes during pile driving on till/rock (600 seconds) and represent the maximum of the 1 second interval peak velocity values during these periods regardless of measurement direction; e) see monitoring notes above.

## Preliminary Vibration Monitoring Report

Turbine Location: T33

## Vibration Measurements at Turbine Site

## Vibration Measurements at Wells

| Pile Driving Times and Dates |                    |                |                  |                    | Daily Maximum<br>Particle Velocity<br>(mm/s) <sup>b</sup> | Particle Velocity (mm/s) <sup>c, d</sup> |        |                      |
|------------------------------|--------------------|----------------|------------------|--------------------|---|--|--------|----------------------|
| Pile No.:                    | Start <sup>a</sup> | Rock/Till      | End <sup>a</sup> | Geophone Dist. (m) |   | Well 3                                   | Well 4 | No Pump <sup>e</sup> |
| 1                            | 9/5/2017 13:10     | 9/5/2017 13:16 | 9/5/2017 13:25   | 10.9               | 5.3   | 0.015                                    | 0.118  |                      |
| 2                            | 9/5/2017 13:46     | 9/5/2017 13:55 | 9/5/2017 14:03   | 11.8               | 5.3   | 0.011                                    | 0.138  |                      |
| 3                            | 9/5/2017 14:11     | 9/5/2017 14:20 | 9/5/2017 14:27   | 14.0               | 5.3   | 0.056                                    | 0.174  |                      |
| 4                            | 9/5/2017 14:38     | 9/5/2017 14:46 | 9/5/2017 14:54   | 16.8               | 5.3   | 0.035                                    | 0.082  |                      |
| 5                            | 9/5/2017 15:05     | 9/5/2017 15:13 | 9/5/2017 15:18   | 19.7               | 5.3   | 0.049                                    | 0.137  |                      |
| 6                            | 9/5/2017 15:34     | 9/5/2017 15:44 | 9/5/2017 15:48   | 22.4               | 5.3   | 0.009                                    | 0.072  |                      |
| 7                            | 9/5/2017 17:02     | 9/5/2017 17:10 | 9/5/2017 17:10   | 24.6               | 5.3   | 0.030                                    | 0.298  |                      |
| 8                            | 9/5/2017 17:32     | 9/5/2017 17:41 | 9/5/2017 17:49   | 26.3               | 5.3   | 0.036                                    | 0.131  |                      |
| 9                            | 9/5/2017 18:14     | 9/5/2017 18:21 | 9/5/2017 18:28   | 27.4               | 5.3   | 0.034                                    | 0.083  |                      |
| 10                           | 9/6/2017 9:30      | 9/6/2017 9:47  | 9/6/2017 9:53    | 27.8               | 3.2   | 0.004                                    | 0.243  |                      |
| 11                           | 9/6/2017 10:09     | 9/6/2017 10:25 | 9/6/2017 10:35   | 27.4               | 3.2   | 0.004                                    | 0.089  |                      |
| 12                           | 9/6/2017 12:03     | 9/6/2017 12:16 | 9/6/2017 12:26   | 26.3               | 3.2   | 0.005                                    | 0.179  |                      |
| 13                           | 9/6/2017 12:58     | 9/6/2017 13:08 | 9/6/2017 13:16   | 24.6               | 3.2   | 0.003                                    | 0.162  |                      |
| 14                           | 9/6/2017 13:33     | 9/6/2017 13:43 | 9/6/2017 13:58   | 22.4               | 3.2   | 0.004                                    | 0.161  |                      |
| 15                           | 9/6/2017 14:37     | 9/6/2017 14:45 | 9/6/2017 14:54   | 19.7               | 3.2   | 0.005                                    | 4.987  |                      |
| 16                           | 9/6/2017 16:01     | 9/6/2017 16:08 | 9/6/2017 16:20   | 16.8               | 3.2   | 0.006                                    | 0.277  |                      |
| 17                           | 9/6/2017 15:29     | 9/6/2017 15:35 | 9/6/2017 15:45   | 14.0               | 3.2   | 0.003                                    | 0.175  |                      |
| 18                           | 9/6/2017 14:13     | 9/6/2017 14:24 | 9/6/2017 14:36   | 11.8               | 3.2   | 0.004                                    | 0.622  |                      |
| <b>Restrikes</b>             |                    |                |                  |                    |   |  |        |                      |
| 6                            | 9/6/2017 18:15     | 9/6/2017 18:15 | 9/6/2017 18:23   | 22.4               | 3.2   | 0.009                                    | 4.858  |                      |
| 5                            | 9/6/2017 17:02     | 9/6/2017 17:02 | 9/6/2017 17:03   | 19.7               | 3.2   | 0.023                                    | 0.129  |                      |

## Well Information

Well No.: 3  
Municipal Address: [REDACTED]  
Distance from Turbine Centre: 1778 m

Well No.: 4  
Municipal Address: [REDACTED]  
Distance from Turbine Centre: 2080 m

ISO 2631-2 particle velocity threshold for human perception is 0.1 mm/s between approximately 8 to 100 Hz

Background values at T5 and T42 test pile sites and Wells 1 and 2, when other common activities observed ranged from <0.01 to approximately 0.07 mm/s

**Monitoring Notes:** After installation, selected piles were struck again with the hammer to demonstrate resistance performance and these are noted as "restrikes". Total pile driving durations derived from start and end times noted above includes labour breaks, equipment work, splicing, welding and other standby time. During vibration monitoring on September 5, 2017, a forklift operated close to the geophone between 16:00:00 and 16:30:00 and triggered a maximum peak particle velocity of 6.2 mm/s. Value shown above excludes the peak measurement triggered by the forklift. On September 5, 2017, tractors, harvest haul trucks and other equipment travelled through Well 3 property frequently from 12:48 to 15:55 and occasionally thereafter until 16:50. On September 5, 2017, St. Clair Road traffic passing at 78 m from Well 4 was observed to include large tractor-trailers, concrete mixers and dump trucks at a rate of about 1 heavy vehicle every 1.5 to 2 minutes. Passenger vehicle movements on the Well 4 property passed and were parked near the well at 12:10, 14:40, 14:47, 15:06, 15:17, 15:42, 16:16, 16:35 and 19:02. On September 6, 2017, heavy vehicle traffic near Well 4 was similar to September 5, 2017. Combine harvesting was on-going as close as 25 to 30 m from Well 4, starting at 8:53 and continuing to after 14:30 on September 6, 2017. Passenger vehicle traffic on September 6, 2017 adjacent to Well 4 on the property was noted at 7:41, 10:40 - 10:45, 10:56 - 11:04, 11:46 - 11:52, 12:57 - 12:59, 13:22, 14:31, 14:36, 16:35, 16:42, 16:49, and 18:34. Various individuals were at and in the well shed at 16:35 to 16:54. Prior to September 6, 2017 observations by Golder personnel indicated that a pump was not connected at Well 4. During the afternoon of September 6, 2017 a pump was connected and operational. From 17:02 to 17:18 the newly connected Well 4 pump was cycled on and off, operating for periods of 1 to more than 7 minutes. The owner was physically working on Well 4 after 17:18 and returning to well shed frequently. All data highlighted above is considered to have been significantly influenced by near-well activities, particularly work directly related to the Well 4 pump and shed.

**Footnotes:** a) start and stop of pile driving are start and stop times for active hammering; b) values shown are maximum daily values regardless of direction; c) preliminary values subject to further data review/analysis; d) values shown are based on fast Fourier transform analyses of consecutive 1 second intervals for a total period of 10 minutes during pile driving on till/rock (600 seconds) and represent the maximum of the 1 second interval peak velocity values during these periods regardless of measurement direction; e) see monitoring notes above.

## Preliminary Vibration Monitoring Report

Turbine Location: T35

| Vibration Measurements at Turbine Site |                              |                 |                  |                    |                                 | Vibration Measurements at Wells          |        |                      |
|--|------------------------------|-----------------|------------------|--------------------|---------------------------------|--|--------|----------------------|
| Pile No.:                              | Pile Driving Times and Dates |                 |                  | Geophone Dist. (m) | Daily Maximum Particle Velocity | Particle Velocity (mm/s) <sup>c, d</sup> |        |                      |
|  | Start <sup>a</sup>           | Rock/Till       | End <sup>a</sup> |                    | (mm/s) <sup>b</sup>             | Well 5                                   | Well 6 | No Pump <sup>e</sup> |
| 1                                      | 6/21/2017 9:16               | 6/21/2017 9:31  | 6/21/2017 9:58   | 25.3               | 4.32                            | 0.005                                    | 0.011  |                      |
| 1A                                     | 7/4/2017 14:09               | 7/4/2017 14:15  | 7/4/2017 14:20   | 25.8               | 4.70                            | 0.011                                    | 0.085  |                      |
| 2                                      | 6/28/2017 11:40              | 6/28/2017 11:50 | 6/28/2017 11:56  | 27.0               | 6.86                            | 0.004                                    | 0.002  |                      |
| 3                                      | 6/29/2017 11:15              | 6/29/2017 11:26 | 6/29/2017 11:37  | 28.1               | 4.70                            | 0.004                                    | 0.080  | 0.009                |
| 4                                      | 6/29/2017 11:45              | 6/29/2017 12:28 | 6/29/2017 12:35  | 28.4               | 4.70                            | 0.002                                    | 0.003  |                      |
| 5                                      | 6/29/2017 10:36              | 6/29/2017 10:53 | 6/29/2017 10:59  | 28.1               | 4.70                            | 0.003                                    | 0.008  |                      |
| 6                                      | 6/29/2017 9:49               | 6/29/2017 10:09 | 6/29/2017 10:19  | 27.0               | 4.70                            | 0.002                                    | 0.017  |                      |
| 7                                      | 6/28/2017 16:45              | 6/28/2017 16:55 | 6/28/2017 16:59  | 25.3               | 6.86                            | 0.002                                    | 0.006  |                      |
| 8                                      | 6/28/2017 16:19              | 6/28/2017 16:28 | 6/28/2017 16:36  | 23.0               | 6.86                            | 0.004                                    | 0.008  |                      |
| 9                                      | 6/29/2017 15:55              | 6/29/2017 16:03 | 6/29/2017 16:09  | 20.3               | 4.70                            | 0.003                                    | 0.011  |                      |
| 10                                     | 6/28/2017 15:23              | 6/28/2017 15:35 | 6/28/2017 15:43  | 17.4               | 6.86                            | 0.002                                    | 0.010  |                      |
| 11                                     | 6/28/2017 14:34              | 6/28/2017 14:52 | 6/28/2017 14:56  | 14.6               | 6.86                            | 0.002                                    | 0.081  | 0.011                |
| 12                                     | 6/28/2017 14:04              | 6/28/2017 14:19 | 6/28/2017 14:23  | 12.4               | 6.86                            | 0.003                                    | 0.016  |                      |
| 13                                     | 6/26/2017 16:52              | 6/26/2017 17:15 | 6/26/2017 17:22  | 11.6               | 4.06                            | 0.004                                    | 0.093  | 0.015                |
| 13A                                    | 6/30/2017 10:53              | 6/30/2017 11:24 | 6/30/2017 11:36  | 11.6               | 4.19                            | 0.001                                    | 0.093  | 0.015                |
| 14                                     | 6/28/2017 8:34               | 6/28/2017 8:59  | 6/28/2017 9:16   | 12.4               | 6.86                            | 0.005                                    | 0.110  | 0.023                |
| 15                                     | 6/26/2017 16:03              | 6/26/2017 16:26 | 6/26/2017 16:28  | 14.6               | 4.06                            | 0.002                                    | 0.009  |                      |
| 15A                                    | 7/4/2017 12:54               | 7/4/2017 13:00  | 7/4/2017 13:21   | 15.1               | 4.70                            | 0.008                                    | 0.130  |                      |
| 16                                     | 6/28/2017 9:32               | 6/28/2017 9:52  | 6/28/2017 9:57   | 17.4               | 6.86                            | 0.002                                    | 0.004  |                      |
| 17                                     | 6/26/2017 7:45               | 6/26/2017 8:19  | 6/26/2017 8:20   | 20.3               | 4.06                            | 0.012                                    | 0.002  |                      |
| 17A                                    | 7/4/2017 13:39               | 7/4/2017 13:45  | 7/4/2017 13:51   | 20.8               | 4.70                            | 0.004                                    | 0.105  |                      |
| 18                                     | 6/28/2017 10:40              | 6/28/2017 10:55 | 6/28/2017 11:25  | 23.0               | 6.86                            | 0.004                                    | 0.015  |                      |
| <b>Restrikes</b>                       |                              |                 |                  |                    |                                 |  |        |                      |
| 1                                      | 6/26/2017 7:39               | 6/26/2017 7:39  | 6/26/2017 7:39   | 25.3               | 4.06                            | 0.007                                    | 0.007  |                      |
| 17                                     | 6/28/2017 12:54              | 6/28/2017 12:54 | 6/28/2017 13:14  | 20.3               | 6.86                            | 0.004                                    | 0.014  |                      |
| 10                                     | 6/29/2017 13:31              | 6/29/2017 13:31 | 6/29/2017 13:32  | 17.4               | 4.70                            | 0.006                                    | 0.004  |                      |
| 13                                     | 6/29/2017 13:37              | 6/29/2017 13:37 | 6/29/2017 13:42  | 11.6               | 4.70                            | 0.004                                    | 0.002  |                      |
| 14                                     | 6/29/2017 13:47              | 6/29/2017 13:47 | 6/29/2017 13:50  | 12.4               | 4.70                            | 0.006                                    | 0.003  |                      |
| 16                                     | 6/29/2017 13:54              | 6/29/2017 13:54 | 6/29/2017 13:56  | 17.4               | 4.70                            | 0.005                                    | 0.003  |                      |
| 15                                     | 6/29/2017 14:20              | 6/29/2017 14:20 | 6/29/2017 14:25  | 14.6               | 4.70                            | 0.008                                    | 0.011  |                      |
| <b>PDA</b>                             |                              |                 |                  |                    |                                 |  |        |                      |
| 13A                                    | 7/6/2017 10:06               | 7/6/2017 10:06  | 7/6/2017 10:15   | 12.1               | 5.21                            | 0.005                                    | 0.138  |                      |
| 13                                     | 7/6/2017 11:05               | 7/6/2017 11:05  | 7/6/2017 11:23   | 11.6               | 5.21                            | 0.006                                    | 0.219  |                      |
| 15A                                    | 7/6/2017 11:39               | 7/6/2017 11:39  | 7/6/2017 11:40   | 15.1               | 5.21                            | 0.009                                    | 0.130  |                      |
| 17A                                    | 7/6/2017 11:55               | 7/6/2017 11:55  | 7/6/2017 11:56   | 20.8               | 5.21                            | 0.010                                    | 0.061  |                      |
| 1A                                     | 7/6/2017 12:18               | 7/6/2017 12:18  | 7/6/2017 12:18   | 25.8               | 5.21                            | 0.011                                    | 0.084  |                      |

**Well Information**

Well No.: 5

Municipal Address:

Distance from Turbine Centre: 623 m

Well No.: 6

Municipal Address:

Distance from Turbine Centre: 880 m

ISO 2631-2 particle velocity threshold for human perception is 0.1 mm/s between approximately 8 to 100 Hz

Background values at T5 and T42 test pile sites and Wells 1 and 3, when other common activities observed ranged from &lt;0.01 to approximately 0.07 mm/s

**Monitoring Notes:** Tractor was observed operating frequently near Well 6. Water pump was observed cycling on and off during pile driving operations and remaining on for periods of 2 to 4 minutes. When pump was operating, casing at Well 6 exhibited particle velocities in the range of 0.08 to 0.12 mm/s and dominated analysis of data. Pile restrike events were of short duration with the following total number of hammer blows shown in parentheses: Pile 1 (20), Pile 10 (5 to 7), 13 (205), 14 (140), 16 (51), 15 (214). Pile 17 experienced 446 hammer blows over a period of 9 minutes. Piles noted with PDA indicate restrike events during which pile dynamics analyzer monitoring was completed. Piles noted with "A" represent piles installed to replace similarly-numbered piles. After installation, selected piles were struck again with the hammer to demonstrate resistance performance and these are noted as "restrikes". Monitoring of deliberate pump operation at Well 6 on July 13, 2017, during a period when no pile driving was occurring, measured maximum particle velocities of 0.08 to 0.8 mm/s. Where total driving duration between till/rock start and end times noted above is not representative, actual driving duration is shown in parentheses in minutes and seconds: 13A(10:00), 15A(6:24), 17 restrike (14:00), 13PDA(6:20). Total pile driving durations derived from start and end times noted above includes labour breaks, equipment work, splicing, welding and other standby time.

**NORTH KENT 1**  
**Preliminary Vibration Monitoring Report**

**Footnotes:** a) start and stop of pile driving are start and stop times for active hammering; b) values shown are maximum daily values regardless of direction; c) preliminary values subject to further data review/analysis; d) values shown are based on fast Fourier transform analyses of consecutive 1 second intervals for a total period of 10 minutes during pile driving on till/rock (600 seconds) and represent the maximum of the 1 second interval peak velocity values during these periods regardless of measurement direction; e) see monitoring notes above.

## Preliminary Vibration Monitoring Report

Turbine Location: T36

| Vibration Measurements at Turbine Site |                              |                 |                  |                    |                                 | Vibration Measurements at Wells |  |        |
|--|------------------------------|-----------------|------------------|--------------------|---------------------------------|---------------------------------|--|--------|
| Pile No.:                              | Pile Driving Times and Dates |                 |                  | Geophone Dist. (m) | Daily Maximum Particle Velocity |                                 | Particle Velocity (mm/s) <sup>c, d</sup> |        |
|  | Start <sup>a</sup>           | Rock/Till       | End <sup>a</sup> |                    | (mm/s) <sup>b</sup>             |                                 | Well 5                                   | Well 6 |
|  |                              |                 |                  |                    |                                 |                                 | No Pump <sup>e</sup>                     |        |
| 1                                      | 7/26/2017 10:33              | 7/26/2017 10:38 | 7/26/2017 10:48  | 23.3               | 7.87                            |                                 | 0.005                                    | 0.086  |
| 2                                      | 7/26/2017 18:16              | 7/26/2017 18:21 | 7/26/2017 18:28  | 21.1               | 7.87                            |                                 | 0.003                                    | 0.016  |
| 3                                      | 7/26/2017 19:24              | 7/26/2017 19:28 | 7/26/2017 19:42  | 18.4               | 7.87                            |                                 | 0.002                                    | 0.005  |
| 4                                      | 7/26/2017 18:37              | 7/26/2017 19:07 | 7/26/2017 19:19  | 15.5               | 7.87                            |                                 | 0.002                                    | 0.027  |
| 5                                      | 7/26/2017 17:59              | 7/26/2017 18:04 | 7/26/2017 18:10  | 12.7               | 7.87                            |                                 | 0.012                                    | 0.016  |
| 6                                      | 7/26/2017 17:30              | 7/26/2017 17:34 | 7/26/2017 17:44  | 10.4               | 7.87                            |                                 | 0.004                                    | 0.032  |
| 7                                      | 7/26/2017 17:10              | 7/26/2017 17:13 | 7/26/2017 17:23  | 9.5                | 7.87                            |                                 | 0.010                                    | 0.044  |
| 8                                      | 7/26/2017 16:41              | 7/26/2017 16:45 | 7/26/2017 16:56  | 10.4               | 7.87                            |                                 | 0.007                                    | 0.038  |
| 9                                      | 7/26/2017 16:19              | 7/26/2017 16:23 | 7/26/2017 16:33  | 12.7               | 7.87                            |                                 | 0.004                                    | 0.010  |
| 10                                     | 7/26/2017 15:48              | 7/26/2017 15:51 | 7/26/2017 16:03  | 15.5               | 7.87                            |                                 | 0.005                                    | 0.070  |
| 11                                     | 7/26/2017 15:12              | 7/26/2017 15:15 | 7/26/2017 15:23  | 18.4               | 7.87                            |                                 | 0.004                                    | 0.045  |
| 12                                     | 7/26/2017 14:32              | 7/26/2017 14:45 | 7/26/2017 14:57  | 21.1               | 7.87                            |                                 | 0.005                                    | 0.048  |
| 13                                     | 7/26/2017 14:15              | 7/26/2017 14:21 | 7/26/2017 14:28  | 23.3               | 7.87                            |                                 | 0.014                                    | 0.018  |
| 14                                     | 7/26/2017 13:58              | 7/26/2017 14:03 | 7/26/2017 14:08  | 25.0               | 7.87                            |                                 | 0.009                                    | 0.031  |
| 15                                     | 7/26/2017 13:16              | 7/26/2017 13:20 | 7/26/2017 13:32  | 26.0               | 7.87                            |                                 | 0.005                                    | 0.111  |
| 16                                     | 7/26/2017 12:48              | 7/26/2017 12:53 | 7/26/2017 13:05  | 26.4               | 7.87                            |                                 | 0.011                                    | 0.038  |
| 17                                     | 7/26/2017 11:41              | 7/26/2017 11:47 | 7/26/2017 11:56  | 26.0               | 7.87                            |                                 | 0.005                                    | 0.021  |
| 18                                     | 7/26/2017 11:08              | 7/26/2017 11:12 | 7/26/2017 11:22  | 25.0               | 7.87                            |                                 | 0.006                                    | 0.068  |
| Restrikes                              |                              |                 |                  |                    |                                 |                                 |  |        |
| 16                                     | 7/27/2017 7:36               | 7/27/2017 7:36  | 7/27/2017 7:37   | 26.4               | 0.89                            |                                 | 0.003                                    | 0.437  |
|  |                              |                 |                  |                    |                                 |                                 |  | 0.029  |

## Well Information

Well No.: 5  
Municipal Address: [REDACTED]  
Distance from Turbine Centre: 4201 m

Well No.: 6  
Municipal Address: [REDACTED]  
Distance from Turbine Centre: 3380 m

ISO 2631-2 particle velocity threshold for human perception is 0.1 mm/s between approximately 8 to 100 Hz

Background values at T5 and T42 test pile sites and Wells 1 and 3, when other common activities observed ranged from <0.01 to approximately 0.07 mm/s

**Monitoring Notes:** A single restrike event occurred on the day following with a total of 24 hammer blows on Pile 16 during a period of approximately 65 seconds. After installation, one pile was struck again with the hammer to demonstrate resistance performance and this event is noted under "restrikes". Water pump was observed cycling on and off during pile driving operations and remaining on for periods of 2 to 4 minutes. When pump was operating during pile driving, casing at Well 6 exhibited particle velocities of up to 0.44 mm/s and this dominated analysis of data. Monitoring of deliberate pump operation at Well 6 on July 13, 2017, during a period when no pile driving was occurring, measured maximum particle velocities of 0.08 to 0.8 mm/s. Total pile driving durations derived from start and end times noted above includes labour breaks, equipment work, splicing, welding and other standby time.

**Footnotes:** a) start and stop of pile driving are start and stop times for active hammering; b) values shown are maximum daily values regardless of direction; c) preliminary values subject to further data review/analysis; d) values shown are based on fast Fourier transform analyses of consecutive 1 second intervals for a total period of 10 minutes during pile driving on till/rock (600 seconds) and represent the maximum of the 1 second interval peak velocity values during these periods regardless of measurement direction; e) see monitoring notes above.

## Preliminary Vibration Monitoring Report

Turbine Location: T43

| Vibration Measurements at Turbine Site |                    |                 |                  |                    |   | Vibration Measurements at Wells          |         |                      |
|--|--------------------|-----------------|------------------|--------------------|---|--|---------|----------------------|
| Pile Driving Times and Dates           |                    |                 |                  |                    |   | Particle Velocity (mm/s) <sup>c, d</sup> |         |                      |
| Pile No.:                              | Start <sup>a</sup> | Rock/Till       | End <sup>a</sup> | Geophone Dist. (m) | Daily Maximum Particle Velocity (mm/s) <sup>b</sup> | Well 11                                  | Well 12 | No Pump <sup>e</sup> |
| 1                                      | 8/18/2017 12:35    | 8/18/2017 12:45 | 8/18/2017 12:52  | 24.8               | 5.59  | 0.006                                    | 0.008   |                      |
| 2                                      | 8/18/2017 13:01    | 8/18/2017 13:12 | 8/18/2017 13:20  | 23.8               | 5.59  | 0.006                                    | 0.007   |                      |
| 3                                      | 8/21/2017 8:28     | 8/21/2017 8:38  | 8/21/2017 8:48   | 22.2               | 3.18  | 0.010                                    | 0.007   |                      |
| 4                                      | 8/21/2017 12:47    | 8/21/2017 12:59 | 8/21/2017 13:10  | 20.0               | 3.18  | 0.007                                    | 0.006   |                      |
| 5                                      | 8/21/2017 9:03     | 8/21/2017 9:16  | 8/21/2017 9:23   | 17.4               | 3.18  | 0.006                                    | 1.468   | 0.009                |
| 6                                      | 8/21/2017 7:56     | 8/21/2017 8:08  | 8/21/2017 8:17   | 14.5               | 3.18  | 0.024                                    | 0.024   |                      |
| 7                                      | 8/18/2017 14:32    | 8/18/2017 14:43 | 8/18/2017 14:50  | 11.6               | 3.18  | 0.006                                    | 0.006   |                      |
| 8                                      | 8/18/2017 13:37    | 8/18/2017 13:49 | 8/18/2017 13:57  | 9.3                | 3.18  | 0.007                                    | 0.005   |                      |
| 9                                      | 8/15/2017 15:09    | 8/15/2017 15:18 | 8/15/2017 15:27  | 8.3                | 7.37  | 0.086                                    | 0.005   |                      |
| 10                                     | 8/15/2017 13:21    | 8/15/2017 13:28 | 8/15/2017 13:37  | 9.3                | 7.37  | 0.004                                    | 0.002   |                      |
| 11                                     | 8/15/2017 12:22    | 8/15/2017 12:34 | 8/15/2017 12:35  | 11.6               | 7.37  | 0.002                                    | 0.006   |                      |
| 12                                     | 8/15/2017 11:58    | 8/15/2017 12:10 | 8/15/2017 12:13  | 14.5               | 7.37  | 0.018                                    | 0.018   |                      |
| 13                                     | 8/15/2017 9:19     | 8/15/2017 9:42  | 8/15/2017 11:40  | 17.4               | 7.37  | 0.003                                    | 0.002   |                      |
| 14                                     | 8/15/2017 15:46    | 8/15/2017 15:57 | 8/15/2017 16:10  | 20.0               | 7.37  | 0.006                                    | 0.013   |                      |
| 15                                     | 8/18/2017 9:17     | 8/18/2017 9:23  | 8/18/2017 9:31   | 22.2               | 5.59  | 0.005                                    | 0.009   |                      |
| 16                                     | 8/18/2017 9:43     | 8/18/2017 9:50  | 8/18/2017 9:59   | 23.8               | 5.59  | 0.012                                    | 0.009   |                      |
| 17                                     | 8/18/2017 10:10    | 8/18/2017 10:17 | 8/18/2017 10:28  | 24.8               | 5.59  | 0.004                                    | 0.018   |                      |
| 18                                     | 8/18/2017 11:45    | 8/18/2017 12:02 | 8/18/2017 12:21  | 25.2               | 5.59  | 0.008                                    | 0.004   |                      |
| <b>Restrikes</b>                       |                    |                 |                  |                    |   |  |         |                      |
| 14                                     | 8/21/2017 10:43    | 8/21/2017 10:43 | 8/21/2017 10:43  | 20.0               | 3.18  | 0.012                                    | 0.010   |                      |
| 16(1)                                  | 8/21/2017 10:30    | 8/21/2017 10:30 | 8/21/2017 10:30  | 23.8               | 3.18  | 0.011                                    | 0.010   |                      |
| 16(2)                                  | 8/21/2017 11:52    | 8/21/2017 11:52 | 8/21/2017 11:54  | 22.2               | 3.18  | 0.005                                    | 0.029   |                      |

## Well Information

Well No.: 11

Municipal Address:

Distance from Turbine Centre: 4092 m

Well No.: 12

Municipal Address:

Distance from Turbine Centre: 4359 m

ISO 2631-2 particle velocity threshold for human perception is 0.1 mm/s between approximately 8 to 100 Hz

Background values at T5 and T42 test pile sites and Wells 1 and 2, when other common activities observed ranged from &lt;0.01 to approximately 0.07 mm/s

**Monitoring Notes:** After installation, selected piles were struck again with the hammer to demonstrate resistance performance and these are noted as "restrikes". Vibration measurements were undertaken on August 17, 2017 at Wells 11 and 12 during water quality sampling events in the absence of pile driving within the cluster. Both pumps turned on and operated during the sampling events. Maximum vibration measurements for Well 11 were 0.016 mm/s and this pump was located within the residence approximately 40 m from the well. Maximum vibration measurements for Well 12 were 0.896 mm/s and the pump was mounted on the well casing. During pile driving for turbine T3, on August 23, 2017, the maximum vibration measurement of the Well 12 casing was 2.4 mm/s for clearly definable periods during which the pump was operating. Data shown for the "no pump" condition was obtained during pile driving when the pump was not operating. Note that driving/restriking of some piles occurred in relatively rapid succession and, therefore, the vibration measurement data for the 10 minute periods of analysis are applicable to multiple piles. Driving of pile 13 was started and stopped on multiple occasions because of problems with fuel pump resulting in a total of approximately 88 minutes of standby between driving intervals for a total driving time on till/rock of 14:45 (minutes:seconds). Pile 18 total driving time on till/rock was 8:46 (minutes:seconds) due to intermittent stops and starts. Total pile driving durations derived from start and end times noted above includes labour breaks, equipment work, splicing, welding and other standby time.

**Footnotes:** a) start and stop of pile driving are start and stop times for active hammering; b) values shown are maximum daily values regardless of direction; c) preliminary values subject to further data review/analysis; d) values shown are based on fast Fourier transform analyses of consecutive 1 second intervals for a total period of 10 minutes during pile driving on till/rock (600 seconds) and represent the maximum of the 1 second interval peak velocity values during these periods regardless of measurement direction; e) see monitoring notes above.



# NORTH KENT 1

## Preliminary Vibration Monitoring Report

**Turbine Location:** T45

| Vibration Measurements at Turbine Site |                              |                 |                  |                    |                                 | Vibration Measurements at Wells          |                 |                      |
|--|------------------------------|-----------------|------------------|--------------------|---------------------------------|--|-----------------|----------------------|
| Pile No.:                              | Pile Driving Times and Dates |                 |                  | Geophone Dist. (m) | Daily Maximum Particle Velocity | Particle Velocity (mm/s) <sup>c, d</sup> |                 |                      |
|  | Start <sup>a</sup>           | Rock/Till       | End <sup>a</sup> |                    | (mm/s) <sup>b</sup>             | Well 11                                  | Well 12         | No Pump <sup>e</sup> |
| 1                                      | 8/23/2017 11:47              | 8/23/2017 11:53 | 8/23/2017 12:18  | 14.8               | 7.75                            | 0.025                                    | 0.010           |                      |
| 2                                      | 8/23/2017 14:20              | 8/23/2017 14:27 | 8/23/2017 14:41  | 12.0               | 7.75                            | 0.024                                    | NA <sup>e</sup> |                      |
| 3                                      | 8/23/2017 15:10              | 8/23/2017 15:17 | 8/23/2017 15:27  | 9.6                | 7.75                            | 0.017                                    | 0.005           |                      |
| 4                                      | 8/23/2017 16:49              | 8/23/2017 16:55 | 8/23/2017 17:05  | 8.7                | 7.75                            | 0.008                                    | 1.148           |                      |
| 5                                      | 8/23/2017 17:22              | 8/23/2017 17:30 | 8/23/2017 17:44  | 9.6                | 7.75                            | 0.011                                    | 0.007           |                      |
| 6                                      | 8/23/2017 10:50              | 8/23/2017 11:00 | 8/23/2017 11:16  | 12.0               | 7.75                            | 0.018                                    | 0.016           |                      |
| 7                                      | 8/24/2017 8:30               | 8/24/2017 8:38  | 8/24/2017 8:47   | 14.8               | 3.30                            | 0.014                                    | 0.014           |                      |
| 8                                      | 8/24/2017 9:05               | 8/24/2017 9:14  | 8/24/2017 9:21   | 17.7               | 3.30                            | 0.021                                    | 0.040           |                      |
| 9                                      | 8/24/2017 9:36               | 8/24/2017 9:44  | 8/24/2017 10:48  | 20.4               | 3.30                            | 0.018                                    | 1.511           |                      |
| 10                                     | 8/23/2017 12:49              | 8/23/2017 12:58 | 8/23/2017 13:15  | 22.6               | 7.75                            | 0.009                                    | 0.005           |                      |
| 11                                     | 8/24/2017 13:32              | 8/24/2017 13:42 | 8/24/2017 13:48  | 24.2               | 3.30                            | 0.004                                    | 0.018           |                      |
| 12                                     | 8/24/2017 15:06              | 8/24/2017 15:15 | 8/24/2017 15:23  | 25.2               | 3.30                            | 0.007                                    | 0.008           |                      |
| 13                                     | 8/24/2017 15:35              | 8/24/2017 15:44 | 8/24/2017 15:53  | 25.6               | 3.30                            | 0.026                                    | 0.034           |                      |
| 14                                     | 8/24/2017 16:05              | 8/24/2017 16:14 | 8/24/2017 16:22  | 25.2               | 3.30                            | 0.012                                    | 0.061           |                      |
| 15                                     | 8/24/2017 16:40              | 8/24/2017 16:46 | 8/24/2017 16:55  | 24.2               | 3.30                            | 0.015                                    | 0.007           |                      |
| 16                                     | 8/24/2017 17:11              | 8/24/2017 17:18 | 8/24/2017 17:24  | 22.6               | 3.30                            | 0.012                                    | 0.004           |                      |
| 17                                     | 8/24/2017 17:33              | 8/24/2017 17:39 | 8/24/2017 17:45  | 20.4               | 3.30                            | 0.006                                    | 0.009           |                      |
| 18                                     | 8/24/2017 17:57              | 8/24/2017 18:08 | 8/24/2017 18:12  | 17.7               | 3.30                            | 0.005                                    | 0.006           |                      |
| <b>Restrikes</b>                       |                              |                 |                  |                    |                                 |  |                 |                      |
| 6                                      | 8/23/2017 13:28              | 8/23/2017 13:28 | 8/23/2017 13:29  | 12.0               | 7.75                            | 0.043                                    | 0.017           |                      |
| 1                                      | 8/23/2017 13:13              | 8/23/2017 13:13 | 8/23/2017 13:13  | 14.8               | 7.75                            | 0.009                                    | 0.005           |                      |
| 15                                     | 8/25/2017 7:45               | 8/25/2017 7:45  | 8/25/2017 7:47   | 24.2               | 5.97                            | 0.015                                    | 0.032           |                      |
| 16                                     | 8/25/2017 9:11               | 8/25/2017 9:11  | 8/25/2017 9:13   | 22.6               | 5.97                            | 0.007                                    | 2.335           | 0.008                |
| 17                                     | 8/25/2017 9:03               | 8/25/2017 9:03  | 8/25/2017 9:06   | 20.4               | 5.97                            | 0.007                                    | 0.019           |                      |
| 18                                     | 8/25/2017 8:51               | 8/25/2017 8:51  | 8/25/2017 8:55   | 17.7               | 5.97                            | 0.011                                    | 0.011           |                      |
| 1                                      | 8/25/2017 11:44              | 8/25/2017 11:44 | 8/25/2017 11:45  | 14.8               | 5.97                            | 0.013                                    | 0.037           |                      |
| 12                                     | 8/25/2017 9:22               | 8/25/2017 9:22  | 8/25/2017 9:25   | 25.2               | 5.97                            | 0.024                                    | 0.010           |                      |
| 18                                     | 8/25/2017 9:16               | 8/25/2017 9:16  | 8/25/2017 9:18   | 17.7               | 5.97                            | 0.011                                    | 0.011           |                      |
| 4                                      | 8/25/2017 8:43               | 8/25/2017 8:43  | 8/25/2017 8:45   | 8.7                | 5.97                            | 0.013                                    | 0.007           |                      |
| 5                                      | 8/25/2017 8:36               | 8/25/2017 8:36  | 8/25/2017 8:37   | 9.6                | 5.97                            | 0.013                                    | 0.013           |                      |
| 7                                      | 8/25/2017 8:30               | 8/25/2017 8:30  | 8/25/2017 8:32   | 14.8               | 5.97                            | 0.006                                    | 0.028           |                      |
| 8                                      | 8/25/2017 8:25               | 8/25/2017 8:25  | 8/25/2017 8:26   | 17.7               | 5.97                            | 0.006                                    | 0.018           |                      |
| 10                                     | 8/25/2017 9:28               | 8/25/2017 9:28  | 8/25/2017 10:19  | 22.6               | 5.97                            | 0.021                                    | 0.011           |                      |
| 13                                     | 8/25/2017 7:53               | 8/25/2017 7:54  | 8/25/2017 7:59   | 25.6               | 5.97                            | 0.013                                    | 0.007           |                      |
| 9                                      | 8/25/2017 8:09               | 8/25/2017 8:09  | 8/25/2017 8:19   | 20.4               | 5.97                            | 0.028                                    | 0.010           |                      |
| 11                                     | 8/25/2017 8:03               | 8/25/2017 8:03  | 8/25/2017 8:05   | 24.2               | 5.97                            | 0.008                                    | 0.024           |                      |
| <b>Spliced</b>                         |                              |                 |                  |                    |                                 |  |                 |                      |
| 13                                     | 8/30/2017 11:06              | 8/30/2017 11:06 | 8/30/2017 11:07  | 25.6               | 6.10                            | 0.006                                    | 0.012           |                      |
| 2                                      | 8/30/2017 10:06              | 8/30/2017 10:06 | 8/30/2017 10:06  | 12.0               | 6.10                            | 0.005                                    | 0.018           |                      |
| 3                                      | 8/30/2017 10:09              | 8/30/2017 10:09 | 8/30/2017 10:10  | 9.6                | 6.10                            | 0.005                                    | 0.018           |                      |
| 4                                      | 8/30/2017 10:14              | 8/30/2017 10:14 | 8/30/2017 10:16  | 8.7                | 6.10                            | 0.011                                    | 0.014           |                      |
| 5                                      | 8/30/2017 10:19              | 8/30/2017 10:19 | 8/30/2017 10:20  | 9.6                | 6.10                            | 0.011                                    | 0.014           |                      |
| 6                                      | 8/30/2017 10:23              | 8/30/2017 10:23 | 8/30/2017 10:25  | 12.0               | 6.10                            | 0.013                                    | 0.016           |                      |
| 7                                      | 8/30/2017 10:27              | 8/30/2017 10:27 | 8/30/2017 10:29  | 14.8               | 6.10                            | 0.013                                    | 0.016           |                      |
| 8                                      | 8/30/2017 10:32              | 8/30/2017 10:32 | 8/30/2017 10:34  | 17.7               | 6.10                            | 0.013                                    | 0.013           |                      |
| 10                                     | 8/30/2017 10:40              | 8/30/2017 10:40 | 8/30/2017 11:00  | 22.6               | 6.10                            | 0.003                                    | 0.018           |                      |
| <b>Replacement Piles</b>               |                              |                 |                  |                    |                                 |  |                 |                      |
| 6A                                     | 9/12/2017 7:51               | 9/12/2017 7:59  | 9/12/2017 9:41   | 13.0               | 4.70                            | 0.014                                    | 0.007           |                      |
| 10A                                    | 9/12/2017 8:29               | 9/12/2017 8:36  | 9/12/2017 9:37   | 23.6               | 4.70                            | 0.015                                    | 0.003           |                      |
| 13A                                    | 9/12/2017 9:07               | 9/12/2017 9:13  | 9/12/2017 9:29   | 26.6               | 4.70                            | 0.015                                    | 0.011           |                      |

# NORTH KENT 1

## Preliminary Vibration Monitoring Report

**Well Information**

**Well No.:** 11  
**Municipal Address:** [REDACTED]  
**Distance from Turbine Centre:** 1223 m

**Well No.:** 12  
**Municipal Address:** [REDACTED]  
**Distance from Turbine Centre:** 1635 m

ISO 2631-2 particle velocity threshold for human perception is 0.1 mm/s between approximately 8 to 100 Hz

Background values at T5 and T42 test pile sites and Wells 1 and 2, when other common activities observed ranged from <0.01 to approximately 0.07 mm/s

**Monitoring Notes:** After installation, selected piles were struck again with the hammer to demonstrate resistance performance and these are noted as "restrikes". Vibration measurements were undertaken on August 17, 2017 at Wells 11 and 12 during water quality sampling events in the absence of pile driving within the cluster. Both pumps turned on and operated during the sampling events. The maximum vibration measurement for Well 11 was 0.016 mm/s and this pump was located within the residence approximately 40 m from the well. The maximum vibration measurement for Well 12 was 0.896 mm/s and the pump was mounted on the well casing. The maximum vibration measurement of the Well 12 casing during all monitoring completed to the date of report issue was about 2.4 mm/s for clearly definable periods during which the pump was operating. Data shown for the "no pump" condition was obtained during pile driving when the pump was not operating. Note that driving/restriking of some piles occurred in relatively rapid succession and, therefore, the vibration measurement data for the 10 minute periods of analysis are applicable to multiple piles. Data for Well 12 during driving of Pile 2 on August 23, 2017 was not captured when data logger battery failed and then changed. Total driving time on till/rock for Pile 9 was interrupted by repairs to the pile driving hammer and the actual driving duration on till/rock was 8:00 (minutes:seconds) for this pile. Total driving time on till/rock for restrike of Pile 10 was interrupted by damage to the pile top, splicing and welding and total driving duration on till/rock was 5:48 (minutes:seconds). Driving time on till/rock for driving of Pile 6A was interrupted from 8:07:35 to 8:10:35 and from 8:12:45 to 9:40:28. Driving time on till/rock for driving of Pile 10A was interrupted from 8:49:30 to 9:37:05. Driving time on till/rock for driving of Pile 13A was interrupted from 9:18:45 to 9:26:30. Total pile driving durations derived from start and end times noted above includes labour breaks, equipment work, splicing, welding and other standby time.

**Footnotes:** a) start and stop of pile driving are start and stop times for active hammering; b) values shown are maximum daily values regardless of direction; c) preliminary values subject to further data review/analysis; d) values shown are based on fast Fourier transform analyses of consecutive 1 second intervals for a total period of 10 minutes during pile driving on till/rock (600 seconds) and represent the maximum of the 1 second interval peak velocity values during these periods regardless of measurement direction; e) see monitoring notes above.

# NORTH KENT 1

## Preliminary Vibration Monitoring Report

**Turbine Location:** T46

| Vibration Measurements at Turbine Site |                    |                 |                  |                    |                                 | Vibration Measurements at Wells          |         |                      |
|--|--------------------|-----------------|------------------|--------------------|---------------------------------|--|---------|----------------------|
| Pile Driving Times and Dates           |                    |                 |                  |                    | Daily Maximum Particle Velocity | Particle Velocity (mm/s) <sup>c, d</sup> |         |                      |
| Pile No.:                              | Start <sup>a</sup> | Rock/Till       | End <sup>a</sup> | Geophone Dist. (m) | (mm/s) <sup>b</sup>             | Well 11                                  | Well 12 | No Pump <sup>e</sup> |
| 1                                      | 8/29/2017 8:38     | 8/29/2017 8:44  | 8/29/2017 9:10   | 26.5               | 5.80                            | NA <sup>e</sup>                          | 0.002   |                      |
| 2                                      | 8/29/2017 9:24     | 8/29/2017 9:33  | 8/29/2017 9:49   | 25.5               | 5.80                            | NA <sup>e</sup>                          | 0.003   |                      |
| 3                                      | 8/29/2017 10:14    | 8/29/2017 10:19 | 8/29/2017 10:30  | 23.8               | 5.80                            | NA <sup>e</sup>                          | 0.037   |                      |
| 4                                      | 8/29/2017 12:41    | 8/29/2017 12:52 | 8/29/2017 13:01  | 21.5               | 5.80                            | 0.004                                    | 0.010   |                      |
| 5                                      | 8/29/2017 12:00    | 8/29/2017 12:09 | 8/29/2017 12:28  | 18.9               | 5.80                            | NA <sup>e</sup>                          | 0.003   |                      |
| 6                                      | 8/29/2017 11:02    | 8/29/2017 11:11 | 8/29/2017 11:25  | 16.0               | 5.80                            | NA <sup>e</sup>                          | 0.006   |                      |
| 7                                      | 8/28/2017 16:35    | 8/28/2017 16:47 | 8/28/2017 16:53  | 13.1               | 7.85                            | 0.015                                    | 0.071   |                      |
| 8                                      | 8/28/2017 16:02    | 8/28/2017 16:12 | 8/28/2017 16:20  | 10.9               | 7.85                            | 0.007                                    | 1.551   | 0.039                |
| 9                                      | 8/28/2017 13:25    | 8/28/2017 13:34 | 8/28/2017 13:36  | 10.0               | 7.85                            | 0.006                                    | 0.011   |                      |
| 10                                     | 8/28/2017 12:44    | 8/28/2017 12:56 | 8/28/2017 12:59  | 10.9               | 7.85                            | 0.006                                    | 0.008   |                      |
| 11                                     | 8/28/2017 11:25    | 8/28/2017 11:34 | 8/28/2017 11:41  | 13.1               | 7.85                            | NA <sup>e</sup>                          | 0.011   |                      |
| 12                                     | 8/28/2017 10:07    | 8/28/2017 10:17 | 8/28/2017 10:20  | 16.0               | 7.85                            | 0.003                                    | 0.009   |                      |
| 13                                     | 8/28/2017 9:33     | 8/28/2017 9:43  | 8/28/2017 9:49   | 18.9               | 7.85                            | 0.021                                    | 0.015   |                      |
| 14                                     | 8/28/2017 9:00     | 8/28/2017 9:12  | 8/28/2017 9:16   | 21.5               | 7.85                            | 0.003                                    | 0.003   |                      |
| 15                                     | 8/28/2017 8:30     | 8/28/2017 8:44  | 8/28/2017 8:47   | 23.8               | 7.85                            | 0.004                                    | 0.004   |                      |
| 16                                     | 8/28/2017 13:53    | 8/28/2017 14:03 | 8/28/2017 14:07  | 25.5               | 7.85                            | 0.002                                    | 0.006   |                      |
| 17                                     | 8/28/2017 14:27    | 8/28/2017 14:38 | 8/28/2017 14:48  | 26.5               | 7.85                            | 0.017                                    | 0.004   |                      |
| 18                                     | 8/29/2017 7:53     | 8/29/2017 8:01  | 8/29/2017 8:05   | 26.9               | 5.80                            | NA <sup>e</sup>                          | 0.002   |                      |
| <b>Restrikes</b>                       |                    |                 |                  |                    |                                 |  |         |                      |
| 9                                      | 8/29/2017 13:14    | 8/29/2017 13:14 | 8/29/2017 13:16  | 10.0               | 5.80                            | 0.005                                    | 0.006   |                      |
| 8                                      | 8/29/2017 13:25    | 8/29/2017 13:25 | 8/29/2017 13:26  | 10.9               | 5.80                            | 0.003                                    | 0.052   |                      |
| 16                                     | 8/29/2017 13:36    | 8/29/2017 13:36 | 8/29/2017 13:38  | 25.5               | 5.80                            | 0.003                                    | 0.006   |                      |

### Well Information

**Well No.:** 11

**Municipal Address:**

**Distance from Turbine Centre:** 1697 m

**Well No.:** 12

**Municipal Address:**

**Distance from Turbine Centre:** 2170 m

ISO 2631-2 particle velocity threshold for human perception is 0.1 mm/s between approximately 8 to 100 Hz


Background values at T5 and T42 test pile sites and Wells 1 and 2, when other common activities observed ranged from <0.01 to approximately 0.07 mm/s

**Monitoring Notes:** Data obtained during pile dynamic analyses is pending. Piles noted with "A" represent piles installed to replace similarly-numbered piles. After installation, selected piles were struck again with the hammer to demonstrate resistance performance and these are noted as "restrikes". Total duration for pile driving on rock/till based on times noted above is not representative for Piles 1 and where the actual duration for driving on till/rock was (minutes:seconds): 1(11:30) and 5(18:32). Maximum vibrations for Well 12 were 1.55 mm/s for August 29, 2017. The pump was mounted on the well casing. During pile driving on August 23, 2017, the maximum vibration measurement of the Well 12 casing was 2.4 mm/s for clearly definable periods during which the pump was operating. Data shown for the "no pump" condition was obtained during pile driving when the pump was not operating. Data not available for Piles 1, 2, 3, 5, 6, 11 and 18 at Well 11 on August 28 and 29, 2017 due to several separate battery failures in monitoring equipment. Batteries were subsequently replaced upon discovery.


**Footnotes:** a) start and stop of pile driving are start and stop times for active hammering; b) values shown are maximum daily values regardless of direction; c) preliminary values subject to further data review/analysis; d) values shown are based on fast Fourier transform analyses of consecutive 1 second intervals for a total period of 10 minutes during pile driving on till/rock (600 seconds) and represent the maximum of the 1 second interval peak velocity values during these periods regardless of measurement direction; e) see monitoring notes above.




SITE PLAN



INSET A (WELL #11)



INSET B (WELL #12)



N.T.S.

TURBINE PILE LAYOUT

#### LEGEND

- INSTANTEL MINIMATE GEOPHONE
- WATER WELL
- TURBINE BEING CONSTRUCTED
- MN MAGNETIC NORTH
- UTM-N UNIVERSAL TRANSVERSE MERCATOR GEOGRAPHIC NORTH

#### REFERENCE

DRAWING BASED ON 2010 AERIAL IMAGERY PROVIDED BY THE MUNICIPALITY OF CHATHAM-KENT. INCLUDES MATERIAL © 2015 OF THE QUEEN'S PRINTER FOR ONTARIO; AND "FOUNDATION PLAN", ENTUTIVE, PROJECT No. C017-0190, DWG No. S002.


#### NOTES

THIS DRAWING IS SCHEMATIC ONLY AND IS TO BE READ IN CONJUNCTION WITH ACCOMPANYING TEXT.  
ALL LOCATIONS ARE APPROXIMATE.


|   |             |         |                              |
|---|-------------|---------|------------------------------|
| PROJECT   |             |         |                              |
| NORTH KENT 1<br>VIBRATION MONITORING              |             |         |                              |
| TITLE   |             |         |                              |
| TURBINE PILES AND WATER WELL<br>LOCATION PLAN, T3 |             |         |                              |
|   | PROJECT NO. | 1668031 | FILE NO. 1668031-2000-RC2013 |
|   | DATE        | DCH/ZLB | Sept. 18/17                  |
|   | CHECKED     |         |                              |
| SCALE   |             |         | AS SHOWN                     |
|   |             |         | FIGURE T3                    |




Drawing file: "668031\_2000\_R020T4.dwg" Sep 20, 2017 12:51pm




SITE PLAN



INSET A (WELL #11)



INSET B (WELL #12)



TURBINE PILE LAYOUT

#### LEGEND

- INSTANTEL MINIMATE GEOPHONE
- WATER WELL
- TURBINE BEING CONSTRUCTED
- MN MAGNETIC NORTH
- UTM-N UNIVERSAL TRANSVERSE MERCATOR GEOGRAPHIC NORTH

#### REFERENCE

DRAWING BASED ON 2010 AERIAL IMAGERY PROVIDED BY THE MUNICIPALITY OF CHATHAM-KENT. INCLUDES MATERIAL c 2015 OF THE QUEEN'S PRINTER FOR ONTARIO; AND "FOUNDATION PLAN", ENTUTIVE, PROJECT No. C017-0190, DWG No. S002.


#### NOTES

THIS DRAWING IS SCHEMATIC ONLY AND IS TO BE READ IN CONJUNCTION WITH ACCOMPANYING TEXT.  
ALL LOCATIONS ARE APPROXIMATE.


|             |   |          |                     |                |
|-------------|---|----------|---------------------|----------------|
| PROJECT     | NORTH KENT 1<br>VIBRATION MONITORING              |          |                     |                |
| TITLE       | TURBINE PILES AND WATER WELL<br>LOCATION PLAN, T4 |          |                     |                |
| PROJECT No. | 1698031   | FILE No. | 1698031-2000-R020T4 |                |
| DATE        | DOH/ZLB   | DATE     | Sept 18/17          | SCALE AS SHOWN |
| CHECKED     |   |          |                     | FIGURE T4      |









**SITE PLAN**



**INSET A (WELL #7)**



**INSET B (WELL #8)**



N.T.S.

**TURBINE PILE LAYOUT**

#### LEGEND

- INSTANTEL MINIMATE GEOPHONE
- WATER WELL
- TURBINE BEING CONSTRUCTED
- MN MAGNETIC NORTH
- UTM-N UNIVERSAL TRANSVERSE MERCATOR GEOGRAPHIC NORTH

#### REFERENCE

DRAWING BASED ON 2010 AERIAL IMAGERY PROVIDED BY THE MUNICIPALITY OF CHATHAM-KENT. INCLUDES MATERIAL c 2015 OF THE QUEEN'S PRINTER FOR ONTARIO; AND 'FOUNDATION PLAN', ENTUTIVE, PROJECT No. C017-0190, DWG No. S002.

#### NOTES

THIS DRAWING IS SCHEMATIC ONLY AND IS TO BE READ IN CONJUNCTION WITH ACCOMPANYING TEXT.  
ALL LOCATIONS ARE APPROXIMATE.

|                   |             |   |                               |
|-------------------|-------------|---|-------------------------------|
| PROJECT           |             | NORTH KENT 1<br>VIBRATION MONITORING              |                               |
| TITLE             |             | TURBINE PILES AND WATER WELL<br>LOCATION PLAN, T6 |                               |
|                   | PROJECT NO. | 16686031  | FILE NO. 16686031-2000-RC2016 |
|                   | DATE        | 09/18/17  | SCALE AS SHOWN                |
| Golder Associates | DRAWN       | DCI/ZLR   | SEP 18/17                     |
|                   | CHECKED     |   |                               |
|                   |             | FIGURE T6   |                               |




Drawing file: "668031\_2000-R02017.dwg" Sep 20, 2017 12:54pm




SITE PLAN



INSET A (WELL #7)



INSET B (WELL #8)



TURBINE PILE LAYOUT

#### LEGEND

- INSTANTEL MINIMATE GEOPHONE
- WATER WELL
- TURBINE BEING CONSTRUCTED
- MN MAGNETIC NORTH
- UTM-N UNIVERSAL TRANSVERSE MERCATOR GEOGRAPHIC NORTH

#### REFERENCE


DRAWING BASED ON 2010 AERIAL IMAGERY PROVIDED BY THE MUNICIPALITY OF CHATHAM-KENT. INCLUDES MATERIAL c 2015 OF THE QUEEN'S PRINTER FOR ONTARIO; AND "FOUNDATION PLAN", ENTUTIVE, PROJECT No. C017-0190, DWG No. S002.

#### NOTES


THIS DRAWING IS SCHEMATIC ONLY AND IS TO BE READ IN CONJUNCTION WITH ACCOMPANYING TEXT.  
ALL LOCATIONS ARE APPROXIMATE.

|             |   |           |                     |
|-------------|---|-----------|---------------------|
| PROJECT     | NORTH KENT 1<br>VIBRATION MONITORING              |           |                     |
| FILE        | TURBINE PILES AND WATER WELL<br>LOCATION PLAN, T7 |           |                     |
| PROJECT No. | 1688031   | FILE No.  | 1688031-2000-R02017 |
| DATE        | DOH/ZLB Sep. 18/17                                | SCALE     | AS SHOWN TYP.       |
| CHECKS      |   |           |                     |
|             |   | FIGURE T7 |                     |







SITE PLAN



INSET A (WELL #6)



INSET B (WELL #5)



TURBINE PILE LAYOUT

#### LEGEND

- INSTANTEL MINIMATE GEOPHONE
- WATER WELL
- TURBINE BEING CONSTRUCTED
- MN MAGNETIC NORTH
- UTM-N UNIVERSAL TRANSVERSE MERCATOR GEOGRAPHIC NORTH

#### REFERENCE

DRAWING BASED ON 2010 AERIAL IMAGERY PROVIDED BY THE MUNICIPALITY OF CHATHAM-KENT. INCLUDES MATERIAL c 2015 OF THE QUEEN'S PRINTER FOR ONTARIO; AND "FOUNDATION PLAN", ENTUITIVE, PROJECT No. C017-0190, DWG No. S002.

#### NOTES


THIS DRAWING IS SCHEMATIC ONLY AND IS TO BE READ IN CONJUNCTION WITH ACCOMPANYING TEXT.  
ALL LOCATIONS ARE APPROXIMATE.

|         |             |  |                               |
|---------|-------------|--|-------------------------------|
| PROJECT |             | NORTH KENT 1<br>VIBRATION MONITORING               |                               |
| TITLE   |             | TURBINE PILES AND WATER WELL<br>LOCATION PLAN, T12 |                               |
|         | PROJECT NO. | 16686031   | FILE NO. 16686031-2000-RC2T12 |
|         | DATE        | DCH/ZLB  | Sept. 20/17                   |
|         | CHECKED     |  |                               |
| SCALE   |             | AS SHOWN   |                               |
|         |             | FIGURE T12   |                               |







**SITE PLAN**



**INSET A (WELL #13)**



**INSET B (WELL #14)**



**TURBINE PILE LAYOUT**

#### LEGEND

- INSTANTEL MINIMATE GEOPHONE
- WATER WELL
- TURBINE BEING CONSTRUCTED
- MN MAGNETIC NORTH
- UTM-N UNIVERSAL TRANSVERSE MERCATOR GEOGRAPHIC NORTH

#### REFERENCE


DRAWING BASED ON 2010 AERIAL IMAGERY PROVIDED BY THE MUNICIPALITY OF CHATHAM-KENT. INCLUDES MATERIAL c 2015 OF THE QUEEN'S PRINTER FOR ONTARIO; AND "FOUNDATION PLAN", ENTUTIVE, PROJECT No. C017-0190, DWG No. S002.

#### NOTES


THIS DRAWING IS SCHEMATIC ONLY AND IS TO BE READ IN CONJUNCTION WITH ACCOMPANYING TEXT.  
ALL LOCATIONS ARE APPROXIMATE.

|  |             |         |                              |
|--|-------------|---------|------------------------------|
| PROJECT  |             |         |                              |
| NORTH KENT 1<br>VIBRATION MONITORING               |             |         |                              |
| TITLE  |             |         |                              |
| TURBINE PILES AND WATER WELL<br>LOCATION PLAN, T14 |             |         |                              |
|  | PROJECT No. | 1668031 | FILE NO. 1668031-2000-R02T14 |
|  | DATE        | DOH/ZLB | Sept. 18/17                  |
|  | CHECKED     |         |                              |
| SCALE  |             |         | AS SHOWN                     |
| <b>FIGURE T14</b>                                  |             |         |                              |







SITE PLAN



INSET A (WELL #11)



INSET B (WELL #12)



TURBINE PILE LAYOUT

#### LEGEND

- INSTANTEL MINIMATE GEOPHONE
- WATER WELL
- TURBINE BEING CONSTRUCTED
- MN MAGNETIC NORTH
- UTM-N UNIVERSAL TRANSVERSE MERCATOR GEOGRAPHIC NORTH

#### REFERENCE

DRAWING BASED ON 2010 AERIAL IMAGERY PROVIDED BY THE MUNICIPALITY OF CHATHAM-KENT. INCLUDES MATERIAL c 2015 OF THE QUEEN'S PRINTER FOR ONTARIO; AND 'FOUNDATION PLAN', ENTUTIVE, PROJECT No. C017-0190, DWG No. S002.

#### NOTES


THIS DRAWING IS SCHEMATIC ONLY AND IS TO BE READ IN CONJUNCTION WITH ACCOMPANYING TEXT.  
ALL LOCATIONS ARE APPROXIMATE.

|  |             |                     |                              |
|--|-------------|---------------------|------------------------------|
| PROJECT  |             |                     |                              |
| NORTH KENT 1<br>VIBRATION MONITORING               |             |                     |                              |
| TITLE  |             |                     |                              |
| TURBINE PILES AND WATER WELL<br>LOCATION PLAN, T20 |             |                     |                              |
|  | PROJECT NO. | 1668031             | FILE NO. 1668031-2000-RC2120 |
|  | DATE        | DCH/ZLB Sept. 18/17 | SCALE AS SHOWN               |
|  | CHECKED     |                     | REV.                         |
|  |             |                     | FIGURE T20                   |







SITE PLAN



INSET A (WELL #11)



INSET B (WELL #12)



TURBINE PILE LAYOUT

#### LEGEND

- INSTANTEL MINIMATE GEOPHONE
- WATER WELL
- TURBINE BEING CONSTRUCTED
- MN MAGNETIC NORTH
- UTM-N UNIVERSAL TRANSVERSE MERCATOR GEOGRAPHIC NORTH

#### REFERENCE


DRAWING BASED ON 2010 AERIAL IMAGERY PROVIDED BY THE MUNICIPALITY OF CHATHAM-KENT. INCLUDES MATERIAL c 2015 OF THE QUEEN'S PRINTER FOR ONTARIO; AND "FOUNDATION PLAN", ENTUTIVE, PROJECT No. C017-0190, DWG No. SC02.

#### NOTES


THIS DRAWING IS SCHEMATIC ONLY AND IS TO BE READ IN CONJUNCTION WITH ACCOMPANYING TEXT.  
ALL LOCATIONS ARE APPROXIMATE.

|  |         |          |                      |
|--|---------|----------|----------------------|
| PROJECT  |         |          |                      |
| NORTH KENT 1<br>VIBRATION MONITORING               |         |          |                      |
| TITLE  |         |          |                      |
| TURBINE PILES AND WATER WELL<br>LOCATION PLAN, T21 |         |          |                      |
| PROJECT No.  | 1058031 | FILE No. | 1058031-2000-RC02T21 |
| DRAWN BY   | DCH/ZLB | DATE     | Sept. 18/17          |
| CHECKED  |         | SCALE    | AS SHOWN             |
| Golden Associates                                  |         |          | FIGURE T21           |







SITE PLAN



INSET A (WELL #13)



INSET B (WELL #14)



N.T.S.

TURBINE PILE LAYOUT

#### LEGEND

- INSTANTEL MINIMATE GEOPHONE
- WATER WELL
- TURBINE BEING CONSTRUCTED
- MN MAGNETIC NORTH
- UTM-N UNIVERSAL TRANSVERSE MERCATOR GEOGRAPHIC NORTH

#### REFERENCE

DRAWING BASED ON 2010 AERIAL IMAGERY PROVIDED BY THE MUNICIPALITY OF CHATHAM-KENT. INCLUDES MATERIAL c 2015 OF THE QUEEN'S PRINTER FOR ONTARIO; AND 'FOUNDATION PLAN', ENTUTIVE, PROJECT No. C017-0190, DWG No. S002.

#### NOTES


THIS DRAWING IS SCHEMATIC ONLY AND IS TO BE READ IN CONJUNCTION WITH ACCOMPANYING TEXT.  
ALL LOCATIONS ARE APPROXIMATE.

|  |             |          |                               |
|--|-------------|----------|-------------------------------|
| PROJECT  |             |          |                               |
| NORTH KENT 1<br>VIBRATION MONITORING               |             |          |                               |
| TITLE  |             |          |                               |
| TURBINE PILES AND WATER WELL<br>LOCATION PLAN, T26 |             |          |                               |
|  | PROJECT NO. | 16686031 | FILE NO. 16686031-2000-RC2126 |
|  | DRAWN       | DCH/ZLB  | DATE 20/17                    |
|  | CHECKED     |          |                               |
|  |             | SCALE    | AS SHOWN                      |
|  |             | FIGURE   | FIGURE T26                    |







**SITE PLAN**



**INSET A (WELL #13)**



**INSET B (WELL #14)**



**TURBINE PILE LAYOUT**

#### LEGEND

- INSTANTEL MINIMATE GEOPHONE
- WATER WELL
- TURBINE BEING CONSTRUCTED
- MN MAGNETIC NORTH
- UTM-N UNIVERSAL TRANSVERSE MERCATOR GEOGRAPHIC NORTH

#### REFERENCE


DRAWING BASED ON 2010 AERIAL IMAGERY PROVIDED BY THE MUNICIPALITY OF CHATHAM-KENT. INCLUDES MATERIAL c 2015 OF THE QUEEN'S PRINTER FOR ONTARIO; AND "FOUNDATION PLAN", ENTUTIVE, PROJECT No. C017-0190, DWG No. S002.

#### NOTES


THIS DRAWING IS SCHEMATIC ONLY AND IS TO BE READ IN CONJUNCTION WITH ACCOMPANYING TEXT.  
ALL LOCATIONS ARE APPROXIMATE.

|  |             |         |                              |
|--|-------------|---------|------------------------------|
| PROJECT  |             |         |                              |
| NORTH KENT 1<br>VIBRATION MONITORING               |             |         |                              |
| TITLE  |             |         |                              |
| TURBINE PILES AND WATER WELL<br>LOCATION PLAN, T27 |             |         |                              |
|  | PROJECT NO. | 1668031 | FILE NO. 1668031-2000-RC2127 |
|  | DATE        | DCH/ZLB | Sept 20/17                   |
|  | CHECKED     |         |                              |
| SCALE  |             |         | AS SHOWN                     |
|  |             |         | FIGURE T27                   |







**SITE PLAN**



**INSET A (WELL #9)**






**INSET B (WELL #10)**



**TURBINE PILE LAYOUT**

#### LEGEND


-  INSTANTEL MINIMATE GEOPHONE
-  WATER WELL
-  TURBINE BEING CONSTRUCTED
- MN MAGNETIC NORTH
- UTM-N UNIVERSAL TRANSVERSE MERCATOR GEOGRAPHIC NORTH

#### REFERENCE

DRAWING BASED ON 2010 AERIAL IMAGERY PROVIDED BY THE MUNICIPALITY OF CHATHAM-KENT. INCLUDES MATERIAL c 2015 OF THE QUEEN'S PRINTER FOR ONTARIO; AND "FOUNDATION PLAN", ENTUTIVE, PROJECT No. C017-0190, DWG No. S002.

#### NOTES


THIS DRAWING IS SCHEMATIC ONLY AND IS TO BE READ IN CONJUNCTION WITH ACCOMPANYING TEXT.  
ALL LOCATIONS ARE APPROXIMATE.

|   |                     |                   |                     |
|---|---------------------|-------------------|---------------------|
| PROJECT   |                     |                   |                     |
| NORTH KENT 1<br>VIBRATION MONITORING  |                     |                   |                     |
| TITLE   |                     |                   |                     |
| TURBINE PILES AND WATER WELL<br>LOCATION PLAN, T28                                    |                     |                   |                     |
| PROJECT No.   | 1098031             | FILE No.          | 1098031-2000-R02728 |
| DATE  | DOH/ZLB Sept. 20/17 | SCALE             | AS SHOWN            |
| CHECKS  |                     |                   |                     |
|  |                     | <b>FIGURE T28</b> |                     |







**SITE PLAN**



**INSET A (WELL #9)**



**INSET B (WELL #10)**



N.T.S.

**TURBINE PILE LAYOUT**

#### LEGEND

- INSTANTEL MINIMATE GEOPHONE
- WATER WELL
- TURBINE BEING CONSTRUCTED
- MN MAGNETIC NORTH
- UTM-N UNIVERSAL TRANSVERSE MERCATOR GEOGRAPHIC NORTH

#### REFERENCE

DRAWING BASED ON 2010 AERIAL IMAGERY PROVIDED BY THE MUNICIPALITY OF CHATHAM-KENT. INCLUDES MATERIAL c 2015 OF THE QUEEN'S PRINTER FOR ONTARIO; AND 'FOUNDATION PLAN', ENTUTIVE, PROJECT No. C017-0190, DWG No. S002.


#### NOTES

THIS DRAWING IS SCHEMATIC ONLY AND IS TO BE READ IN CONJUNCTION WITH ACCOMPANYING TEXT.  
ALL LOCATIONS ARE APPROXIMATE.

|  |             |          |                               |
|--|-------------|----------|-------------------------------|
| PROJECT  |             |          |                               |
| NORTH KENT 1<br>VIBRATION MONITORING               |             |          |                               |
| TITLE  |             |          |                               |
| TURBINE PILES AND WATER WELL<br>LOCATION PLAN, T30 |             |          |                               |
|  | PROJECT NO. | 16686031 | FILE NO. 16686031-2000-RC2130 |
|  | DATE        | DCH/ZLB  | Sept. 20/17                   |
|  | CHECKED     |          |                               |
|  |             | SCALE    | AS SHOWN                      |
|  |             | REV.     |                               |

**FIGURE T30**







**SITE PLAN**



**INSET A (WELL #7)**



**INSET B (WELL #8)**



**TURBINE PILE LAYOUT**

#### LEGEND

- INSTANTEL MINIMATE GEOPHONE
- WATER WELL
- TURBINE BEING CONSTRUCTED
- MN MAGNETIC NORTH
- UTM-N UNIVERSAL TRANSVERSE MERCATOR GEOGRAPHIC NORTH

#### REFERENCE

DRAWING BASED ON 2010 AERIAL IMAGERY PROVIDED BY THE MUNICIPALITY OF CHATHAM-KENT. INCLUDES MATERIAL c 2015 OF THE QUEEN'S PRINTER FOR ONTARIO; AND "FOUNDATION PLAN", ENTUTIVE, PROJECT No. C017-0190, DWG No. S002.

#### NOTES


THIS DRAWING IS SCHEMATIC ONLY AND IS TO BE READ IN CONJUNCTION WITH ACCOMPANYING TEXT.  
ALL LOCATIONS ARE APPROXIMATE.

|  |             |                     |                              |
|--|-------------|---------------------|------------------------------|
| PROJECT  |             |                     |                              |
| NORTH KENT 1<br>VIBRATION MONITORING               |             |                     |                              |
| TITLE  |             |                     |                              |
| TURBINE PILES AND WATER WELL<br>LOCATION PLAN, T31 |             |                     |                              |
|  | PROJECT No. | 1058031             | FILE No. 1058031-2000-RC2131 |
|  | DATE        | DOH/ZLB Sept. 18/17 | SCALE AS SHOWN               |
|  | CHECKED     |                     | FIGURE T31                   |
|  | APPROVED    |                     |                              |







**SITE PLAN**



**INSET A (WELL #9)**



**INSET B (WELL #10)**



N.T.S.

**TURBINE PILE LAYOUT**

#### LEGEND

- INSTANTEL MINIMATE GEOPHONE
- WATER WELL
- TURBINE BEING CONSTRUCTED
- MN MAGNETIC NORTH
- UTM-N UNIVERSAL TRANSVERSE MERCATOR GEOGRAPHIC NORTH

#### REFERENCE

DRAWING BASED ON 2010 AERIAL IMAGERY PROVIDED BY THE MUNICIPALITY OF CHATHAM-KENT. INCLUDES MATERIAL c 2015 OF THE QUEEN'S PRINTER FOR ONTARIO; AND "FOUNDATION PLAN", ENTUTIVE, PROJECT No. C017-0190, DWG No. S002.

#### NOTES


THIS DRAWING IS SCHEMATIC ONLY AND IS TO BE READ IN CONJUNCTION WITH ACCOMPANYING TEXT.  
ALL LOCATIONS ARE APPROXIMATE.

|  |         |                   |                     |
|--|---------|-------------------|---------------------|
| PROJECT  |         |                   |                     |
| NORTH KENT 1<br>VIBRATION MONITORING               |         |                   |                     |
| TITLE  |         |                   |                     |
| TURBINE PILES AND WATER WELL<br>LOCATION PLAN, T32 |         |                   |                     |
| PROJECT No.  | 1688031 | FILE No.          | 1688031-2000-R02T32 |
| DATE   | DOH/ZLB | DATE              | AS SHOWN            |
| CHECKED  |         | DATE              | 18/17               |
|  |         | <b>FIGURE T32</b> |                     |







SITE PLAN



INSET A (WELL #3)



INSET B (WELL #4)



N.T.S.

TURBINE PILE LAYOUT

#### LEGEND

- INSTANTEL MINIMATE GEOPHONE
- WATER WELL
- TURBINE BEING CONSTRUCTED
- MN MAGNETIC NORTH
- UTM-N UNIVERSAL TRANSVERSE MERCATOR GEOGRAPHIC NORTH

#### REFERENCE

DRAWING BASED ON 2010 AERIAL IMAGERY PROVIDED BY THE MUNICIPALITY OF CHATHAM-KENT. INCLUDES MATERIAL © 2015 OF THE QUEEN'S PRINTER FOR ONTARIO; AND "FOUNDATION PLAN", ENTUTIVE, PROJECT No. C017-0190, DWG No. S002.


#### NOTES

THIS DRAWING IS SCHEMATIC ONLY AND IS TO BE READ IN CONJUNCTION WITH ACCOMPANYING TEXT.  
ALL LOCATIONS ARE APPROXIMATE.


|  |             |                     |                               |
|--|-------------|---------------------|-------------------------------|
| PROJECT  |             |                     |                               |
| NORTH KENT 1<br>VIBRATION MONITORING               |             |                     |                               |
| TITLE  |             |                     |                               |
| TURBINE PILES AND WATER WELL<br>LOCATION PLAN, T33 |             |                     |                               |
|  | PROJECT NO. | 16686031            | FILE NO. 16686031-2000-RC2133 |
|  | DATE        | DCH/ZLB Sept. 18/17 | SCALE AS SHOWN                |
|  | CHECKED     |                     | FIGURE T33                    |




Drawing file: "666031\_2000\_R02"35.dwg Sep 20, 2017 12:47pm




SITE PLAN



INSET A (WELL #6)



INSET B (WELL #5)



TURBINE PILE LAYOUT

#### LEGEND

- INSTANTEL MINIMATE GEOPHONE
- WATER WELL
- TURBINE BEING CONSTRUCTED
- MN MAGNETIC NORTH
- UTM-N UNIVERSAL TRANSVERSE MERCATOR GEOGRAPHIC NORTH

#### REFERENCE

DRAWING BASED ON 2010 AERIAL IMAGERY PROVIDED BY THE MUNICIPALITY OF CHATHAM-KENT. INCLUDES MATERIAL c 2015 OF THE QUEEN'S PRINTER FOR ONTARIO; AND "FOUNDATION PLAN", ENTUTIVE, PROJECT No. C017-0190, DWG No. S002.


#### NOTES

THIS DRAWING IS SCHEMATIC ONLY AND IS TO BE READ IN CONJUNCTION WITH ACCOMPANYING TEXT.  
ALL LOCATIONS ARE APPROXIMATE.


|  |             |          |                              |
|--|-------------|----------|------------------------------|
| PROJECT  |             |          |                              |
| NORTH KENT 1<br>VIBRATION MONITORING               |             |          |                              |
| TITLE  |             |          |                              |
| TURBINE PILES AND WATER WELL<br>LOCATION PLAN, T35 |             |          |                              |
|  | PROJECT No. | 1098031  | FILE No. 1098031-2000-R02T35 |
|  | DATE        | 09/28/18 | SCALE AS SHOWN               |
|  | DRAWN BY    | 18/17    |                              |
|  |             |          | FIGURE T35                   |




SITE PLAN



INSET A (WELL #6)



INSET B (WELL #5)



TURBINE PILE LAYOUT

#### LEGEND

- INSTANTEL MINIMATE GEOPHONE
- WATER WELL
- TURBINE BEING CONSTRUCTED
- MN MAGNETIC NORTH
- UTM-N UNIVERSAL TRANSVERSE MERCATOR GEOGRAPHIC NORTH

#### REFERENCE

DRAWING BASED ON 2010 AERIAL IMAGERY PROVIDED BY THE MUNICIPALITY OF CHATHAM-KENT. INCLUDES MATERIAL © 2015 OF THE QUEEN'S PRINTER FOR ONTARIO; AND "FOUNDATION PLAN", ENTUITIVE, PROJECT No. C017-0190, DWG No. S002.

#### NOTES

THIS DRAWING IS SCHEMATIC ONLY AND IS TO BE READ IN CONJUNCTION WITH ACCOMPANYING TEXT.  
ALL LOCATIONS ARE APPROXIMATE.


|  |             |             |                               |
|--|-------------|-------------|-------------------------------|
| PROJECT  |             |             |                               |
| NORTH KENT 1<br>VIBRATION MONITORING               |             |             |                               |
| TITLE  |             |             |                               |
| TURBINE PILES AND WATER WELL<br>LOCATION PLAN, T36 |             |             |                               |
|  | PROJECT No. | 16686031    | FILE No. 16686031-2000-R02T36 |
|  | DATE        | 09/20/2017  | SCALE AS SHOWN                |
|  | CHECKED     | SEP 20 2017 | REV.                          |
| FIGURE T36   |             |             |                               |




Drawing file: '608021-2000-RC2143.dwg' Sep 20, 2017 - 12:00pm




SITE PLAN



INSET A (WELL #11)



INSET B (WELL #12)



TURBINE PILE LAYOUT

#### LEGEND

- INSTANTEL MINIMATE GEOPHONE
- WATER WELL
- TURBINE BEING CONSTRUCTED
- MN MAGNETIC NORTH
- UTM-N UNIVERSAL TRANSVERSE MERCATOR GEOGRAPHIC NORTH

#### REFERENCE

DRAWING BASED ON 2010 AERIAL IMAGERY PROVIDED BY THE MUNICIPALITY OF CHATHAM-KENT. INCLUDES MATERIAL c 2015 OF THE QUEEN'S PRINTER FOR ONTARIO; AND "FOUNDATION PLAN", ENTUTIVE, PROJECT No. C017-0190, DWG No. S002.


#### NOTES

THIS DRAWING IS SCHEMATIC ONLY AND IS TO BE READ IN CONJUNCTION WITH ACCOMPANYING TEXT.  
ALL LOCATIONS ARE APPROXIMATE.


|  |             |            |                              |
|--|-------------|------------|------------------------------|
| PROJECT  |             |            |                              |
| NORTH KENT 1<br>VIBRATION MONITORING               |             |            |                              |
| TITLE  |             |            |                              |
| TURBINE PILES AND WATER WELL<br>LOCATION PLAN, T43 |             |            |                              |
|  | PROJECT NO. | 1668031    | FILE NO. 1668031-2000-RC2143 |
|  | DATE        | 09/21/2017 | SCALE AS SHOWN               |
|  | CHG         |            | REV                          |
|  |             |            | FIGURE T43                   |




Drawing file: '608021-2000-RC2145.dwg' Sep '08, 2017 - 2:07pm




SITE PLAN



INSET A (WELL #11)



INSET B (WELL #12)



N.T.S.

TURBINE PILE LAYOUT

#### LEGEND

- INSTANTEL MINIMATE GEOPHONE
- WATER WELL
- TURBINE BEING CONSTRUCTED
- MN MAGNETIC NORTH
- UTM-N UNIVERSAL TRANSVERSE MERCATOR GEOGRAPHIC NORTH

#### REFERENCE

DRAWING BASED ON 2010 AERIAL IMAGERY PROVIDED BY THE MUNICIPALITY OF CHATHAM-KENT. INCLUDES MATERIAL c 2015 OF THE QUEEN'S PRINTER FOR ONTARIO; AND "FOUNDATION PLAN", ENTUTIVE, PROJECT No. C017-0190, DWG No. S002.

#### NOTES


THIS DRAWING IS SCHEMATIC ONLY AND IS TO BE READ IN CONJUNCTION WITH ACCOMPANYING TEXT.  
ALL LOCATIONS ARE APPROXIMATE.

|         |             |  |                              |
|---------|-------------|--|------------------------------|
| PROJECT |             | NORTH KENT 1<br>VIBRATION MONITORING               |                              |
| TITLE   |             | TURBINE PILES AND WATER WELL<br>LOCATION PLAN, T45 |                              |
|         | PROJECT NO. | 1668031  | FILE NO. 1668031-2000-RC2145 |
|         | DATE        | DCH/ZLB  | Sept. 18/17                  |
|         | CHECKED     |  |                              |
|         |             | SCALE  | AS SHOWN                     |
|         |             | REV.   |                              |


FIGURE T45




Drawing file: '668031\_0000\_R02T46.dwg' Sep -8, 2017 2:07pm




SITE PLAN



INSET A (WELL #11)



INSET B (WELL #12)



TURBINE PILE LAYOUT

#### LEGEND

- INSTANTEL MINIMATE GEOPHONE
- WATER WELL
- TURBINE BEING CONSTRUCTED
- MN MAGNETIC NORTH
- UTM-N UNIVERSAL TRANSVERSE MERCATOR GEOGRAPHIC NORTH

#### REFERENCE

DRAWING BASED ON 2010 AERIAL IMAGERY PROVIDED BY THE MUNICIPALITY OF CHATHAM-KENT. INCLUDES MATERIAL c 2015 OF THE QUEEN'S PRINTER FOR ONTARIO; AND "FOUNDATION PLAN", ENTUTIVE, PROJECT No. C017-0190, DWG No. SC02.

#### NOTES

THIS DRAWING IS SCHEMATIC ONLY AND IS TO BE READ IN CONJUNCTION WITH ACCOMPANYING TEXT.  
ALL LOCATIONS ARE APPROXIMATE.

|  |             |          |                              |
|--|-------------|----------|------------------------------|
| PROJECT  |             |          |                              |
| NORTH KENT 1<br>VIBRATION MONITORING               |             |          |                              |
| TITLE  |             |          |                              |
| TURBINE PILES AND WATER WELL<br>LOCATION PLAN, T46 |             |          |                              |
|  | PROJECT No. | 1668031  | FILE No. 1668031-2000-R02T46 |
|  | DATE        | DCH/ZLB  | Sept. 18/17                  |
|  | CHECK       |          |                              |
|  | SCALE       | AS SHOWN | REV.                         |
| FIGURE T46   |             |          |                              |

**AECOM**

# Attachment **C**

**MOECC Water Well  
Record**





## The Ontario Water Resources Act

# WATER WELL RECORD

1. PRINT ONLY IN SPACES PROVIDED

2. CHECK ☒ CORRECT BOX WHERE APPLICABLE

11

3308387

MUNICIP  
|3,30,02

CON.  
|C|O|N|

106

COUNTY OR DISTRICT

TOWNSHIP, BOROUGH, CITY, TOWN, VILLAGE

CON BLOCK TRACT SURVEY, ETC

|     |       |
|-----|-------|
| LOT | 25-27 |
|-----|-------|

DATE COMPLETED 48-53

DAY 24 MO 11 YR 80

705293

|    |           |
|----|-----------|
| RC | ELEVATION |
|    | 600       |

BASIN CODE

11

iv

## LOG OF OVERBURDEN AND BEDROCK MATERIALS (SEE INSTRUCTIONS)

[illegible]

31

32

41 WATER RECORD

| WATER FOUND<br>AT - FEET |   | KIND OF WATER   |   |
|--------------------------|---|---|---|
| 10-13                    | 1 <input checked="" type="checkbox"/> FRESH | 3 <input type="checkbox"/> SULPHUR                                    | 1 |
|                          | 2 <input type="checkbox"/> SALTY            | 4 <input type="checkbox"/> MINERALS<br>6 <input type="checkbox"/> GAS |   |
| 15-18                    | 1 <input type="checkbox"/> FRESH            | 3 <input type="checkbox"/> SULPHUR                                    | 1 |
|                          | 2 <input type="checkbox"/> SALTY            | 4 <input type="checkbox"/> MINERALS<br>6 <input type="checkbox"/> GAS |   |
| 20-23                    | 1 <input type="checkbox"/> FRESH            | 3 <input type="checkbox"/> SULPHUR                                    | 2 |
|                          | 2 <input type="checkbox"/> SALTY            | 4 <input type="checkbox"/> MINERALS<br>6 <input type="checkbox"/> GAS |   |
| 25-28                    | 1 <input type="checkbox"/> FRESH            | 3 <input type="checkbox"/> SULPHUR                                    | 2 |
|                          | 2 <input type="checkbox"/> SALTY            | 4 <input type="checkbox"/> MINERALS<br>6 <input type="checkbox"/> GAS |   |
| 30-33                    | 1 <input type="checkbox"/> FRESH            | 3 <input type="checkbox"/> SULPHUR                                    | 3 |
|                          | 2 <input type="checkbox"/> SALTY            | 4 <input type="checkbox"/> MINERALS<br>6 <input type="checkbox"/> GAS |   |

## 51 CASING &amp; OPEN HOLE RECORD

| INSIDE<br>DIAM<br>INCHES | MATERIAL  | WALL<br>THICKNESS<br>INCHES | DEPTH - FEET |       |
|--------------------------|---|-----------------------------|--------------|-------|
|                          |   |                             | FROM         | TO    |
| 10-11<br>5               | <input checked="" type="checkbox"/> STEEL<br><input type="checkbox"/> GALVANIZED<br><input type="checkbox"/> CONCRETE<br><input type="checkbox"/> OPEN HOLE<br><input type="checkbox"/> PLASTIC | 12<br>188                   | 0            | 62    |
| 17-18                    | <input type="checkbox"/> STEEL<br><input type="checkbox"/> GALVANIZED<br><input type="checkbox"/> CONCRETE<br><input checked="" type="checkbox"/> OPEN HOLE<br><input type="checkbox"/> PLASTIC | 19                          | 62           | 63    |
| 24-25                    | <input type="checkbox"/> STEEL<br><input type="checkbox"/> GALVANIZED<br><input type="checkbox"/> CONCRETE<br><input type="checkbox"/> OPEN HOLE<br><input type="checkbox"/> PLASTIC            | 26                          |              | 27-30 |

**SCREEN**

|                               |       |                           |       |        |       |
|-------------------------------|-------|---------------------------|-------|--------|-------|
| SIZE OF OPENING<br>(SLOT NO.) | 31-33 | DIAMETER                  | 34-38 | LENGTH | 39-40 |
|                               |       | INCHES                    |       | FEET   |       |
| MATERIAL AND TYPE             |       | DEPTH TO TOP<br>OF SCREEN |       | 41-44  | 10    |
|                               |       |                           |       | FEET   |       |

## 61 PLUGGING & SEALING RECORD

| DEPTH SET AT - FEET |       | MATERIAL AND TYPE<br>(CEMENT GROUT<br>LEAD PACKER, ETC.) |
|---------------------|-------|--|
| FROM                | TO    |  |
| 10-13               | 14-17 |  |
| 18-21               | 22-25 |  |
| 26-29               | 30-33 | 80   |

|   |   |                            |                          |                     |                          |            |   |                        |
|---|---|----------------------------|--------------------------|---------------------|--------------------------|------------|---|------------------------|
| PUMPING TEST  | PUMPING TEST METHOD   |                            | 10                       | PUMPING RATE        |                          | 11-14      | DURATION OF PUMPING   |                        |
|   | 1 <input type="checkbox"/> PUMP 2 <input type="checkbox"/> BAILER |                            |                          | 4                   |                          | GPM        | 5   | 15-18 HOURS 17-18 MINS |
|   | STATIC LEVEL  | WATER LEVEL END OF PUMPING | 25                       | WATER LEVELS DURING |                          |            | 1 <input checked="" type="checkbox"/> PUMPING 2 <input type="checkbox"/> RECOVERY |                        |
|   | 10-21   | 22-24                      | 15 MINUTES               | 30 MINUTES          | 45 MINUTES               | 60 MINUTES |   |                        |
|   | 13 FEET   | 25 FEET                    | 17 FEET                  | 21 FEET             | 24 FEET                  | 25 FEET    |   |                        |
| IF FLOWING, GIVE RATE   |   |                            | 30-41                    | PUMP INTAKE SET AT  |                          |            | WATER AT END OF TEST  |                        |
| GPM   |   |                            |                          | FEET                |                          |            | 1 <input checked="" type="checkbox"/> CLEAR 2 <input type="checkbox"/> CLOUDY     |                        |
| RECOMMENDED PUMP TYPE   |   |                            | RECOMMENDED PUMP SETTING | 43-45               | RECOMMENDED PUMPING RATE |            |   | 46-51                  |
| <input type="checkbox"/> SHALLOW <input checked="" type="checkbox"/> DEEP |   |                            | 50                       | FEET                |                          |            | 4   | GPM                    |
| 50-53   |   |                            |                          |                     |                          |            |   |                        |

|   |  |   |
|---|--|---|
| <div>54</div> <div>FINAL<br/>STATUS<br/>OF WELL</div>   | <div>1 <input checked="" type="checkbox"/> WATER SUPPLY</div> <div>2 <input type="checkbox"/> OBSERVATION WELL</div> <div>3 <input type="checkbox"/> TEST HOLE</div> <div>4 <input type="checkbox"/> RECHARGE WELL</div>   | <div>6 <input type="checkbox"/> ABANDONED. INSUFFICIENT SUPPLY</div> <div>8 <input type="checkbox"/> ABANDONED POOR QUALITY</div> <div>9 <input type="checkbox"/> UNFINISHED</div> <div>7 <input type="checkbox"/> DEWATERING</div>                                   |
| <div>55-56</div> <div>WATER<br/>USE</div>               | <div>1 <input checked="" type="checkbox"/> DOMESTIC</div> <div>2 <input type="checkbox"/> STOCK</div> <div>3 <input type="checkbox"/> IRRIGATION</div> <div>4 <input type="checkbox"/> INDUSTRIAL</div> <div><input type="checkbox"/> OTHER _____</div>                                | <div>5 <input type="checkbox"/> COMMERCIAL</div> <div>8 <input type="checkbox"/> MUNICIPAL</div> <div>7 <input type="checkbox"/> PUBLIC SUPPLY</div> <div>8 <input type="checkbox"/> COOLING OR AIR CONDITIONING</div> <div>9 <input type="checkbox"/> NOT USED</div> |
| <div>57</div> <div>METHOD<br/>OF<br/>CONSTRUCTION</div> | <div>1 <input checked="" type="checkbox"/> CABLE TOOL</div> <div>2 <input type="checkbox"/> ROTARY (CONVENTIONAL)</div> <div>3 <input type="checkbox"/> ROTARY (REVERSE)</div> <div>4 <input type="checkbox"/> ROTARY (AIR)</div> <div>5 <input type="checkbox"/> AIR PERCUSSION</div> | <div>6 <input type="checkbox"/> BORING</div> <div>7 <input type="checkbox"/> DIAMOND</div> <div>8 <input type="checkbox"/> JETTING</div> <div>9 <input type="checkbox"/> DRIVING</div> <div><input type="checkbox"/> DIGGING <input type="checkbox"/> OTHER</div>     |

## LOCATION OF WELL

IN DIAGRAM BELOW SHOW DISTANCES OF 70m FROM ROAD AND LOT LINE INDICATE NORTH BY ARROW

Caledonia  
Side Rd

36  
X ← 135 - 2

27611

DRILLERS REMARKS

Mr. J. A. Haskins

|            |                                      |  |                                  |  |
|------------|--------------------------------------|--|----------------------------------|--|
| CONTRACTOR | NAME OF WELL CONTRACTOR              |  | WELL CONTRACTOR'S LICENCE NUMBER |  |
|            | MARVIN L. HASTON                     |  | 3005                             |  |
|            | ADDRESS                              |  |                                  |  |
|            | R R 1 PAIN COURT                     |  |                                  |  |
|            | NAME OF WELL TECHNICIAN              |  | WELL TECHNICIAN'S LICENCE NUMBER |  |
|            | MARVIN L. HASTON                     |  | T0224                            |  |
|            | SIGNATURE OF TECHNICIAN / CONTRACTOR |  | SUBMISSION DATE                  |  |
|            | MARVIN L. HASTON                     |  | DAY 24 MO 11 YR 80               |  |

|                 |  |    |            |       |               |       |
|-----------------|--|----|------------|-------|---------------|-------|
| OFFICE USE ONLY | DATA SOURCE  | S8 | CONTRACTOR | S8-62 | DATE RECEIVED | 63-68 |
|                 |  |    | 3005       |       | JAN 13 1989   |       |
|                 | DATE OF INSPECTION   |    | INSPECTOR  |       |               |       |
|                 | REMARKS  |    |            |       |               |       |
|                 | <div style="border: 2px solid black; padding: 5px; display: inline-block;">WDE</div> <div style="margin-left: 200px;">CSS.S8</div> |    |            |       |               |       |

MINISTRY OF THE ENVIRONMENT COPY

FORM NO. 0506 (11/86) FORM 9

**AECOM**

# **Attachment D**

**Water Quality Data**

**CLIENT NAME: AECOM CANADA LTD  
105 COMMERCE VALLEY DR.W 7TH FLOOR  
MARKHAM, ON L3T7W3  
(905) 886-7022**

**ATTENTION TO: Erin Wilson**

**PROJECT: 60343599**

**AGAT WORK ORDER: 17T180137**

**MICROBIOLOGY ANALYSIS REVIEWED BY: Inesa Alizarchyk, Inorganic Lab Supervisor**

**WATER ANALYSIS REVIEWED BY: Mike Muneswar, BSc (Chem), Senior Inorganic Analyst**

**DATE REPORTED: Jan 30, 2017**

**PAGES (INCLUDING COVER): 9**

**VERSION\*: 1**

Should you require any information regarding this analysis please contact your client services representative at (905) 712-5100

**\*NOTES**

**All samples will be disposed of within 30 days following analysis. Please contact the lab if you require additional sample storage time.**

**AGAT** Laboratories (V1)

Member of: Association of Professional Engineers and Geoscientists of Alberta (APEGA)  
Western Enviro-Agricultural Laboratory Association (WEALA)  
Environmental Services Association of Alberta (ESAA)

AGAT Laboratories is accredited to ISO/IEC 17025 by the Canadian Association for Laboratory Accreditation Inc. (CALA) and/or Standards Council of Canada (SCC) for specific tests listed on the scope of accreditation. AGAT Laboratories (Mississauga) is also accredited by the Canadian Association for Laboratory Accreditation Inc. (CALA) for specific drinking water tests. Accreditations are location and parameter specific. A complete listing of parameters for each location is available from [www.cala.ca](http://www.cala.ca) and/or [www.scc.ca](http://www.scc.ca). The tests in this report may not necessarily be included in the scope of accreditation.

*Results relate only to the items tested and to all the items tested  
All reportable information as specified by ISO 17025:2005 is available from AGAT Laboratories upon request*



**AGAT** Laboratories

## Certificate of Analysis

AGAT WORK ORDER: 17T180137

PROJECT: 60343599

5835 COOPERS AVENUE  
MISSISSAUGA, ONTARIO  
CANADA L4Z 1Y2  
TEL (905)712-5100  
FAX (905)712-5122  
<http://www.agatlabs.com>

CLIENT NAME: AECOM CANADA LTD

SAMPLING SITE:

ATTENTION TO: Erin Wilson

SAMPLED BY: B. M.

### Microbiological Analysis (water)

DATE RECEIVED: 2017-01-23

DATE REPORTED: 2017-01-30

007420039;

SAMPLE DESCRIPTION:

SAMPLE TYPE:

Water

DATE SAMPLED:

2017-01-20

| Parameter        | Unit      | G / S | RDL | 8142060 |
|------------------|-----------|-------|-----|---------|
| Escherichia coli | CFU/100mL | 0     | 1   | NDOGN   |
| Total Coliforms  | CFU/100mL | 0     | 1   | NDOGN   |

**Comments:** RDL - Reported Detection Limit; G / S - Guideline / Standard: Refers to SDWA - Microbiology  
8142060 NDOGN – No Data; Overgrown with non- target, refers to over-crowding microbial growth;

Certified By:



# AGAT Laboratories

## Certificate of Analysis

AGAT WORK ORDER: 17T180137

PROJECT: 60343599

5835 COOPERS AVENUE  
MISSISSAUGA, ONTARIO  
CANADA L4Z 1Y2  
TEL (905)712-5100  
FAX (905)712-5122  
<http://www.agatlabs.com>

CLIENT NAME: AECOM CANADA LTD

SAMPLING SITE:

ATTENTION TO: Erin Wilson

SAMPLED BY: B. M.

### North Kent - Groundwater Samples

DATE RECEIVED: 2017-01-23

DATE REPORTED: 2017-01-30

007420039;

SAMPLE DESCRIPTION:

SAMPLE TYPE:

Water

DATE SAMPLED:

2017-01-20

| Parameter                              | Unit     | G / S     | RDL   | 8142060 |
|--|----------|-----------|-------|---------|
| Electrical Conductivity                | uS/cm    |           | 2     | 548     |
| pH                                     | pH Units | (6.5-8.5) | NA    | 8.23    |
| Total Hardness (as CaCO <sub>3</sub> ) | mg/L     | (80-100)  | 0.5   | 36.7    |
| Total Dissolved Solids                 | mg/L     | 500       | 20    | 292     |
| Total Suspended Solids                 | mg/L     |           | 10    | <10     |
| Alkalinity (as CaCO <sub>3</sub> )     | mg/L     | (30-500)  | 5     | 258     |
| Fluoride                               | mg/L     | 1.5       | 0.05  | 1.37    |
| Chloride                               | mg/L     | 250       | 0.10  | 20.7    |
| Nitrate as N                           | mg/L     | 10.0      | 0.05  | <0.05   |
| Nitrite as N                           | mg/L     | 1.0       | 0.05  | <0.05   |
| Bromide                                | mg/L     |           | 0.05  | 0.26    |
| Sulphate                               | mg/L     | 500       | 0.10  | <0.10   |
| Ammonia as N                           | mg/L     |           | 0.02  | 0.09    |
| Dissolved Organic Carbon               | mg/L     | 5         | 0.5   | 3.8     |
| Colour                                 | TCU      | 5         | 5     | 19      |
| Turbidity                              | NTU      | 5         | 0.5   | 3.7     |
| Calcium                                | mg/L     |           | 0.05  | 9.29    |
| Magnesium                              | mg/L     |           | 0.05  | 3.29    |
| Sodium                                 | mg/L     | 20 (200)  | 0.05  | 114     |
| Potassium                              | mg/L     |           | 0.05  | 1.33    |
| Iron                                   | mg/L     | 0.3       | 0.010 | 0.305   |
| Manganese                              | mg/L     | 0.05      | 0.002 | 0.010   |

Comments: RDL - Reported Detection Limit; G / S - Guideline / Standard: Refers to O.Reg.169/03(mg/L)

Certified By:



**AGAT** Laboratories

## Guideline Violation

AGAT WORK ORDER: 17T180137

PROJECT: 60343599

5835 COOPERS AVENUE  
MISSISSAUGA, ONTARIO  
CANADA L4Z 1Y2  
TEL (905)712-5100  
FAX (905)712-5122  
<http://www.agatlabs.com>

CLIENT NAME: AECOM CANADA LTD

ATTENTION TO: Erin Wilson

| SAMPLEID | SAMPLE TITLE          | GUIDELINE          | ANALYSIS PACKAGE                 | PARAMETER | UNIT | GUIDEVALUE | RESULT |
|----------|-----------------------|--------------------|----------------------------------|-----------|------|------------|--------|
| 8142060  | 007420039; [REDACTED] | O.Reg.169/03(mg/L) | North Kent - Groundwater Samples | Colour    | TCU  | 5          | 19     |
| 8142060  | 007420039; [REDACTED] | O.Reg.169/03(mg/L) | North Kent - Groundwater Samples | Iron      | mg/L | 0.3        | 0.305  |
| 8142060  | 007420039; [REDACTED] | O.Reg.169/03(mg/L) | North Kent - Groundwater Samples | Sodium    | mg/L | 20 (200)   | 114    |

## Quality Assurance

CLIENT NAME: AECOM CANADA LTD

PROJECT: 60343599

SAMPLING SITE:

AGAT WORK ORDER: 17T180137

ATTENTION TO: Erin Wilson

SAMPLED BY: B. M.

### Microbiology Analysis

| RPT Date: Jan 30, 2017 |       |           | DUPLICATE |        |     |              | REFERENCE MATERIAL |                   |       | METHOD BLANK SPIKE |                   |       | MATRIX SPIKE |                   |       |
|------------------------|-------|-----------|-----------|--------|-----|--------------|--------------------|-------------------|-------|--------------------|-------------------|-------|--------------|-------------------|-------|
| PARAMETER              | Batch | Sample Id | Dup #1    | Dup #2 | RPD | Method Blank | Measured Value     | Acceptable Limits |       | Recovery           | Acceptable Limits |       | Recovery     | Acceptable Limits |       |
|                        |       |           |           |        |     |              |                    | Lower             | Upper |                    | Lower             | Upper |              | Lower             | Upper |

#### Microbiological Analysis (water)

|                  |         |         |    |    |    |     |
|------------------|---------|---------|----|----|----|-----|
| Escherichia coli | 8142038 | 8142038 | ND | ND | NA | < 1 |
| Total Coliforms  | 8142038 | 8142038 | ND | ND | NA | < 1 |

Comments: ND - Not Detected, NA - % RPD Not Applicable

#### Microbiological Analysis (water)

|                  |         |         |       |       |    |     |
|------------------|---------|---------|-------|-------|----|-----|
| Escherichia coli | 8142104 | 8142104 | NDOGN | NDOGN | NA | < 1 |
| Total Coliforms  | 8142104 | 8142104 | NDOGN | NDOGN | NA | < 1 |

Comments: NDOGN – No Data; Overgrown with non- target, refers to over-crowding microbial growth;  
NA - % RPD Not Applicable

Certified By:





## Quality Assurance

CLIENT NAME: AECOM CANADA LTD

PROJECT: 60343599

SAMPLING SITE:

AGAT WORK ORDER: 17T180137

ATTENTION TO: Erin Wilson

SAMPLED BY: B. M.

| Water Analysis                   |         |           |           |        |      |              |                    |                   |       |                    |                   |       |              |                   |       |
|----------------------------------|---------|-----------|-----------|--------|------|--------------|--------------------|-------------------|-------|--------------------|-------------------|-------|--------------|-------------------|-------|
| RPT Date: Jan 30, 2017           |         |           | DUPLICATE |        |      | Method Blank | REFERENCE MATERIAL |                   |       | METHOD BLANK SPIKE |                   |       | MATRIX SPIKE |                   |       |
| PARAMETER                        | Batch   | Sample Id | Dup #1    | Dup #2 | RPD  |              | Measured Value     | Acceptable Limits |       | Recovery           | Acceptable Limits |       | Recovery     | Acceptable Limits |       |
|                                  |         |           |           |        |      |              |                    | Lower             | Upper |                    | Lower             | Upper |              | Lower             | Upper |
| North Kent - Groundwater Samples |         |           |           |        |      |              |                    |                   |       |                    |                   |       |              |                   |       |
| Electrical Conductivity          | 8142104 | 8142104   | 550       | 550    | 0.0% | < 2          | 101%               | 80%               | 120%  | NA                 |                   |       | NA           |                   |       |
| pH                               | 8142104 | 8142104   | 8.40      | 8.27   | 1.6% | NA           | 100%               | 90%               | 110%  | NA                 |                   |       | NA           |                   |       |
| Total Dissolved Solids           | 8142038 | 8142038   | 430       | 398    | 7.7% | < 20         | 98%                | 80%               | 120%  | NA                 |                   |       | NA           |                   |       |
| Total Suspended Solids           | 8142110 | 8142110   | < 10      | < 10   | NA   | < 10         | 96%                | 80%               | 120%  | NA                 |                   |       | NA           |                   |       |
| Alkalinity (as CaCO3)            | 8142104 | 8142104   | 256       | 265    | 3.5% | < 5          | 96%                | 80%               | 120%  | NA                 |                   |       | NA           |                   |       |
| Fluoride                         | 8142066 | 8142066   | 1.36      | 1.36   | 0.0% | < 0.05       | 94%                | 90%               | 110%  | 106%               | 90%               | 110%  | 95%          | 80%               | 120%  |
| Chloride                         | 8142066 | 8142066   | 21.0      | 20.6   | 1.9% | < 0.10       | 93%                | 90%               | 110%  | 103%               | 90%               | 110%  | 103%         | 80%               | 120%  |
| Nitrate as N                     | 8142066 | 8142066   | < 0.05    | <0.05  | NA   | < 0.05       | 94%                | 90%               | 110%  | 107%               | 90%               | 110%  | 101%         | 80%               | 120%  |
| Nitrite as N                     | 8142066 | 8142066   | < 0.05    | <0.05  | NA   | < 0.05       | NA                 | 90%               | 110%  | 93%                | 90%               | 110%  | 119%         | 80%               | 120%  |
| Bromide                          | 8142066 | 8142066   | 0.29      | 0.28   | 3.5% | < 0.05       | 106%               | 90%               | 110%  | 102%               | 90%               | 110%  | 84%          | 80%               | 120%  |
| Sulphate                         | 8142066 | 8142066   | < 0.10    | <0.10  | NA   | < 0.10       | 94%                | 90%               | 110%  | 99%                | 90%               | 110%  | 96%          | 80%               | 120%  |
| Ammonia as N                     | 8142054 | 8142054   | 0.10      | 0.10   | 0.0% | < 0.02       | 93%                | 90%               | 110%  | 98%                | 90%               | 110%  | 104%         | 80%               | 120%  |
| Dissolved Organic Carbon         | 8142038 | 8142038   | 2.4       | 2.2    | NA   | < 0.5        | 98%                | 90%               | 110%  | 92%                | 90%               | 110%  | 87%          | 80%               | 120%  |
| Colour                           | 8142048 | 8142048   | 7         | 7      | NA   | < 5          | 98%                | 90%               | 110%  | NA                 |                   |       | NA           |                   |       |
| Turbidity                        | 8142038 | 8142038   | 1.4       | 1.4    | NA   | < 0.5        | 104%               | 90%               | 110%  | NA                 |                   |       | NA           |                   |       |
| Calcium                          | 8142038 | 8142038   | 7.92      | 8.34   | 5.2% | < 0.05       | 102%               | 90%               | 110%  | 101%               | 90%               | 110%  | 99%          | 70%               | 130%  |
| Magnesium                        | 8142038 | 8142038   | 2.43      | 2.46   | 1.2% | < 0.05       | 96%                | 90%               | 110%  | 97%                | 90%               | 110%  | 96%          | 70%               | 130%  |
| Sodium                           | 8142038 | 8142038   | 169       | 174    | 2.9% | < 0.05       | 99%                | 90%               | 110%  | 100%               | 90%               | 110%  | 91%          | 70%               | 130%  |
| Potassium                        | 8142038 | 8142038   | 1.67      | 1.68   | 0.6% | < 0.05       | 99%                | 90%               | 110%  | 100%               | 90%               | 110%  | 99%          | 70%               | 130%  |
| Iron                             | 8142038 | 8142038   | 0.190     | 0.193  | 1.6% | < 0.010      | 105%               | 90%               | 110%  | 100%               | 90%               | 110%  | 105%         | 70%               | 130%  |
| Manganese                        | 8142038 | 8142038   | 0.009     | 0.009  | NA   | < 0.002      | 101%               | 90%               | 110%  | 103%               | 90%               | 110%  | 86%          | 70%               | 130%  |

Comments: NA signifies Not Applicable.

Duplicate Qualifier: As the measured result approaches the RL, the uncertainty associated with the value increases dramatically, thus duplicate acceptance limits apply only where the average of the two duplicates is greater than five times the RL.

Certified By:



## Method Summary

**CLIENT NAME:** AECOM CANADA LTD

**PROJECT:** 60343599

**SAMPLING SITE:**
**AGAT WORK ORDER:** 17T180137

**ATTENTION TO:** Erin Wilson

**SAMPLED BY:** B. M.

| PARAMETER                              | AGAT S.O.P   | LITERATURE REFERENCE                                | ANALYTICAL TECHNIQUE     |
|--|--------------|---|--------------------------|
| <b>Microbiology Analysis</b>           |              |   |                          |
| Escherichia coli                       | MIC-93-7010  | EPA 1604  | Membrane Filtration      |
| Total Coliforms                        | MIC-93-7010  | EPA 1604  | Membrane Filtration      |
| <b>Water Analysis</b>                  |              |   |                          |
| Electrical Conductivity                | INOR-93-6000 | SM 2510 B   | PC TITRATE               |
| pH                                     | INOR-93-6000 | SM 4500-H+ B  | PC TITRATE               |
| Total Hardness (as CaCO <sub>3</sub> ) | MET-93-6105  | EPA SW-846 6010C & 200.7                            | ICP/OES                  |
| Total Dissolved Solids                 | INOR-93-6028 | SM 2540 C   | BALANCE                  |
| Total Suspended Solids                 | INOR-93-6028 | SM 2540 D   | BALANCE                  |
| Alkalinity (as CaCO <sub>3</sub> )     | INOR-93-6000 | SM 2320 B   | PC TITRATE               |
| Fluoride                               | INOR-93-6004 | SM 4110 B   | ION CHROMATOGRAPH        |
| Chloride                               | INOR-93-6004 | SM 4110 B   | ION CHROMATOGRAPH        |
| Nitrate as N                           | INOR-93-6004 | SM 4110 B   | ION CHROMATOGRAPH        |
| Nitrite as N                           | INOR-93-6004 | SM 4110 B   | ION CHROMATOGRAPH        |
| Bromide                                | INOR-93-6004 | SM 4110 B   | ION CHROMATOGRAPH        |
| Sulphate                               | INOR-93-6004 | SM 4110 B   | ION CHROMATOGRAPH        |
| Ammonia as N                           | INOR-93-6059 | QuikChem 10-107-06-1-J & SM 4500 NH <sub>3</sub> -F | LACHAT FIA               |
| Dissolved Organic Carbon               | INOR-93-6049 | EPA 415.1 & SM 5310 B                               | SHIMADZU CARBON ANALYZER |
| Colour                                 | INOR-93-6046 | SM 2120 B   | SPECTROPHOTOMETER        |
| Turbidity                              | INOR-93-6044 | SM 2130 B   | NEPHELOMETER             |
| Calcium                                | MET-93-6105  | EPA SW-846 6010C & 200.7                            | ICP/OES                  |
| Magnesium                              | MET-93-6105  | EPA SW-846 6010C & 200.7                            | ICP/OES                  |
| Sodium                                 | MET-93-6105  | EPA SW-846 6010C & 200.7                            | ICP/OES                  |
| Potassium                              | MET-93-6105  | EPA SW-846 6010C & 200.7                            | ICP/OES                  |
| Iron                                   | MET-93-6103  | EPA SW-846 6020A & 200.8                            | ICP-MS                   |
| Manganese                              | MET-93-6103  | EPA SW-846 6020A & 200.8                            | ICP-MS                   |

CLIENT NAME: AECOM CANADA LTD  
105 Commerce Valley Drive West 7th Floor  
MARKHAM, ON L3T7W3  
(905) 886-7022

ATTENTION TO: Jason Murchison

PROJECT: 60343599

AGAT WORK ORDER: 17T270567

MICROBIOLOGY ANALYSIS REVIEWED BY: Nivine Basily, Inorganics Report Writer

WATER ANALYSIS REVIEWED BY: Yris Verastegui, Report Reviewer

DATE REPORTED: Oct 17, 2017

PAGES (INCLUDING COVER): 8

VERSION\*: 1

Should you require any information regarding this analysis please contact your client services representative at (905) 712-5100

\*NOTES

All samples will be disposed of within 30 days following analysis. Please contact the lab if you require additional sample storage time.



**AGAT** Laboratories

## Certificate of Analysis

AGAT WORK ORDER: 17T270567

PROJECT: 60343599

5835 COOPERS AVENUE  
MISSISSAUGA, ONTARIO  
CANADA L4Z 1Y2  
TEL (905)712-5100  
FAX (905)712-5122  
<http://www.agatlabs.com>

CLIENT NAME: AECOM CANADA LTD

ATTENTION TO: Jason Murchison

SAMPLING SITE:

SAMPLED BY:

### North Kent - Microbiological Analysis (water)

DATE RECEIVED: 2017-10-12

DATE REPORTED: 2017-10-17

007420039;

SAMPLE DESCRIPTION:

SAMPLE TYPE:

Water

DATE SAMPLED:

2017-10-11

| Parameter        | Unit      | G / S | RDL | 8807888 |
|------------------|-----------|-------|-----|---------|
| Escherichia coli | CFU/100mL | 0     | 1   | ND      |
| Total Coliforms  | CFU/100mL | 0     | 1   | 90      |

Comments: RDL - Reported Detection Limit; G / S - Guideline / Standard: Refers to SDWA - Microbiology  
Guideline values are for general reference only. The guidelines provided may or may not be relevant for the intended use. Refer directly to the applicable standard for regulatory interpretation.  
8807888 ND - Not Detected.

Certified By:

*Divine Basily*



## Certificate of Analysis

AGAT WORK ORDER: 17T270567

PROJECT: 60343599

5835 COOPERS AVENUE  
MISSISSAUGA, ONTARIO  
CANADA L4Z 1Y2  
TEL (905)712-5100  
FAX (905)712-5122  
<http://www.agatlabs.com>

CLIENT NAME: AECOM CANADA LTD

ATTENTION TO: Jason Murchison

SAMPLING SITE:

SAMPLED BY:

### North Kent - Groundwater Samples

DATE RECEIVED: 2017-10-12

DATE REPORTED: 2017-10-17

007420039;

SAMPLE DESCRIPTION:

SAMPLE TYPE:

Water

DATE SAMPLED:

2017-10-11

| Parameter                              | Unit        | G / S     | RDL   |       |
|--|-------------|-----------|-------|-------|
| Electrical Conductivity                | uS/cm       |           | 2     | 540   |
| pH                                     | pH Units    | (6.5-8.5) | NA    | 8.21  |
| Total Hardness (as CaCO <sub>3</sub> ) | mg/L        | (80-100)  | 0.5   | 37.2  |
| Total Dissolved Solids                 | mg/L        | 500       | 20    | 318   |
| Total Suspended Solids                 | mg/L        |           | 10    | <10   |
| Alkalinity (as CaCO <sub>3</sub> )     | mg/L        | (30-500)  | 5     | 269   |
| Fluoride                               | mg/L        | 1.5       | 0.05  | 1.44  |
| Chloride                               | mg/L        | 250       | 0.10  | 20.8  |
| Nitrate as N                           | mg/L        | 10.0      | 0.05  | <0.05 |
| Nitrite as N                           | mg/L        | 1.0       | 0.05  | <0.05 |
| Bromide                                | mg/L        |           | 0.05  | <0.05 |
| Sulphate                               | mg/L        | 500       | 0.10  | <0.10 |
| Ammonia as N                           | mg/L        |           | 0.02  | 0.69  |
| Dissolved Organic Carbon               | mg/L        | 5         | 0.5   | 4.2   |
| Colour                                 | Apparent CU | 5         | 5     | 67    |
| Turbidity                              | NTU         | 5         | 0.5   | 10.9  |
| Calcium                                | mg/L        |           | 0.05  | 9.44  |
| Magnesium                              | mg/L        |           | 0.05  | 3.32  |
| Sodium                                 | mg/L        | 20 (200)  | 0.05  | 116   |
| Potassium                              | mg/L        |           | 0.05  | 1.37  |
| Iron                                   | mg/L        | 0.3       | 0.010 | 0.733 |
| Manganese                              | mg/L        | 0.05      | 0.002 | 0.011 |

Comments: RDL - Reported Detection Limit; G / S - Guideline / Standard: Refers to O.Reg.169/03(mg/L)  
Guideline values are for general reference only. The guidelines provided may or may not be relevant for the intended use. Refer directly to the applicable standard for regulatory interpretation.

Certified By:

*José Verástegui*



## Guideline Violation

AGAT WORK ORDER: 17T270567

PROJECT: 60343599

5835 COOPERS AVENUE  
MISSISSAUGA, ONTARIO  
CANADA L4Z 1Y2  
TEL (905)712-5100  
FAX (905)712-5122  
<http://www.agatlabs.com>

CLIENT NAME: AECOM CANADA LTD

ATTENTION TO: Jason Murchison

| SAMPLEID | SAMPLE TITLE          | GUIDELINE           | ANALYSIS PACKAGE                              | PARAMETER       | UNIT        | GUIDEVALUE | RESULT |
|----------|-----------------------|---------------------|---|-----------------|-------------|------------|--------|
| 8807888  | 007420039; [REDACTED] | O.Reg.169/03(mg/L)  | North Kent - Groundwater Samples              | Colour          | Apparent CU | 5          | 67     |
| 8807888  | 007420039; [REDACTED] | O.Reg.169/03(mg/L)  | North Kent - Groundwater Samples              | Iron            | mg/L        | 0.3        | 0.733  |
| 8807888  | 007420039; [REDACTED] | O.Reg.169/03(mg/L)  | North Kent - Groundwater Samples              | Sodium          | mg/L        | 20 (200)   | 116    |
| 8807888  | 007420039; [REDACTED] | O.Reg.169/03(mg/L)  | North Kent - Groundwater Samples              | Turbidity       | NTU         | 5          | 10.9   |
| 8807888  | 007420039; [REDACTED] | SDWA - Microbiology | North Kent - Microbiological Analysis (water) | Total Coliforms | CFU/100mL   | 0          | 90     |



## Quality Assurance

CLIENT NAME: AECOM CANADA LTD

PROJECT: 60343599

SAMPLING SITE:

AGAT WORK ORDER: 17T270567

ATTENTION TO: Jason Murchison

SAMPLED BY:

### Microbiology Analysis

| RPT Date: Oct 17, 2017 |       |           | DUPLICATE |        |     | Method Blank | REFERENCE MATERIAL |                   | METHOD BLANK SPIKE |          | MATRIX SPIKE      |       |
|------------------------|-------|-----------|-----------|--------|-----|--------------|--------------------|-------------------|--------------------|----------|-------------------|-------|
| PARAMETER              | Batch | Sample Id | Dup #1    | Dup #2 | RPD |              | Measured Value     | Acceptable Limits |                    | Recovery | Acceptable Limits |       |
|                        |       |           |           |        |     |              |                    | Lower             | Upper              |          | Lower             | Upper |

North Kent - Microbiological Analysis (water)

|                  |         |         |    |    |       |     |
|------------------|---------|---------|----|----|-------|-----|
| Escherichia coli | 8807888 | 8807888 | ND | ND | NA    | < 1 |
| Total Coliforms  | 8807888 | 8807888 | 90 | 81 | 10.5% | < 1 |

Comments: ND – Not detected; NA - % RPD Not Applicable

Certified By:

*Divine Basily*



## Quality Assurance

CLIENT NAME: AECOM CANADA LTD

PROJECT: 60343599

SAMPLING SITE:

AGAT WORK ORDER: 17T270567

ATTENTION TO: Jason Murchison

SAMPLED BY:

| Water Analysis                   |         |           |           |        |       |              |                    |                   |       |                    |                   |       |              |                   |       |
|----------------------------------|---------|-----------|-----------|--------|-------|--------------|--------------------|-------------------|-------|--------------------|-------------------|-------|--------------|-------------------|-------|
| RPT Date: Oct 17, 2017           |         |           | DUPLICATE |        |       | Method Blank | REFERENCE MATERIAL |                   |       | METHOD BLANK SPIKE |                   |       | MATRIX SPIKE |                   |       |
| PARAMETER                        | Batch   | Sample Id | Dup #1    | Dup #2 | RPD   |              | Measured Value     | Acceptable Limits |       | Recovery           | Acceptable Limits |       | Recovery     | Acceptable Limits |       |
|                                  |         |           |           |        |       |              |                    | Lower             | Upper |                    | Lower             | Upper |              | Lower             | Upper |
| North Kent - Groundwater Samples |         |           |           |        |       |              |                    |                   |       |                    |                   |       |              |                   |       |
| Electrical Conductivity          | 8807179 |           | 1250      | 1260   | 0.8%  | < 2          | 102%               | 80%               | 120%  | NA                 |                   |       | NA           |                   |       |
| pH                               | 8807179 |           | 8.35      | 8.21   | 1.7%  | NA           | 99%                | 90%               | 110%  | NA                 |                   |       | NA           |                   |       |
| Total Dissolved Solids           | 8807888 | 8807888   | 318       | 318    | 0.0%  | < 20         | 100%               | 80%               | 120%  | NA                 |                   |       | NA           |                   |       |
| Total Suspended Solids           | 8807179 |           | <10       | <10    | NA    | < 10         | 102%               | 80%               | 120%  | NA                 |                   |       | NA           |                   |       |
| Alkalinity (as CaCO3)            | 8807179 |           | 402       | 403    | 0.2%  | < 5          | 100%               | 80%               | 120%  | NA                 |                   |       | NA           |                   |       |
| Fluoride                         | 8790200 |           | 0.41      | 0.43   | 4.8%  | < 0.05       | 96%                | 90%               | 110%  | 102%               | 90%               | 110%  | 111%         | 80%               | 120%  |
| Chloride                         | 8790200 |           | 10.4      | 9.99   | 4.0%  | < 0.10       | 91%                | 90%               | 110%  | 109%               | 90%               | 110%  | 109%         | 80%               | 120%  |
| Nitrate as N                     | 8790200 |           | <0.05     | <0.05  | NA    | < 0.05       | 90%                | 90%               | 110%  | 100%               | 90%               | 110%  | 105%         | 80%               | 120%  |
| Nitrite as N                     | 8790200 |           | <0.05     | <0.05  | NA    | < 0.05       | NA                 | 90%               | 110%  | 97%                | 90%               | 110%  | 96%          | 80%               | 120%  |
| Bromide                          | 8790200 |           | <0.05     | <0.05  | NA    | < 0.05       | 104%               | 90%               | 110%  | 107%               | 90%               | 110%  | 89%          | 80%               | 120%  |
| Sulphate                         | 8790200 |           | 113       | 112    | 0.9%  | < 0.10       | 103%               | 90%               | 110%  | 106%               | 90%               | 110%  | 95%          | 80%               | 120%  |
| Ammonia as N                     | 8807888 | 8807888   | 0.69      | 0.71   | 2.9%  | < 0.02       | 105%               | 90%               | 110%  | 95%                | 90%               | 110%  | 95%          | 80%               | 120%  |
| Dissolved Organic Carbon         | 8807179 |           | 2.7       | 2.6    | 3.8%  | < 0.5        | 103%               | 90%               | 110%  | 106%               | 90%               | 110%  | 99%          | 80%               | 120%  |
| Colour                           | 8807179 |           | 33        | 33     | 0.0%  | < 5          | 107%               | 90%               | 110%  | NA                 |                   |       | NA           |                   |       |
| Turbidity                        | 8807134 |           | 3.6       | 3.7    | 2.7%  | < 0.5        | 100%               | 90%               | 110%  | NA                 |                   |       | NA           |                   |       |
| Calcium                          | 8807888 | 8807888   | 9.44      | 9.44   | 0.0%  | < 0.05       | 95%                | 90%               | 110%  | 95%                | 90%               | 110%  | 94%          | 70%               | 130%  |
| Magnesium                        | 8807888 | 8807888   | 3.32      | 3.36   | 1.2%  | < 0.05       | 97%                | 90%               | 110%  | 97%                | 90%               | 110%  | 97%          | 70%               | 130%  |
| Sodium                           | 8807888 | 8807888   | 116       | 116    | 0.0%  | < 0.05       | 101%               | 90%               | 110%  | 100%               | 90%               | 110%  | 98%          | 70%               | 130%  |
| Potassium                        | 8807888 | 8807888   | 1.37      | 1.37   | 0.0%  | < 0.05       | 100%               | 90%               | 110%  | 99%                | 90%               | 110%  | 98%          | 70%               | 130%  |
| Iron                             | 8810249 |           | 0.289     | 0.259  | 10.9% | < 0.010      | 94%                | 90%               | 110%  | 93%                | 90%               | 110%  | 82%          | 70%               | 130%  |
| Manganese                        | 8810249 |           | 0.069     | 0.065  | 6.0%  | < 0.002      | 96%                | 90%               | 110%  | 91%                | 90%               | 110%  | 90%          | 70%               | 130%  |

Comments: NA signifies Not Applicable.

Duplicate Qualifier: As the measured result approaches the RL, the uncertainty associated with the value increases dramatically, thus duplicate acceptance limits apply only where the average of the two duplicates is greater than five times the RL.

Certified By:

*Iris Veraestegui*



## Method Summary

CLIENT NAME: AECOM CANADA LTD

PROJECT: 60343599

SAMPLING SITE:

AGAT WORK ORDER: 17T270567

ATTENTION TO: Jason Murchison

SAMPLED BY:

| PARAMETER                              | AGAT S.O.P   | LITERATURE REFERENCE                   | ANALYTICAL TECHNIQUE     |
|--|--------------|--|--------------------------|
| Microbiology Analysis                  |              |  |                          |
| Escherichia coli                       | MIC-93-7010  | EPA 1604                               | Membrane Filtration      |
| Total Coliforms                        | MIC-93-7010  | EPA 1604                               | Membrane Filtration      |
| Water Analysis                         |              |  |                          |
| Electrical Conductivity                | INOR-93-6000 | SM 2510 B                              | PC TITRATE               |
| pH                                     | INOR-93-6000 | SM 4500-H+ B                           | PC TITRATE               |
| Total Hardness (as CaCO <sub>3</sub> ) | MET-93-6105  | EPA SW-846 6010C & 200.7               | ICP/OES                  |
| Total Dissolved Solids                 | INOR-93-6028 | SM 2540 C                              | BALANCE                  |
| Total Suspended Solids                 | INOR-93-6028 | SM 2540 D                              | BALANCE                  |
| Alkalinity (as CaCO <sub>3</sub> )     | INOR-93-6000 | SM 2320 B                              | PC TITRATE               |
| Fluoride                               | INOR-93-6004 | SM 4110 B                              | ION CHROMATOGRAPH        |
| Chloride                               | INOR-93-6004 | SM 4110 B                              | ION CHROMATOGRAPH        |
| Nitrate as N                           | INOR-93-6004 | SM 4110 B                              | ION CHROMATOGRAPH        |
| Nitrite as N                           | INOR-93-6004 | SM 4110 B                              | ION CHROMATOGRAPH        |
| Bromide                                | INOR-93-6004 | SM 4110 B                              | ION CHROMATOGRAPH        |
| Sulphate                               | INOR-93-6004 | SM 4110 B                              | ION CHROMATOGRAPH        |
| Ammonia as N                           | INOR-93-6002 | AMM-002-A & SM 4500 NH <sub>3</sub> -G | DISCRETE ANALYZER        |
| Dissolved Organic Carbon               | INOR-93-6049 | EPA 415.1 & SM 5310 B                  | SHIMADZU CARBON ANALYZER |
| Colour                                 | INOR-93-6046 | SM 2120 C                              | SPECTROPHOTOMETER        |
| Turbidity                              | INOR-93-6044 | SM 2130 B                              | NEPHELOMETER             |
| Calcium                                | MET-93-6105  | EPA SW-846 6010C & 200.7               | ICP/OES                  |
| Magnesium                              | MET-93-6105  | EPA SW-846 6010C & 200.7               | ICP/OES                  |
| Sodium                                 | MET-93-6105  | EPA SW-846 6010C & 200.7               | ICP/OES                  |
| Potassium                              | MET-93-6105  | EPA SW-846 6010C & 200.7               | ICP/OES                  |
| Iron                                   | MET-93-6103  | EPA SW-846 6020A & 200.8               | ICP-MS                   |
| Manganese                              | MET-93-6103  | EPA SW-846 6020A & 200.8               | ICP-MS                   |



**AECOM**